# **Attachment A**

**Recommended Conditions of Consent** 

# **GENERAL CONDITIONS**

# (1) APPROVED DEVELOPMENT

(a) Development must be in accordance with Development Application No. D/2023/852 dated 25 September 2023 and the following drawings prepared by TKD Architects:

Drawing Number	Drawing Name	Date
AR DA 2001 Rev B	Ground Level Existing/ Demolition Plan	16/10/2023
AR DA 2002 Rev A	Level 1 Existing/ Demolition Plan	19/04/2023
AR DA 2003 Rev A	Level 2 Existing/ Demolition Plan	19/04/2023
AR DA 2004 Rev A	Level 3 Existing/ Demolition Plan	19/04/2023
AR DA 2005 Rev A	Roof Level Existing/ Demolition Plan	19/04/2023
AR DA 2031 Rev A	Ground Level Existing/ Demolition RCP	07/02/2024
AR DA 2032 Rev A	Level 1 Existing/ Demolition RCP	07/02/2024
AR DA 2033 Rev A	Level 2 Existing/ Demolition RCP	07/02/2024
AR DA 2050 Rev A	North Elevation – Existing/ Demolition	07/02/2024
AR DA 2051 Rev A	West Elevation – Existing/ Demolition	19/04/2023
AR DA 2052 Rev A	South Elevation – Existing/ Demolition	19/04/2023
AR DA 2053 Rev A	East Elevation – Existing/ Demolition	19/04/2023
AR DA 2054 Rev A	Existing/ Demolition Section 1	19/04/2023
AR DA 2055 Rev A	Existing/ Demolition Section 2	19/04/2023
AR DA 2101 Rev B	Proposed Ground Floor Plan	07/02/2024
AR DA 2102 Rev B	Proposed Level 1 Floor Plan	07/02/2024
AR DA 2103 Rev B	Proposed Level 2 Floor Plan	07/02/2024
AR DA 2104 Rev B	Proposed Level 3 Floor Plan	07/02/2024
AR DA 2105 Rev B	Proposed Level 4 Floor Plan	07/02/2024
AR DA 2106 Rev B	Proposed Roof Floor Plan	07/02/2024

Drawing Number	Drawing Name	Date
AR DA 3011 Rev A	West Elevation – Proposed	19/04/2023
AR DA 3012 Rev B	South Elevation – Proposed	07/02/2024
AR DA 3013 Rev A	East Elevation – Proposed	19/04/2023
AR DA 3014 Rev A	North Elevation – Proposed	07/02/2024
AR DA 3111 Rev B	Section 1 – Proposed	07/02/2024
AR DA 3112 Rev B	Section A – Proposed	07/02/2024
AR DA 4301 Rev A	Sign Details	19/04/2023
AR DA 4302 Rev B	Sliding Screen Details	19/03/2024
AR DA 4303 Rev A	Partition Details	07/02/2024
AR DA 9101 Rev C	Materials & Finishes	19/03/2024

and the following landscape drawings prepared by Context:

Drawing Number	Drawing Name	Date
- Rev A	Landscape Plans	7/02/2024
- Rev A	Indicative Landscape Section	7/02/2024
- Rev A	Indicative Planting Species	7/02/2024
- Rev A	Indicative Planting & Material Palette	7/02/2024

and as amended by the conditions of this consent.

(b) In the event of any inconsistency between the approved plans and supplementary documentation, the drawings will prevail.

# Reason

To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

# (2) APPROVED DESIGN ROOF - TOP PLANT

All roof-top plant and associated equipment must be located within the approved building envelope.

#### Reason

To ensure the constructed development complies with the approved height.

# (3) USE - SEPARATE DA REQUIRED

No consent is granted or implied for the fit out of the Level 3 and Level 4 commercial office tenancies.

A development consent or Complying Development Certificate (as appropriate) is required to be obtained for the fit out and use of the Level 3 and Level 4 commercial office tenancies prior to that fit out or use commencing.

#### Reason

To require separate consent to be obtained for a use.

# (4) MATERIALS FOR MAKING GOOD

New materials for making good and repairs, are to match the existing in terms of colours, finishes, sizes, profile and properties.

#### Reason

To ensure appropriate materials and finishes are used.

#### (5) ERECTION OF SIGN

The projecting wall sign is to be erected in a secure manner to ensure safety and its installation is not to involve measures that would cause irreversible damage to the building.

#### Reason

To ensure signage installed does not cause irreversible damage to the building.

#### (6) SIGNAGE GENERAL REQUIREMENTS

The design of the approved signage must comply with the following:-

- (a) The signage is not to contain highly reflective materials, colours and finishes.
- (b) The signage is not to incorporate sound, vibration, odour and other emissions.

#### Reason

To ensure signage is designed in accordance with Council's DCP.

#### (7) SIGN ILLUMINATION

- (a) At no time is the intensity, period of intermittency and hours of illumination of the sign to cause objectionable glare or injury to the amenity of the neighbourhood and as such must be designed, installed and used in accordance with the latest edition of AS/NZS 4828.
- (b) The sign must not flash. Signs with flashing, chasing, pulsating or flickering lights are not permitted.

- (c) The maximum night time luminance of any sign is not to exceed 300 cd/sqm.
- (d) Signage is only permitted to be illuminated between 5:30pm and 10:30pm Monday to Sunday.
- (e) Upward facing light sources onto the signage is not permitted.

To ensure signage illumination is designed in accordance with the Australian Standards and Council's DCP.

# (8) SIGNS - SEPARATE DA REQUIRED

A separate development application for any proposed signs additional to those approved as part of this consent (other than exempt or complying signs) must be submitted to and approved by Council prior to the erection or display of any such signs.

# Reason

To require separate consent to be obtained for any additional signs.

# (9) SIGNS/GOODS IN THE PUBLIC WAY

No signs or goods are to be placed on the footway or roadway adjacent to the property.

#### Reason

To ensure the public domain is kept free from physical obstructions.

# (10) ASSOCIATED ROADWAY COSTS

All costs associated with the construction of any new road works including kerb and gutter, road pavement, drainage system and footway shall be borne by the developer. The new road works must be designed and constructed in accordance with the City's "Sydney Streets Technical Specification" including amendments and "Sydney Streets Design Code".

#### Reason

To ensure all roadway works are designed and constructed in accordance with Council requirements.

# (11) COST OF SIGNPOSTING

All costs associated with signposting for any kerbside parking restrictions and traffic management measures associated with the development shall be borne by the developer.

#### Reason

To ensure all associated roadway works costs are borne by the developer.

# (12) WASTE AND RECYCLING MANAGEMENT - GENERAL

The proposal must comply with the relevant provisions of Council's *Guidelines for Waste Management in New Developments 2018* which requires facilities to promote the efficient storage, separation, collection and handling of waste to maximise resources recovery.

# Reason

To ensure that waste and recycling is appropriately managed.

# (13) ENCROACHMENTS – NEIGHBOURING PROPERTIES

No portion of the proposed structure shall encroach onto the adjoining properties.

#### Reason

To protect neighbouring properties.

# (14) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

# Reason

To protect the public way.

# **BUILDING WORK** BEFORE ISSUE OF A CONSTRUCTION CERTIFICATE

# (15) AFFORDABLE HOUSING CONTRIBUTION – RESIDUAL LAND OR CENTRAL SYDNEY – PAYMENT IN LIEU OF FLOOR SPACE CONTRIBUTION – PRIOR TO CONSTRUCTION CERTIFICATE

- (a) In accordance with the City of Sydney Affordable Housing Program and prior to the issue of a Construction Certificate, the applicant must provide evidence that a monetary contribution towards the provision of affordable housing has been paid to the City of Sydney Council.
- (b) The contribution is \$318,075.28 (indexed at 19/04/2024). This is calculated by establishing the sum of the equivalent monetary contribution \$11,176.22 multiplied by 1% of the total floor area for non-residential development (2,846.00 sqm).
- (c) If the contribution is paid after the indexation period in which the consent is granted, being March 2024 to February 2025, the above contribution will be adjusted according to the Sydney LGA median strata dwelling price ('MDP') using the following formula.
- (d) Contribution payable at Time of Payment = C x MDP2 / MDP1, where:
  - C is the original total contribution amount payable to the City of Sydney as shown above;
  - (ii) MDP2 is the Median Strata Dwelling Price in Sydney LGA taken from the most recent NSW Government Rent and Sales Report at the time of indexation of the equivalent monetary contribution rate; and
  - (iii) MDP1 is the Median Strata Dwelling Price in Sydney LGA taken from the NSW Government Rent and Sales Report used to establish the current equivalent monetary contribution rate, being March 2024 to February 2025.

Contact Council's Planning Assessment Unit at planningsystemsadmin@cityofsydney.nsw.gov.au for written confirmation of the amount payable, with indexation as necessary, prior to payment.

# Reason

To ensure development contributions are paid to contribute to the provision of essential affordable rental housing infrastructure.

# (16) SECTION 7.11 CONTRIBUTIONS PAYABLE - CONTRIBUTION TOWARDS PUBLIC AMENITIES – CITY OF SYDNEY DEVELOPMENT CONTRIBUTIONS PLAN 2015 – EAST PRECINCT

Council has identified the development will increase demand for public amenities and facilities. Pursuant to Section 7.11 of the Environmental Planning and Assessment Act, 1979 (as amended), and the City of Sydney Development Contributions Plan 2015 the following monetary contributions are required towards the cost of public amenities.

Contribution Category	<u>Amount</u>
Open Space	\$46,019.85
Community Facilities	\$43,361.93
Traffic and Transport	\$7,214.33
Stormwater Drainage	\$0.00
Total	\$96,596.11

The City of Sydney will index the above contribution for inflation at the time of payment using the following formula.

Cpayment	= Cconsent x (CPIpayment ÷ CPIconsent)
Where:	
Cpayment	= Is the contribution at time of payment;
Cconsent	= Is the contribution at the time of consent, as shown above;
CPIpayment	Is the Consumer Price Index (All Groups Index) for Sydney published by the Australian Bureau of Statistics that applies at the time of payment; and
CPI1consent	<ul> <li>Is the Consumer Price Index (All Groups Index) for Sydney at the date the contribution amount above was calculated being – 136.4 for the December 2023 quarter.</li> </ul>

The contribution must be paid prior to the issue of any Construction Certificate in relation to this development.

Please contact Council's Planning Administration staff at planningsystemsadmin@cityofsydney.nsw.gov.au to request a letter confirming the indexed contribution amount payable.

Once the letter confirming the indexed contribution is obtained, payment may be made at any of the City's Neighbourhood Service Centres or the One Stop Shop at Town Hall House. Acceptable payment methods are EFTPOS (debit card only), cash (up to 10K only), Credit Card (up to 50K only) or a bank cheque made payable to the City of Sydney. Personal or company cheques will not be accepted.

# Reason

To ensure development contributions are paid to address the increased demand for public amenities and services resulting from the approved development.

# (17) COMPLIANCE WITH THE ACOUSTIC REPORT PRIOR TO CONSTRUCTION AND OR OCCUPATION CERTIFICATES

- (a) All relevant performance parameters (including but not limited to requirements, engineering assumptions and recommendations) in the DA Acoustic Report prepared by Resonate, dated 16 March 2023, ref S210928RP1 Revision A, titled Belvoir Street Theatre Warehouse Renewal, Environmental Noise Assessment Council Ref 2023/553875 must be implemented in the development prior to the commencement of its use.
- (b) Prior to the issue of any relevant Construction Certificate, the final construction drawings and final construction methodology must be assessed and reported to be in accordance with the requirements of the DA Acoustic Report in (a) above, with reference to relevant documentation. This must be done by a Suitably Qualified Acoustic Consultant\* (see definition below). This work will be to the satisfaction of the Registered Certifier.
- (c) Prior to the issue of any Occupation Certificate, a Suitably Qualified Acoustic Consultant\* is to provide a written Acoustic Verification Report to the satisfaction of the Principal Certifier that the development complies with the requirements set out in the Report and in (a) and (b) above.

*Note:* Suitably Qualified Acoustic Consultant means a consultant who possesses the qualifications to join the Australian Acoustical Society, Institution of Engineers Australia (grade of member) or the Association of Australasian Acoustical Consultants (grade of member firm).

(d) All physical aspects of the building's structure installed in order to meet performance parameters in accordance with this condition must be maintained at all times.

# Reason

To ensure all parties are aware of the supporting documentation that applies to the development.

# (18) BICYCLE PARKING AND END OF TRIP FACILITIES

(a) The minimum number of bicycle parking spaces and end of trip facilities to be provided within the site boundary for the development must comply with the table below.

Bicycle Parking Type	Number	Requirements
Staff/customer of commercial offices	14	Spaces must be Class 2 bicycle facilities
Staff of creative industry use (Belvoir Theatre Company)	1	Spaces must be Class 2 bicycle facilities
End of Trip Facility Type	Number	
Showers with change area	2	
Personal lockers	15	

All bicycle parking spaces and end of trip facility must be provided on private land. The public domain cannot be used to satisfy this condition.

# Notes:

- (i) If a basement storage area on title that is large enough to store a bike and is no smaller than a class 1 bike locker this can be counted as a space.
- (b) The layout, design and security of bicycle facilities must comply with the minimum requirements of Australian Standard AS 2890.3 Parking Facilities Part 3: Bicycle Parking Facilities. The details must be submitted to and approved by the Registered Certifier confirming prior to and form part of the Construction Certificate being issued.

#### Reason

To ensure the allocation of bicycle parking onsite that is in accordance with Australian Standards and the Council's DCP.

# (19) CONSTRUCTION TRAFFIC MANAGEMENT PLAN

- (a) A Construction Traffic Management Plan must be submitted to and approved by Council prior to a Construction Certificate being issued.
- (b) The approved plan must be complied with during any demolition and/or construction work.

# Reason

To ensure that the impacts of construction traffic is appropriately managed.

# (20) ENERGY EFFICIENCY OF BUILDINGS

The design of the building and its services must achieve a Base Building National Australian Built Environment Rating System (NABERS) Energy Commitment Agreement of 5 Stars as per the Department of Planning, Industry and Environment (DPIE). This is to be demonstrated by:

(a) Entering into a Commitment Agreement with DPIE, to deliver this star rating for the base building;

The applicant must provide a copy of the signed Commitment Agreement contract with their Construction Certificate application; and

(b) Providing a copy of the independent energy assessment report to NABERS administration and submitting the same report with the Construction Certificate application. This report must be based on the same design documents as that submitted with the Construction Certificate.

Note: Definitions referred to above are as follows:

- (i) Commitment Agreement means an agreement that is set out in accordance with DPIE. The NABERS Commitment Agreement, which is signed between DPIE and the applicant/building owner/building manager, to design, build and commission the premises to achieve an agreed star rating.
- (ii) Star rating refers to the benchmarking system applied by DPIE for measuring the energy efficiency of a building and known as NABERS the National Australian Built Environment Rating System.
- (iii) Base Building means central services and common areas of a building, as defined under NABERS.

#### Reason

To ensure the building is designed to meet an appropriate energy efficiency standard.

#### (21) INSTALLATION OF DUAL-FLUSH TOILETS

All toilets installed within the development must be of water efficient dual-flush or other water-saving capacity with at least a 4-star rating under the Water Efficiency and Labelling Scheme (WELS). The details must be submitted for the approval of the Registered Certifier, prior to a Construction Certificate being issued.

## Reason

To ensure the provision of water efficient toilets.

## (22) INSTALLATION OF WATER EFFICIENT URINALS

New urinal suites, urinals and urinal flushing control mechanisms must use waterless technology. Where it is submitted that this is not feasible, it must be demonstrated that products have been selected with at least a 4-star rating under the Water Efficiency and Labelling Scheme (WELS). Systems must include "smart controls" to reduce unnecessary flushing. Continuous flushing systems are not approved. Details are to be submitted to and approved by the Registered Certifier, prior to a Construction Certificate being issued.

#### Reason

To ensure the provision of water efficient urinals.

# (23) INSTALLATION OF WATER EFFICIENT TAPS

All taps and shower heads installed must be water efficient with at least a 4-star rating under the Water Efficiency and Labelling Scheme (WELS). The details are to be submitted for the approval of the Principal Certifier, prior to any Occupation Certificate being issued.

# Reason

To ensure the provision of water efficient taps.

# (24) INTERNAL LIGHTING SYSTEM

The internal lighting system for the commercial office spaces must provide for the efficient use of energy including the use of energy efficient light fittings, zoned lighting and controls and sensors to ensure automatic switch off during non-working hours. LED lighting technology (or other technology with an improved lighting power density – watts per square metre) must be implemented. Details of the internal lighting system must be submitted to and approved by the Registered Certifier prior to a Construction Certificate being issued.

#### Reason

To ensure the provision of energy efficient lighting.

#### (25) DESIGN FOR ENVIRONMENTAL PERFORMANCE

- (a) Prior to the issue of any Construction Certificate, the Registered Certifier must be satisfied that those matters listed in the following sections of the approved Design for Environmental Performance report prepared by Alex Krickx dated 15 September 2023 (Council Ref: 2023/553862) are incorporated into the relevant construction plans and accompanying documentation:
  - (i) Section 4 Energy Efficiency and Greenhouse Gas Abatement
  - (ii) Section 5 Passive Design for Thermal Performance Building Envelope Design
  - (iii) Section 6 On site Renewable Energy Generation and Storage
  - (iv) Section 7 Design for Resilience to Climate Change

- (v) Section 8 Designing for mains potable water savings and water efficiency
- (vi) Section 9 Storm water quality
- (b) Changes to any commitments as listed in the approved Design for Environmental Performance report must be submitted to and approved by Council's Area Planning Manager or Coordinator prior to the issue of any relevant Construction Certificate.

To ensure the environmental performance of the development.

# (26) PUBLIC DOMAIN DAMAGE BOND

- (a) A Public Domain Damage Deposit calculated on the basis of 85 square metres of asphalt site frontage must be lodged with Council in accordance with the City of Sydney's adopted Schedule of Fees and Charges. The bond must be provided as security for repairing any damage to the public domain in the vicinity of the site.
- (b) The City's Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The Bond must be lodged with the City prior to an approval for demolition being granted or any Construction Certificate being issued, whichever is earlier.
- (c) The bond in this condition will be released in full when the Public Domain Works Security Bond is lodged with the City.

# Reason

To allow for the appropriate management and rectification of damage to the public domain.

# (27) PROTECTION OF STONE KERBS

- (a) The existing stone kerbs on the Elizabeth Street and Belvoir Street frontages of the site are to be retained and properly protected during demolition, excavation and construction works.
- (b) To avoid damage to stone kerbs during excavation and construction works for the development, temporary removal and storage of the stone kerbs may be approved by Council. Removed, serviceable stone kerbs (i.e. those that are in good condition as agreed by Council officers) must be reinstalled in accordance with the City of Sydney's standard details and specifications after the construction works have been completed. A temporary concrete kerb will need to be constructed to retain the footpath until the stone kerbs can be reinstalled.
- (c) Note the following:
  - (i) all costs associated with the works are to be borne by the developer.

- (ii) Damaged kerbs are to be replaced to match existing to Council's satisfaction or as otherwise advised by Council officers.
- (iii) Where new vehicle crossings or temporary crossings are to be constructed to access the property, the affected kerb stones should be salvaged and reused wherever possible.
- (iv) All new driveway laybacks and kerbs are to be constructed with stone kerbs to match existing stones or as specified by City officers.
- (v) Council approval is required before kerbs are removed.
- (vi) Council approval is required prior to the cutting of existing stone kerbs for stormwater kerb outlets.
- (vii) Stone kerbs and gutters may be bonded in accordance with the City of Sydney's adopted Schedule of Fees and Charges. If so, this will be included with the Public Domain Damage Bond.

To ensure the protection of stone kerbs.

#### (28) PROTRUDING WINDOW CASINGS

The Protruding Window Casings which are proposed to be constructed above the public domain (including a public footway) must have separate approval(s) obtainable through the lodgement of an application under Section 68 of the Local Government Act 1993 and/or Section 138/139 of the Roads Act 1993 prior to any Construction Certificate for the building

Documentation must be submitted to the City's Construction and Building Certification Services Unit with the application demonstrating that the protruding window casings height complies with awning heights noted in Development Control Plan 2012. Plans are to include dimensions confirming the encroachment width and setback from the kerb. Any gutters are to be concealed from the public domain and plans are to confirm downpipes are located within or recessed into the ground floor frontage of the building.

#### Reason

To ensure that protruding window casings are designed in accordance with the DCP.

#### (29) SURVEY INFRASTRUCTURE – IDENTIFICATION AND RECOVERY

Under Section 24 of the Surveying and Spatial Information Act 2002, it is an offence to remove, damage, destroy, displace, obliterate or deface any survey mark unless authorised to do so by the Surveyor-General. Accordingly, the applicant must, where possible, ensure the preservation of existing survey infrastructure undisturbed and in its original state or else provide evidence of the Surveyor-General's authorisation to remove or replace marks.

Prior to the issue of any Construction Certificate, documentary evidence must be prepared by a Registered Surveyor and submitted to and approved by Council's Area Planning Manager / Coordinator. This evidence must include either:

- (a) A copy of any Surveyor-General's Approval for Survey Mark Removal granted by NSW Spatial Services for the subject site, including all documentation submitted as part of that application (for example the survey mark audit schedule, strategy plan and strategy report); or
- (b) A letter, signed by a current NSW Registered Land Surveyor and including his or her Board of Surveying and Spatial Information (BOSSI) identification number, stating that all investigations required under Surveyor-General's Direction No.11 have been made for the subject site and that no survey infrastructure will be affected by the proposal.

Council's Principal Surveyor may request further information and/or add conditions to any Surveyor-General's Approval at their discretion.

# Reason

To ensure the preservation of existing survey infrastructure.

# (30) PUBLIC DOMAIN LEVELS AND GRADIENTS - MAJOR

Prior to the issue of any Construction Certificate, a Public Domain Levels and Gradients submission for the building and site frontages must be submitted to and approved by the City's Public Domain Unit. The submission must be prepared in accordance with the City's *Public Domain Manual* and submitted with a completed Application for *Public Domain Levels and Gradients*. Information on how to complete the submission can be downloaded from the City's website at https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works.

Any requirements to comply with Disability Discrimination Act at the entrance to a building or publicly accessible space must be resolved inside the site boundary.

Note: Public Domain Levels and Gradient plans are to be included with the Public Domain Plan – Detailed Documentation for Construction condition submission.

#### Reason

To ensure public domain levels and gradients comply with Council's requirements.

# (31) PUBLIC DOMAIN LIGHTING UPGRADE

Prior to issue of any Construction Certificate for excavation, civil construction, drainage or building work (whichever is earlier), a concept Public Domain Lighting Upgrade Plan for pedestrian and street lighting in the public domain must be submitted to and approved by City's Public Domain Unit. The Lighting Plan must be prepared in accordance with the *Sydney Streets Technical Specifications* A5 and B8, *Sydney Lights Design Code* and *Public Domain Manual*. This information is available for download from the City's website at https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works.

The lighting upgrade plan must cover all adjacent street frontages, being Elizabeth Street and Belvoir Street and shall be designed to include the following requirements:

# Elizabeth Street (from Ausgrid pole #SY05243 to SY05244)

- Lighting must comply with requirements of AS1158 under Category V1 on the road and PP1 on the footpath (both sides).
- If required, supply and install COS light poles or extend Ausgrid street lighting network to achieve compliance.

# Belvoir Street (from Ausgrid pole #SY05313 to SY05316)

- Lighting must comply with requirements of AS1158 under Category PR3.
- If required, supply and install COS light poles or extend Ausgrid street lighting network to achieve compliance.

#### Notes:

- Lighting designs must be certified by a suitably qualified practicing lighting engineer and must consist of two parts: illumination design and electrical supply reticulation design. COS can only review electrical reticulation design once receiving final illumination designs.
- Lighting design submission requirements are specified in "Sydney Streets Technical Specifications A5: Street Lighting Design". E.g.:
  - Plans should show calculation points as per Australian Standards.
  - Calculation plot scale should not be smaller than 1:250 @ A1.
  - Provide a Calculation Summary table showing all relevant light technical parameters and compliance, including Maximum lux levels
  - Highlight all areas of non-compliance.
- If applicable, developers must submit site-specific structural footing designs certified by a practicing structural engineer for council review before footing construction of COS assets.

- If applicable, provide temporary lighting complying with COS public domain lighting specifications prior to removal of existing public lights if applicable.
- If applicable, undertake ASP works required to modify and remove redundant Ausgrid assets and carry out all electrical/civil works to ensure continuity of supply to the remainder of Ausgrid assets on the affected circuits.
- Proposals for Building exterior lighting, signage lighting, terrace lighting and lighting of landscape features are to be assessed under a separate DA.
- If applicable, under awning lighting must comply with the requirements of COS Awnings Policy using LED luminaires.
- All relevant engineering design plans (incl electrical and lighting), design certificates, As-Builts plans, WAE plans, and construction certificates must be submitted for COS review.
- All works shall comply with the requirements of all applicable standards and guidelines, including (but not limited to) AS1158, AS4282, and the City of Sydney's A5, B8 and Ausgrid NS119 documents.

Advice on site specific lighting requirements must be obtained from City's Public Domain Unit before proceeding with the preparation of any final lighting design proposals.

# Reason

To ensure pedestrian and street lighting in the public domain complies with Council's requirements.

# (32) DILAPIDATION REPORT - PUBLIC DOMAIN

Prior to an approval for demolition and preparatory works being granted or the issue of any Construction Certificate, whichever is earlier, a photographic recording of the public domain site frontages is to be prepared as described in the Public Domain Manual and submitted for approval by Council's Public Domain Unit. The City's *Public Domain Manual* is available for download from the City's website at <u>https://www.cityofsydney.nsw.gov.au/</u>

The submission is to include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

#### Reason

To establish and document the condition of the public domain for comparison as building work progresses and is completed.

# (33) WASTE AND RECYCLING MANAGEMENT - COMMERCIAL

The Waste and Recycling Management Plan accompanying this Development Application (prepared by Foresight Environmental, dated 17/03/2023) has been approved by this consent.

#### Reason

To ensure that waste and recycling is appropriately managed.

# (34) DILAPIDATION REPORT – MINOR

Subject to the receipt of permission of the affected landowner, dilapidation report/s of adjoining buildings are to be prepared by an appropriately qualified practising structural engineer and submitted for the approval of the Registered Certifier prior to the issue of a construction certification.

#### Reason

To ensure that dilapidation reports are prepared and to identify damage to for adjoining/nearby properties resulting from building work on the development site.

# (35) SALVAGE, REUSE AND RECYCLING OF TRADITIONAL BUILDING MATERIALS – MAJOR DEVELOPMENT

Stone, bricks, roof tiles joinery and decorative architectural elements to be demolished, which include stairs, windows and doors, must be salvaged and where possible reused on the project.

Salvaged building materials surplus to the project must either be stored on site for future reuse or transferred to an established second building material dealer for recycling.

Documentation of the salvage methodology must be submitted to and approved by Council's Urban Design and Heritage Manager / Area Planning Manager prior to the issue of a Construction Certificate.

# Reason

To ensure the salvaging and reuse of traditional building materials.

# **BEFORE BUILDING WORK COMMENCES**

# (36) HAZARDOUS MATERIALS SURVEY REQUIRED

A Hazardous Materials Survey Report must be prepared by a certified Occupational Hygienist (*Australia Institute of Occupational Hygienists*) and submitted to the satisfaction of Council's Area Coordinator Planning Assessments or Area Planning Manager prior to any demolition / refurbishment work commencing at the site. The report must identify and record the type, location and extent of any hazardous materials on the site and make recommendations as to their safe management and/or removal to ensure the site is made safe for demolition, construction and future use/occupation.

#### Reason

To ensure that hazardous materials on the site are identified and appropriately managed.

# (37) SITE SUPERVISION AND REPORTING

- (a) An arborist with minimum AQF Level 5 qualification in arboriculture must oversee various stages of work within the Tree Protection Zone of any tree listed for retention. The Arborist must certify compliance with each key milestone detailed below:
  - (i) The installation of tree protection measures prior to the commencement of any construction works;
  - During demolition of any ground surface materials (pavers, concrete, grass etc.) within the Tree Protection Zone (TPZ) of any tree to be retained;
  - (iii) During any excavation and trenching within the TPZ which has been approved by Council;
  - (vi) During any landscape works within the TPZ which has been approved by Council.
- (b) An Arboricultural Compliance Report which includes photographic evidence and provides details on the health and structure of tree/s must be submitted to and approved by Council's Area Planning Coordinator or Area Planning Manager at each hold point listed below:
  - (i) Certification that tree protection measures have been installed in accordance with these consent conditions;
  - (ii) Certification of compliance with each key milestone listed above within 48 hours of completion;
  - (iii) Details of any other works undertaken on any tree to be retained or any works within the TPZ which has been approved by Council.
- (c) A final compliance report must be submitted to and approved by Council's Area Planning Coordinator or Area Planning Manager prior to the issue of any Occupation Certificate.

To ensure the protection and ongoing health of trees on the site.

# (38) STREET TREE PRUNING

- (a) The consent from Council's Tree Management Officer must be obtained prior to the undertaking of any street tree pruning works including tree roots greater than 30mm diameter. Only minor pruning works will be approved by Council.
- (b) Any request to Council to prune any street tree to facilitate installation of scaffolding and hoarding shall include a Pruning Specification Report prepared by a qualified Arborist(minimum AQF Level 5). The report must include number of branches and orientation, branch diameter, percentage of canopy to be pruned/removed. A maximum of 10% pruning of any tree with a maximum branch diameter of 100mm will be permitted by Council.
- (c) Any pruning that has been approved by Council, must be carried out by a qualified Arborist (AQF3), and must be in accordance with AS4373 Australian Standards 'Pruning of Amenity Trees'.

# Reason

To ensure that approval is obtained for any pruning works to, or removal of, street trees and that such works are carried out in an appropriate manner.

# (39) PUBLIC DOMAIN WORK – CONSTRUCTION APPROVAL UNDER SECTION 138 ROADS ACT 1993

Prior to the construction of any public domain works, approval under Section 138 / 139 of the Roads Act 1993 must be issued by the City's Public Domain Unit.

# Reason

To ensure relevant approvals for public domain work are obtained.

# (40) PUBLIC DOMAIN WORKS SECURITY BOND

A Public Domain Works Security Bond will be required for the public domain works and for repairing damage that may be caused to the public domain in the vicinity of the site, in accordance with the City of Sydney's adopted fees and charges and the Public Domain Manual.

The City's Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The bond must be lodged with the City prior to an approval being issued for the approval of the Public Domain Plan.

The bond will be retained in full until all public domain works, including rectification of damage to the public domain, are completed to City's standards and approval and the required works-as-executed documentation are approved. On satisfying the above requirements, and the issue of the Public Domain Works Letter of Completion Operational Acceptance by the City, 90% of the bond will be released. The remaining 10% will be retained for the duration of the specified Defects Liability Period.

To ensure public domain works are completed and any damage to the public domain is rectified.

# (41) PUBLIC DOMAIN PLAN DETAILED DOCUMENTATION FOR CONSTRUCTION

A detailed public domain plan and all relevant documentation must be submitted to and approved by City's Public Domain Unit prior to the construction of any public domain works. This Plan must document all works required to ensure that the public domain upgrade work complies with the City's specifications and requirements, as outlined in documents such as City of Sydney's *Public Domain Manual, Sydney Streets Code, Sydney Street Tree Masterplan, Sydney Lights: Public Domain Design Code and Sydney Streets Technical Specification.* The documentation must be *checked, accurate, and comply with specified requirements.* Plans must be based on an accurate survey, to scale and fully coordinated across all disciplines and submissions. The supplied documentation must be for Construction issue and will be approved under Section 138 of the Roads Act.

The Public Domain Manual and all other relevant documents are available for download from Council's website at <u>https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works</u>.

The Public Domain Plan documentation must be submitted with an Application for Public Domain Plan Assessment and include the approved Public Domain Levels and Gradients documentation. If the proposed detailed design of the public domain requires changes to any previously approved levels, details must be submitted for approval with the public domain plan and additional fees may apply.

# Reason

To ensure the public domain complies with Council's requirements.

# (42) HOLD POINTS

Prior to an approval being issued for the construction of public domain and / or planning agreement works, including civil, drainage and subsurface works, a set of hold points will be provided by the City's Public Domain Unit in accordance with the City's Public Domain Manual and Sydney Streets Technical Specification. The list of hold point inspections will be included in the Public Domain works approval letter.

These hold point inspections must be adhered to during construction works. Prior to the issue of any Occupation Certificate, confirmation from the City's Public Domain Unit, that hold point inspections have been completed and works have been accepted by the City must be provided to the Principal Certifier.

#### Reason

To ensure hold points are adhered to during construction works.

# (43) PUBLIC DOMAIN LIGHTING RETICULATION

Prior to the issue of any relevant approval for the construction of public domain works, a detailed Public Domain Lighting Reticulation Plan for pedestrian and street lighting in the public domain in accordance with the approved concept Public Domain Lighting Plan must be submitted to and approved by the City's Public Domain Unit in accordance with the City's *Sydney Lights Design Code, Sydney Streets Code, Sydney Streets Technical Specification* and *Public Domain Manual.* 

The Public Domain Manual and all other relevant documents are available for download from Council's website at

https://www.cityofsydney.nsw.gov.au/development/public-domain-works/daassociated-works.

If applicable, this public domain lighting documentation must include pole footing locations and structural details, location and details of underground electrical reticulation including connections and conduits, pit cabling and certifications as described in the City's *Public Domain Manual*. The public domain lighting is to be superimposed on the public domain plan to show any conflicts between lighting and the proposed landscape design.

#### Reason

To ensure the public domain lighting documentation complies with Council requirements.

# DURING BUILDING WORK

# (44) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on-site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Team, prior to works proceeding.

The City of Sydney Code of Practice for Construction Hours/Noise 1992 allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and* Assessment Act 1979.

# Reason

To protect the amenity of the surrounding area.

# (45) NOTIFICATION OF EXCAVATION WORKS OR USE OF HIGH NOISE EMISSION APPLIANCES/PLANT

The immediately adjoining neighbours must be given a minimum of 48 hours notice that excavation, shoring or underpinning works or use of high noise emission appliances / plant are about to commence.

#### Reason

To protect the amenity of the surrounding area.

#### (46) ASBESTOS REMOVAL WORKS

(a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence must be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.
- (c) All work must be carried out in accordance with the Work Health and Safety Regulation 2017 and the NSW Government and SafeWork NSW document entitled How to manage and control asbestos in the work place: Code of Practice (Safework NSW) December 2011 and the City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.
- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 -1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.
- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).
- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.

 A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

#### Reason

To ensure that the handling and removal of asbestos from the site is appropriately managed.

# (47) NOTIFICATION – NEW CONTAMINATION EVIDENCE

Council's Area Planning Manager and the Principal Certifier must be notified of any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination.

#### Reason

To ensure that the site is appropriately remediated.

#### (48) IMPORTED FILL MATERIALS

All fill imported onto the site must be validated to ensure the imported fill is suitable for the proposed land use from a contamination perspective. Fill imported on to the site shall also be compatible with the existing soil characteristic for site drainage purposes.

The City may require details of appropriate validation of imported fill material to be submitted with any application for future development of the site. Hence all fill imported onto the site should be validated by either one or both of the following methods during remediation works:

- (a) Imported fill must be accompanied by documentation from the supplier which certifies that the material is not contaminated based upon analyses of the material for the known past history of the site where the material is obtained; and/or
- (b) Sampling and analysis of the fill material shall be conducted in accordance with NSW EPA (2022) Sampling Design Guidelines.

# Reason

To ensure that imported fill is not contaminated.

# (49) CLASSIFICATION OF WASTE

Prior to the exportation of waste (including fill or soil) from the site, the waste materials must be classified in accordance with the provisions of the Protection of the *Environment Operations Act 1997* and the *NSW EPA Waste Classification Guidelines, Part1: Classifying Waste (November 2014).* The classification of the material is essential to determine where the waste may be legally taken. The *Protection of the Environment Operations Act 1997* provides for the commission of an offence for both the waste owner and the transporters if the waste is taken to a place that cannot lawfully be used as a waste facility for a particular class of waste. For the transport and disposal of industrial, hazardous or Group A liquid waste advice should be sought from the EPA.

#### Reason

To ensure that waste from site is classified and disposed of appropriately.

# (50) DISCHARGE OF CONTAMINATED GROUNDWATER

Contaminated groundwater must not be discharged into the City's stormwater drainage system.

Options for the disposal of groundwater include disposal to sewer with prior approval from Sydney Water or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

#### Reason

To ensure that the discharge of ground water is appropriately managed.

# (51) STOCKPILES

- (a) No stockpiles of soil or other materials must be placed on footpaths or nature strips unless prior approval has been obtained from the City's Construction Regulation Team.
- (b) All stockpiles of soil or other materials must be placed away from drainage lines, gutters or stormwater pits or inlets.
- (c) All stockpiles of soil or other materials likely to generate dust or odours must be covered.
- (d) All stockpiles of contaminated soil must be stored in a secure area and be covered if remaining more than 24 hours.

#### Reason

To ensure that stockpiles of soil or other materials are appropriately managed.

#### (52) STREET TREE PROTECTION

All street trees located directly outside the site must be retained and protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites. All street trees must be protected during the construction works as follows:

- (a) Tree trunk and major branch protection must be undertaken prior to the commencement of any works (including demolition). The protection must be installed and certified by an arborist with a minimum AQF Level 5 qualification in arboriculture and must include:
  - (i) An adequate clearance, minimum 250mm, must be provided between the structure and tree branches, and trucks at all times.
  - (ii) Tree trunk/s and/or major branches, must be protected by wrapped thick underlay carpet or similar padding material to limit damage, and
  - (iii) Timber planks (50mm x 100mm or similar) must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals and must be fixed against the trunk with tie wire, or strapping. The thick underlay carpet or similar padding material and timber planks must not be fixed to the tree in any instance, or in any fashion.
  - (iv) Tree trunk and major branch protection is to remain in place for the duration of construction and development works and must be removed at the completion of the project.
- (b) Temporary signs, or any other items, shall not be fixed or attached to any street tree.
- (c) All hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree pits. Supporting columns must not be placed on any tree roots that are exposed.
- (d) Young street trees must be protected by installing three (3) wooden stakes around the edge of the tree pits or a minimum of 1 metre from the base of the trunk. Hessian must be wrapped around the stakes. If existing stakes or a metal tree guard are already in place, these suffice as tree protection.
- (e) Materials or goods, including site sheds, must not be stored or placed:
  - (i) around or under the tree canopy; or
  - (ii) within two (2) metres of tree trunks or branches of any street trees.
- (f) Any excavation within any area known to or suspected of having tree roots greater than 30mm diameter must be undertaken by hand.
- (g) Any trenching works for services, hydraulics, drainage etc. must not be undertaken within six metres of the trunk of any street tree. Alternate installation methods for services such as directional boring/drilling or redirection of services must be employed where roots greater than 30mm diameter are encountered during installation of any services.
- (h) Existing sections of kerbs adjacent to any street tree must not be removed without approval from the Council's Tree Management Officer.

(i) Any damage sustained to street tree/s as a result of the erection of any construction activities (including demolition) must be immediately reported to the Council's Tree Management Officer on 9265 9333. Any damage to street trees as a result of any construction activities may result in prosecution under the Local Government Act 1993 and the Environmental Planning and Assessment Act 1979.

## Reason

To ensure the protection and ongoing health of the street trees.

# (53) LOADING AND UNLOADING DURING CONSTRUCTION

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site, where possible.
- (b) If, it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.
- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.
- (d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate application under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993 must be submitted to and approved by Council.

#### Reason

To protect the amenity of the public domain.

# (54) NO OBSTRUCTION OF PUBLIC WAY

Unless otherwise approved by Council, the public way must not be obstructed by any materials, vehicles, waste receptacles, skip-bins or the like. Non-compliance with this requirement may result in the issue of a notice by Council to stop all work on the site.

# Reason

To protect the amenity of the public domain.

# (55) USE OF MOBILE CRANES

The following requirements apply:

(a) Mobile cranes operating from the road must not be used as a method of demolishing or constructing a building.

- (b) For special operations including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes, permits must be obtained from Council for the use of a mobile crane. The permits must be obtained 48 hours beforehand for partial road closures which, in the opinion of Council will create minimal traffic disruptions and 4 weeks beforehand in the case of full road closures and partial road closures which, in the opinion of Council, will create significant traffic disruptions.
- (c) The use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of approved hours of construction can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

To ensure mobile cranes are used appropriately.

# (56) SURVEY

All footings, walls and floor slabs adjacent to a boundary must be set out by a registered surveyor. On commencement of brickwork or wall construction a survey and report, prepared by a Registered Surveyor, must be submitted to the Principal Certifier indicating the position of external walls in relation to the boundaries of the allotment. Any encroachments by the subject building over adjoining boundaries or roads must be removed prior to continuation of building construction work.

#### Reason

To ensure the development does not encroach onto neighbouring properties.

# (57) SURVEY CERTIFICATE AT COMPLETION

A Survey Certificate prepared by a Registered Surveyor must be submitted to the Principal Certifier at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

#### Reason

To ensure the development does not encroach onto neighbouring properties.

# (58) COVERING OF LOADS

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

#### Reason

To ensure loads are managed appropriately and do not impact local amenity.

# **BEFORE ISSUE OF AN OCCUPATION CERTIFICATE**

# (59) PUBLIC ART

Public art must be installed to the City's satisfaction prior to the issue of any Occupation Certificate.

- (a) The public artwork must be in accordance with the revised Preliminary Public Art Plan (210321\_P3806\_Belvoir Street Theatre Warehouse Renewal\_Preliminary Public Art Plan1.0), 2024/199375, by UAP dated March 2024, the Sydney DCP 2012, the Public Art Policy, and the Interim Guidelines: Public art in private developments.
- (b) A Detailed Public Art Plan with final details of the proposed public artwork must be submitted to and approved by Council's Are Planning Manager prior to issue of any Construction Certificate for above ground works.
- (c) Public artwork must be installed to the City's satisfaction, inspected and approved and the Final Public Art Report submitted and approved by Council's Area Planning Manager prior to the issue of any Occupation Certificate.

Note: Public Art must be reviewed and endorsed by the City's Public Art Team and/or the Public Art Advisory Panel prior to submission for Council approval. Further information is available online at <u>http://www.cityofsydney.nsw.gov.au/explore/arts-and-culture/public-art</u> Please contact the Public Art Team at <u>publicartreferrals@cityofsydney.nsw.gov.au</u> for further information.

# Reason

To ensure public art is installed to the City's satisfaction.

# (60) WASTE AND RECYCLING COLLECTION CONTRACT

Prior to any Occupation Certificate being issued, the building owner must ensure that there is a contract with a licensed contractor for the removal of **all waste**. Waste is to be stored and collected from within the curtilage of the site at all times.

# Reason

To ensure that waste and recycling is appropriately managed.

# (61) PUBLIC DOMAIN WORKS COMPLETION

The Public Domain works are to be constructed in accordance with the Public Domain Works Approval letter, stamped plans for Public Domain Levels and Gradients, Stormwater, Public Domain Lighting, the City's *Public Domain Manual,* Stormwater *Drainage Manual, Sydney Lights Design Code* and *Sydney Streets Technical Specification.* 

The public domain work must be inspected and a Public Domain Work Letter of Completion Operational Acceptance must be issued by Council's Public Domain Officer prior to the issue of any Occupation Certificate or before the commencement of use, whichever is earlier.

# Reason

To ensure the public domain works are completed in accordance with the approved documents and Council's requirements.

# (62) PUBLIC DOMAIN COMPLETION – WORK AS EXECUTED DOCUMENTATION

Prior to a Public Domain Works Letter of Completion Operational Acceptance being issued for public domain works, works-as-executed (As-Built) plans and documentation, must be submitted to and accepted by the City of Sydney for all public domain works, including where required Stormwater, Public Domain Lighting and road construction. These works must be certified by a suitably qualified, independent professional. Details of the documentation required for approval will be advised by the City's Public Domain Unit.

# Reason

To ensure Council receives works-as-executed documentation for public domain works.

# (63) SURVEY INFRASTRUCTURE – RESTORATION

- (a) Prior to any Occupation Certificate being issued for the development, documentary evidence of restoration must be prepared by a Registered Surveyor and submitted to and approved by Council's Area Planning Manager / Coordinator. This evidence must include:
  - Certification that all requirements requested under the Surveyor-General's Approval for Survey Mark Removal or by the City's Principal Surveyor under condition "Survey Infrastructure – Identification and Recovery" have been complied with;
  - (ii) Certification that all requirements requested under any Surveyor-General's Approval for Deferment of Survey Marks from condition "Survey Infrastructure – Pre Subdivision Certificate works" have been complied with and;
  - (iii) Time-stamped photographic records of all new survey infrastructure relating to the site clearly showing the mark itself and sufficient context to aid in identifying the mark on site.

#### Reason

To ensure all requirements for survey mark removal are complied with.

# (64) PHYSICAL MODELS

(a) Prior to the issue of any Occupation Certificate an accurate 1:500 scale model of the development as constructed must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the City Model in Town Hall House.

# Note:

- (i) The models must be constructed in accordance with the Model Specifications available online at <u>http://www.cityofsydney.nsw.gov.au/development/applicationguide/application-process/model-requirements</u> Council's modellers must be consulted prior to construction of the model.
- (ii) The models are to comply with all of the conditions of the Development Consent.
- (iii) The models must be amended to reflect any further modifications to the approval (under Section 4.55 of the *Environmental Planning and Assessment Act*) that affect the external appearance of the building.

# Reason

To ensure the provision of an appropriate physical model of the development.

# (65) SUBMISSION OF ELECTRONIC CAD MODELS PRIOR TO OCCUPATION CERTIFICATE

- (a) Prior to any Occupation Certificate being issued, an accurate 1:1 electronic CAD model of the completed development must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the electronic Visualisation City Model.
- (b) The data required to be submitted within the surveyed location must include and identify:
  - (i) building design above and below ground in accordance with the development consent;
  - (ii) all underground services and utilities, underground structures and basements, known archaeological structures and artefacts;
  - (iii) a current two points on the site boundary clearly marked to show their Northing and Easting MGA (Map Grid of Australia) coordinates, which must be based on Established Marks registered in the Department of Lands and Property Information's SCIMS Database with a Horizontal Position Equal to or better than Class C.

The data is to be submitted as a DGN or DWG file on a Compact Disc. All modelling is to be referenced to the Map Grid of Australia (MGA) spatially located in the Initial Data Extraction file.

(c) The electronic model must be constructed in accordance with the City's 3D CAD electronic model specification. The specification is available online at <a href="http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements">http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements</a> Council's Modelling staff should be consulted prior to creation of the model. The data is to comply with all of the conditions of the Development Consent.

# Reason

To ensure the provision of an appropriate electronic model of the development.

# (66) DISPOSAL OF SURPLUS SALVAGED MATERIALS

Salvaged traditional building materials surplus to the requirements of this project including structural timber, staircases, and joinery are to be sold to an established dealer in second-hand heritage building materials. Documentation of the salvage methodology must be submitted for the approval of Council prior to the commencement of demolition.

# Reason

To ensure the salvaging and reuse of traditional building materials.

# **OCCUPATION AND ONGOING USE**

# (67) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

# Reason

To ensure the site is authorised for occupation.

# (68) USE OF THE GROUND FLOOR REHEARSAL SPACE

- (a) The ground floor rehearsal space is not to be used for public performances.
- (b) The internal sliding screens to Elizabeth Street are to remain open when the rehearsal space is not in use.

# (69) NOISE - ENTERTAINMENT

- (a) The L<sub>Aeq, 15</sub> minute noise level from the use must not exceed the background noise level (L<sub>A90, 15</sub>minute) in any octave band (reference frequency 31.5 Hz to 8 kHz inclusive) by more than 5dB between 7.00am and 12.00 midnight when assessed at the boundary of any residential accommodation or tourist and visitor accommodation.
- (b) The L<sub>Aeq, 15 minute</sub> noise level from the use must not exceed the background noise level (L<sub>A90, 15 minute</sub>) in any octave band (reference frequency 31.5 Hz to 8 kHz inclusive) between 12.00 midnight and 7.00am when assessed at the boundary of any residential accommodation or tourist and visitor accommodation.
- (c) Notwithstanding (a) above, the L<sub>Aeq, 15 minute</sub> noise level from the use must not exceed the greater of the following levels between 7am and 12 midnight inside any habitable room of a residential accommodation or tourist and visitor accommodation, or at any time in an affected commercial premises:
  - (i) The existing internal L<sub>A90, 15 minute</sub> (from external sources excluding the use) in any octave band (reference frequency 31.5 Hz to 8 kHz inclusive). Or,
  - (ii) If the L<sub>Z90, 15 minute</sub> background level is below the hearing threshold curve (Tf - Table 1 of ISO 226 : 2003) in an above octave band, the lowest audible sound level (Lp) of the Tf curve in that octave band shall become that octave's L<sub>Zeq 15 minute</sub> noise criteria level.
- (d) Notwithstanding (b) above, the L<sub>A1 15 minute</sub> noise level from the use must not exceed the greater of the following sound pressure levels inside any habitable room between 12 midnight and 7am inside any habitable room of an affected residential accommodation or tourist and visitor accommodation:

- The existing internal L<sub>A90, 15 minute</sub> (from external sources excluding the use) minus 10 dB in any octave band (reference frequency 31.5 Hz to 8 kHz inclusive) inside a habitable room of an affected residential accommodation or tourist and visitor accommodation. Or,
- (ii) If the L<sub>Z90, 15 minute</sub> minus 10 dB level is below the hearing threshold curve (Tf Table 1 of ISO 226 : 2003) in an above octave band, the lowest audible sound level (Lp) of the Tf curve in that octave band shall become that octave's L<sub>Z1 15 minute</sub> noise criteria level.

Note:  $L_{eq}$ ,  $L_{01}$ , and  $L_{90}$ , metrics and 'A' (weightings) are as per the definitions in the standard AS1055-20148. 'Z' means unweighted noise. An internal  $L_{A90}$  level must be determined in the absence of noise emitted by the use and be sufficiently representative of the receiver in a low noise level quiet state. External  $L_{A90}$  levels for planning must be established as per the long-term methodology in Fact Sheet B of the NPfl unless otherwise agreed by the City's Area Planning Manager.

# Reason

To protect the acoustic amenity of surrounding properties.

# (70) NOISE – COMMERCIAL PLANT / INDUSTRIAL DEVELOPMENT

- (a) Noise from commercial plant and industrial development must not exceed a project amenity/intrusiveness noise level or maximum noise level in accordance with relevant requirements of the NSW EPA <u>Noise Policy for</u> <u>Industry 2017 (NPfl)</u> unless agreed to by the City's Area Planning Manager. Further:
  - (i) Background noise monitoring must be carried out in accordance with the long-term methodology in *Fact Sheet B* of the NPfI unless otherwise agreed by the City's Area Planning Manager.
  - (ii) Commercial plant is limited to heating, ventilation, air conditioning, refrigeration and energy generation equipment.
- (b) An L<sub>Aeq,15 minute</sub> (noise level) emitted from the development must not exceed the L<sub>A90, 15 minute</sub> (background noise level) by more than 3dB when assessed inside any habitable room of any affected residence or noise sensitive commercial premises at any time. Further:
  - (i) The noise level and the background noise level must both be measured with all external doors and windows of the affected residence closed.
  - (ii) Background noise measurements must not include noise from the development but may include noise from necessary ventilation at the affected premises.
- (c) Corrections in <u>Fact Sheet C</u> of the NPfI are applicable to relevant noise from the development measured in accordance with this condition, however duration corrections are excluded from commercial noise.

To protect the acoustic amenity of surrounding properties.

# (71) TRANSPORT ACCESS GUIDE

A Transport Access Guide must be implemented and maintained by the operators of the premises and be made available to staff, clients, customers and visitors at all times. The following information shall be submitted to and approved by Council prior to the issue of an Occupation Certificate for the site/use.

The Transport Access Guide is to include (but not limited to) the following:

- a) A Transport Access Guide detailing sustainable transport options to access the site including public transport, cycling and walking or a combination of these modes.
- b) Public Transport Options adjacent to the site.
- c) Information regarding lack of off street car parking and passenger pickup and set down areas at the development site.
- d) Suitable nearby drop-off/pickup locations.
- e) Identify areas where drop-off/ pickup is prohibited and instruct visitors to avoid use of these areas.
- f) Suitable nearby Taxi Zones.
- g) Pedestrian access to the site.
- h) Bicycle Parking and cycleway networks to the site.
- i) Communication methods by which the Transport Access Guide will be made available to staff, clients, customers and visitors

#### Reason

To provide suitable transport options.

# (72) WASTE/RECYCLING COLLECTION - COMMERCIAL

Waste storage and the collection of waste and recycling must only occur during the designated zone collection times as outlined in the City's Waste Policy – Local Approvals Policy for Managing Waste in Public Places 2017.

#### Reason

To ensure that waste and recycling is appropriately managed.

#### (73) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS

All works to the City's public domain, including rectification of identified defects, are subject to a 6 month defects liability period from the date of Completion. The date of Completion will be nominated by Council on the Public Domain Works – Letter of Completion Operational Acceptance.

To ensure all works to the City's public domain are protected under a liability period.

# **SCHEDULE 2**

# PRESCRIBED CONDITIONS

# The prescribed conditions in accordance with Division 8A of the *Environmental Planning and Assessment Regulation 2021* apply:

- Clause 69 Compliance with *Building Code of Australia* and insurance requirements under the *Home Building Act 1989*
- Clause 70 Erection of signs
- Clause 71 Notification of *Home Building Act 1989* requirements
- Clause 72 Conditions relating to entertainment venues
- Clause 73 Conditions relating to maximum capacity signage
- Clause 74 Conditions relating to shoring and adequacy of adjoining property

Refer to the NSW State legislation for full text of the clauses under Division 2 conditions of the *Environmental Planning and Assessment Regulation 2021*. This can be accessed at: <u>http://www.legislation.nsw.gov.au</u>

# SCHEDULE 3

The following conditions have been imposed by Ausgrid:

# (74) OVERHEAD POWERLINES

The developer should refer to SafeWork NSW Document – Work Near Overhead Powerlines: Code of Practice. This document outlines the minimum separation requirements between electrical mains (overhead wires) and structures within the development site throughout the construction process. It is a statutory requirement that these distances be maintained throughout the construction phase.

Consideration should be given to the positioning and operating of cranes, scaffolding, and sufficient clearances from all types of vehicles that are expected be entering and leaving the site.

The "as constructed" minimum clearances to the mains should also be considered. These distances are outlined in the Ausgrid Network Standard, NS220 Overhead Design Manual. This document can be sourced from Ausgrid's website, www.ausgrid.com.au

It is the responsibility of the developer to verify and maintain minimum clearances onsite. In the event where minimum safe clearances are not able to be met due to the design of the development, the Ausgrid mains may need to be relocated in this instance. Any Ausgrid asset relocation works will be at the developer's cost.

Additional information can be found in the Ausgrid Quick Reference Guide for Safety Clearances "Working Near Ausgrid Assets - Clearances". This document can be found by visiting the following Ausgrid website:

www.ausgrid.com.au/Your-safety/Working-Safe/Clearance-enquiries

For new connections or to alter the existing electrical connection to the property from the Ausgrid network, the proponent should engage an Accredited Service Provider and submit a connection application to Ausgrid as soon as practicable. Visit the Ausgrid website for further details:

https://www.ausgrid.com.au/Connections/Get-connected

# (75) UNDERGROUND CABLES

Special care should also be taken to ensure that driveways and any other construction do not interfere with existing underground cables located in the footpath of adjacent roadways.

It is recommended that the developer locate and record the depth of all known underground services prior to any excavation in the area. Information regarding the position of cables along footpaths and roadways can be obtained by contacting Dial Before You Dig (DBYD).

In addition to DBYD the proponent should refer to the following documents to support safety in design and construction: SafeWork Australia – Excavation Code of Practice. Ausgrid's Network Standard NS156 which outlines the minimum requirements for working around Ausgrid's underground cables.

The following points should also be taken into consideration. Ausgrid cannot guarantee the depth of cables due to possible changes in ground levels from previous activities after the cables were installed.

Should ground anchors be required in the vicinity of the underground cables, the anchors must not be installed within 300mm of any cable, and the anchors must not pass over the top of any cable.