

**ITEM 5. ITEM FOR COMMITTEE INFORMATION – OTHER AUTHORITIES –
TRAFFIC TREATMENT – RELOCATION OF PEDESTRIAN
CROSSING AND ASSOCIATED WORKS – HICKSON ROAD
BARANGAROO**

TRIM RECORD NO: 2017/634744

RECOMMENDATION

It is recommended that the Committee note the relocation of the existing pedestrian crossing in Hickson Road, Barangaroo between Watermans Quay and Towns Place and associated line-marking and signage as shown in the Metro Stage 3 Construction Traffic Management Plan for Barangaroo.

VOTING MEMBERS FOR THIS ITEM

<i>Voting Members</i>	<i>Support</i>	<i>Object</i>
Barangaroo Deliver Authority	✓	
Roads and Maritime Services	✓	
NSW Police – Sydney City LAC	✓	
Representative for the Member for Sydney	✓	

DECISION

The Committee carried the recommendation unanimously out-of-session on 19 December 2017.

BACKGROUND

The Sydney Metro City and Southwest is an approved Critical State Significant Infrastructure (CSSI) project and includes the delivery of a station at Barangaroo in Hickson Road. The method of construction is a cut and cover box which sits in Hickson Road and takes the entire width of the road for a length of approximately 210 metres (between the High Street Steps and 25 Hickson Road).

There is an existing pedestrian crossing on Hickson Road located approximately 290 metres north of the northern kerb of Watermans Quay. This pedestrian crossing is currently within the area that is to be excavated by Metro for the station box from January 2018. It is proposed that the crossing is relocated approximately 20 metres to the south of its current location as a critical part of the Metro Stage 3 works at Barangaroo.

COMMENTS

The Tunnelling and Station Excavation contractor on behalf of Transport for NSW has completed a Construction Traffic and Management Plan (CTMP) for Stage 3 of their works which includes the relocation of the existing pedestrian crossing. The CTMP for Stage 3 has been circulated to the City of Sydney, Sydney Coordination Office and the Roads and Maritime Services via the Metro Traffic Control Group for comment. No concerns have been raised about the relocation of the crossing from any party. The Barangaroo Delivery Authority as the relevant roads authority has no objection to the proposal.

The Stage 3 CTMP outlines the necessary temporary roadworks including relocation of the pedestrian crossing, line-marking and signage to deliver this part of the project. The designs for Stage 3 have been subject to a Road Safety Audit without any outstanding issues.

CONSULTATION

Consultation has occurred on the Stage 3 CTMP with the City of Sydney, Sydney Coordination Office, Roads and Maritime Services and the Barangaroo Delivery Authority via the Sydney Metro Traffic Control Group. There have been no issues raised with the relocation or the associated works.

It should be noted that the works cannot proceed unless all parties endorse and give approval for the Stage 3 CTMP.

FINANCIAL

All costs will be borne by Transport for NSW.

Item for Committee Information – Other Authorities – Traffic Treatment – Relocation of Pedestrian Crossing And Associated Works – Hickson Road Barangaroo

Melanie Fyfe, Director Transport & Infrastructure – Barangaroo Delivery Authority