

Attachment A

Recommended Conditions of Consent
--

SCHEDULE 1

GENERAL CONDITIONS

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2025/1006 dated 6 November 2025 and the following drawings prepared by TKD Architects:

Drawing Number	Drawing Name	Date
AR DA 1000 Rev C	Proposed site plan	05.03.26
AR DA 1500 Rev B	Basement demolition plan	03.11.25
AR DA 1501 Rev B	Ground floor demolition plan	03.11.25
AR DA 1502 Rev B	First floor demolition plan	03.11.25
AR DA 1503 Rev B	Second floor demolition plan	03.11.25
AR DA 1504 Rev B	Third floor demolition plan	03.11.25
AR DA 1505 Rev B	Fourth floor demolition plan	03.11.25
AR DA 1506 Rev B	Roof demolition plan	03.11.25
AR DA 2000 Rev C	Proposed basement plan	05.03.26
AR DA 2001 Rev C	Proposed ground floor plan	05.03.26
AR DA 2002 Rev C	Proposed first floor plan	05.03.26
AR DA 2003 Rev C	Proposed second floor plan	05.03.26
AR DA 2004 Rev C	Proposed third floor plan	05.03.26
AR DA 2005 Rev C	Proposed fourth floor plan	05.03.26
AR DA 2006 Rev C	Proposed roof terrace plan	05.03.26
AR DA 2007 Rev C	Proposed roof plan	05.03.26

Drawing Number	Drawing Name	Date
AR DA 2100 Rev B	Adaptable apartment plans	05.03.26
AR DA 3100 Rev C	Proposed west elevation	05.03.26
AR DA 3101 Rev C	Proposed north elevation	05.03.26
AR DA 3102 Rev C	Proposed east elevation	05.03.26
AR DA 3103 Rev C	Proposed south elevation	05.03.26
AR DA 3400 Rev C	Building Section Sheet 1	05.03.26
AR DA 3401 Rev C	Building Section Sheet 2	05.03.26
AR DA 3402 Rev B	Building Section Sheet 3	05.03.26
AR DA 3500 Rev B	Façade sections	05.03.26
AR DA 3501 Rev B	Entrance arrangement	05.03.26
AR DA 3600 Rev A	Typical window sections	02.10.25
AR DA 4300 Rev B	Proposed materials and finishes	05.03.26

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the drawings will prevail.

Reason

To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

(2) HOUSING AND PRODUCTIVITY CONTRIBUTION

Before the issue of any Construction Certificate the housing and productivity contribution (HPC) set out in the table below is required to be made.

Housing and productivity contribution	Amount
Housing and productivity contribution (base component)	\$127,925.46

Housing and productivity contribution	Amount
Transport project component	-
Total housing and productivity contribution	\$127,925.46

The HPC must be paid using the NSW planning portal.

At the time of payment, the amount of the HPC is to be adjusted in accordance with the *Environmental Planning and Assessment (Housing and Productivity Contributions) Order 2024* (HPC Order).

The HPC may be made wholly or partly as a non-monetary contribution (apart from any transport project component) if the Minister administering the *Environmental Planning and Assessment Act 1979* agrees.

The HPC is not required to be made to the extent that a planning agreement excludes the application of Subdivision 4 of Division 7.1 of the *Environmental Planning and Assessment Act 1979* to the development, or the HPC Order exempts the development from the contribution.

The amount of the contribution may be reduced under the HPC Order, including if payment is made before 1 July 2025.

Reason

To require contributions towards the provision of regional infrastructure.

(3) AFFORDABLE HOUSING CONTRIBUTION – RESIDUAL LAND OR CENTRAL SYDNEY – PAYMENT IN LIEU OF FLOOR SPACE CONTRIBUTION – PRIOR TO CONSTRUCTION CERTIFICATE

- (a) In accordance with the City of Sydney Affordable Housing Program and prior to the issue of a Construction Certificate, the applicant must provide evidence that a monetary contribution towards the provision of affordable housing has been paid to the City of Sydney Council.
- (b) The contribution is \$2,409,750 (indexed at 31 March 2026). This is calculated by establishing the sum of the equivalent monetary contribution \$11,223.28 multiplied by 3% of the total floor area for residential development (7,157sqm).
- (c) If the contribution is paid after the indexation period in which the consent is granted, being 1 March 2026 to 28 February 2027 the above contribution will be adjusted according to the Sydney LGA median strata dwelling price ('MDP') using the following formula.
- (d) Contribution payable at Time of Payment = $C \times \text{MDP2} / \text{MDP1}$, where:
 - (i) C is the original total contribution amount payable to the City of Sydney as shown above;
 - (ii) MDP2 is the Median Strata Dwelling Price in Sydney LGA taken from the most recent NSW Government Rent and Sales Report at

the time of indexation of the equivalent monetary contribution rate; and

- (iii) MDP1 is the Median Strata Dwelling Price in Sydney LGA taken from the NSW Government Rent and Sales Report used to establish the current equivalent monetary contribution rate, being 1 March 2026 to 28 February 2027.

Contact Council's Planning Assessment Unit at planningsystemsadmin@cityofsydney.nsw.gov.au for written confirmation of the amount payable, with indexation as necessary, prior to payment.

Reason

To ensure development contributions are paid to contribute to the provision of essential affordable rental housing infrastructure.

(4) BUILDING HEIGHT

- (a) The height of the building must not exceed RL 48.26 (AHD) to the top of the new building additions.
- (b) Prior to an Occupation Certificate being issued, a Registered Surveyor must provide certification that the height of the building accords with (a) above, to the satisfaction of the Principal Certifier.

Reason

To ensure the constructed development complies with the approved height.

(5) FLOOR SPACE RATIO - ALL OTHER AREAS

The following applies to Floor Space Ratio:

- (a) The Floor Space Ratio for the business use must not exceed 2.46:1.
- (b) Prior to an Occupation Certificate being issued, a Registered Surveyor must provide certification of the total and component Gross Floor Areas (by use) in the development, utilising the definition under Sydney Local Environmental Plan 2012, applicable at the time of development consent, to the satisfaction of the Principal Certifier.

Reason

To ensure the constructed development complies with the approved floor space ratio.

(6) SIGNAGE REQUIREMENTS

The design of the approved building name signage must comply with the following:-

- (a) Details of the building name sign are to be submitted for approval prior to the installation of any building name signage as shown on the approved plans.

- (b) The signage is not to contain highly reflective materials, colours and finishes.
- (c) The signage is not to incorporate sound, vibration, odour and other emissions.

Reason

To ensure signage is designed in accordance with Council's DCP.

(7) ALLOCATION OF ACCESSIBLE CAR PARKING SPACES

For residential development, accessible car parking spaces for people with mobility impairment are only to be allocated as visitor parking or to adaptable units. Where allocated to adaptable units, the accessible car spaces and any storage spaces must form part of the adaptable strata lot in any future strata subdivision of the building.

Reason

To ensure accessible vehicle parking spaces are allocated to adaptable units.

(8) SIGNS AT EGRESS

The following signs must be provided and maintained within the site at the point(s) of vehicle egress:

- (a) Compelling drivers to stop before proceeding onto the public way
- (b) Compelling drivers to "Give Way to Pedestrians" before crossing the footway; or compelling drivers to "Give Way to Pedestrians and Bicycles" before crossing a footway on an existing or identified shared path route.

Reason

To ensure the safety of surrounding pedestrians and cyclists.

(9) SERVICE VEHICLE SIZE LIMIT

The size of vehicles servicing the property must be a maximum length of 6.4m and a maximum height of 2.2m.

Reason

To maintain the orderly operation of vehicle parking and loading areas.

(10) ASSOCIATED ROADWAY COSTS

All costs associated with the construction of any new road works including kerb and gutter, road pavement, drainage system and footway shall be borne by the developer. The new road works must be designed and constructed in accordance with the City's "Sydney Streets Technical Specification" including amendments and "Sydney Streets Design Code".

Reason

To ensure all roadway works are designed and constructed in accordance with Council requirements.

(11) VEHICLE ACCESS

All vehicles are to enter and depart the site travelling in a forward direction.

Reason

To increase pedestrian safety at the site access.

(12) SMALL CAR PARKING SPACES

- (a) The design and layout of all off-street small car parking spaces must comply with the minimum requirements of Australian Standard AS/NZS 2890.1 - 2004 Parking facilities Part 1: Off-street car parking and Council's Development Control Plan. The details must be submitted to and approved by the Principal Certifying Authority prior to a Construction Certificate being issued.
- (b) All small car spaces must be clearly marked and identifiable as small car spaces. The signs or line markings must be in place and approved by the Principal Certifying Authority prior to an Occupation Certificate being issued and must be maintained in good order at all times.

Reason

To ensure all parking areas are designed in accordance with the requirements of the Australian Standards and Council requirements.

(13) SWINGING DOORS OVER PUBLIC WAY

Any access doors to enclosures housing building services and facilities, such as hydrant and sprinkler booster assemblies or the like, must not open over the footway/roadway.

Reason

To ensure no element of the development obstructs the use of the public way.

(14) GENERAL HERITAGE

- (a) The proposed works are to be carried out in a manner that minimises demolition, alterations and new penetrations/fixings to the significant fabric of the existing building which is listed as a Heritage Item.
- (b) The fabric and features to be retained by the proposal must be properly protected during the process of demolition and construction.
- (c) All conservation and adaptation works are to be in accordance with the Articles of the Australian ICOMOS Burra Charter 2013.

- (d) New services are to be installed with minimal impact to heritage fabric and significant spaces. Where possible new services are to use existing service runs.
- (e) Appropriately qualified tradespersons (as appropriate) are to be commissioned who are skilled in traditional building and engineering trades to carry out the proposed scope of works.

Reason

To ensure that the development does not result in adverse heritage impacts.

(15) REPAIRS AND WORKS FOR MAKING GOOD

All new repairs and works for making good of existing building fabric are to be carried out on a like for like basis and match the existing in terms of materials, colours, finishes, sizes, profile and properties.

Reason

To ensure repairs and works for making good are appropriate.

(16) WASTE AND RECYCLING MANAGEMENT - GENERAL

The proposal must comply with the relevant provisions of the Sydney Development Control Plan 2012 and Council's *Guidelines for Waste Management in New Developments 2018*, which requires facilities to promote the safe and efficient storage, separation, collection and handling of waste to maximise resource recovery.

Reason

To ensure that waste and recycling is appropriately managed throughout all phases of the development.

(17) TREE(S) APPROVED FOR REMOVAL

- (a) The tree(s) detailed in Table below are approved for removal. Tree removal must not occur until the Construction Certificate has been issued.

Table 1 – Tree Removal:

Tree Number	Species:	Location
3	Elaeocarpus reticulatus (Blueberry Ash)	SW corner boundary
6	Banksia integrifolia (Coastal Banksia)	Northern boundary - Leichhardt St
7	Banksia integrifolia (Coastal Banksia)	Northern boundary - Leichhardt St

10	Corymbia cirtiodora (Lemon-scented Gum)	Northern boundary - Leichhardt St
12	Corymbia cirtiodora (Lemon-scented Gum)	Northern boundary - Leichhardt St
13	Melaleuca bracteata (Black Tea Tree)	Northern boundary - Leichhardt St
14	Melaleuca bracteata (Black Tea Tree)	Northern boundary - Leichhardt St
20	Banksia integrifolia (Coastal Banksia)	Southern boundary
20A	Acacia sp. (Wattle)	Southern boundary
24	Jacaranda mimosifolia (Jacaranda)	Southern boundary
25	Corymbia cirtiodora (Lemon-scented Gum)	Southern boundary

- (b) Tree removal works must be carried out by a qualified Arborist (minimum AQF Level 3) and in accordance with SafeWork's Code of Practice - Amenity Tree Industry.

Reason

To identify the trees that can be removed.

(18) TREE(S) THAT MUST BE RETAINED

- (a) The tree(s) detailed in the table below must be retained and protected in accordance with the conditions throughout development works.
- (b) Approval is NOT granted for the removal of the tree(s) detailed in the table below, which the City of Sydney has determined to be important landscape elements.

Table 2 – Tree Retention:

Tree Number	Species:	Location
1	Populus simonii (Simon's Poplar)	Street Tree Glebe Point Rd

2	<i>Populus simonii</i> (Simon's Poplar)	Street Tree Glebe Point Rd
4	<i>Callistomen viminalis</i> (Weeping Bottlebrush)	NW corner boundary
5	<i>Eucalyptus robusta</i> (Swamp Mahogany)	Northern boundary - Leichhardt St
8	<i>Corymbia cirtiodora</i> (Lemon-scented Gum)	Northern boundary - Leichhardt St
9	<i>Sapium sebiferum</i> (Chinese Tallowood)	Northern boundary - Leichhardt St
11	<i>Casuarina glauca</i> (Swamp Sheoak)	Northern boundary - Leichhardt St
15	<i>Eucalyptus paniculata</i> (Grey Iron Bark)	Northern boundary - Leichhardt St
16	<i>Corymbia cirtiodora</i> (Lemon-scented Gum)	Northern boundary - Leichhardt St
17	<i>Eucalyptus paniculata</i> (Grey Iron Bark)	Northern boundary - Leichhardt St
18	<i>Corymbia cirtiodora</i> (Lemon-scented Gum)	Northern boundary - Leichhardt St
19	<i>Corymbia cirtiodora</i> (Lemon-scented Gum)	NE boundary - Leichhardt St
21	<i>Banksia integrifolia</i> (Coastal Banksia)	Southern boundary
21A	<i>Banksia integrifolia</i> (Coastal Banksia)	Southern boundary
22	<i>Jacaranda mimosifolia</i> (Jacaranda)	Southern boundary
23	<i>Corymbia cirtiodora</i> (Lemon-scented Gum)	Southern boundary
24	<i>Jacaranda mimosifolia</i> (Jacaranda)	Southern boundary

Reason

To identify the trees that cannot be removed and must be retained and protected.

(19) NO OBSTRUCTIONS

All public footways and paths of travel must be free from obstructions. If services are required to be relocated to clear paths of travel, then this must be undertaken at the developer's expense. All obstructions are to be removed prior to the issue of any type of Occupation Certificate.

Reason

To ensure there are no obstructions on public footways and paths of travel.

BUILDING WORK

BEFORE ISSUE OF A CONSTRUCTION CERTIFICATE

(20) APPROVED ACOUSTIC REPORT

The report 'Acoustics Report – 431 Glebe Point Road, Glebe' prepared by West and Associates Pty Ltd dated 9 September 2025, ref 2294/8 Issue B is approved.

Where there is a conflict between the approved acoustic report and this development consent, this consent prevails.

Reason

To specify an acoustic report for reference in other noise control conditions.

(21) COMPLIANCE WITH THE ACOUSTIC REPORT PRIOR TO CONSTRUCTION CERTIFICATE

Prior to the issue of a relevant construction certificate, the Certifier must ensure the following:

- (a) A suitably qualified acoustic consultant must be appointed in accordance with the definition noted in the City of Sydney – Environmental Noise Technical Requirements, dated October 2025.
- (b) The consultant is required to review the relevant building plans, specifications, and associated documentation, and must:
 - (i) Verify that the construction plans, drawings, and construction methodology for the development are consistent with the approved acoustic report and comply with all relevant conditions and documentation of this consent.

- (ii) Resolve any non-compliances through amended construction plans, drawings, and construction methodology as necessary.
 - (iii) Ensure that all requirements under this clause are completed to the written satisfaction of the Certifier.
- (c) Following completion of the above tasks, the consultant must provide written notification to the Certifier outlining any identified non-compliances.

Reason

To ensure detailed construction and fit plans comply with the relevant standards in the approved acoustic report.

(22) DEMOLITION, EXCAVATION AND CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

A site-specific noise management plan must be submitted to the Council for comment and approval prior to issue of any Construction Certificate.

The Plan must be prepared by a suitably qualified acoustic consultant who is a person who possesses the qualifications to join the Australian Acoustic Society, Institution of Engineers Australia (grade of member) or the Association of Australasian Acoustic Consultants (grade of member firm).

The plan must include but not be limited to the following:-

- (a) identification of noise sensitive receivers near to the site.
- (b) A prediction as to the level of noise impact likely to affect the nearest noise sensitive receivers from the use and proposed number of high noise intrusive appliances intended to be operated onsite. A statement should also be submitted outlining whether or not predicted noise levels will comply with the noise criteria stated within the *City of Sydney Construction Hours /Noise Code of Practice 1992* for the typical construction hours of 07.00am to 7.00pm. Where resultant site noise levels are likely to be in exceedance of this noise criteria then a suitable proposal must be given as to the duration and frequency of respite periods that will be afforded to the occupiers of neighbouring property.
- (c) A representative background noise measurement ($L_{A90, 15 \text{ minute}}$) should be submitted, assessed in the vicinity of any potentially affected receiver locations and measured in accordance with AS 1055:1.2.1997.
- (d) Confirmation of the level of community consultation that has/is and will be undertaken with Building Managers/ occupiers of the main adjoining noise sensitive properties likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.
- (e) Confirmation of noise monitoring methodology that is to be undertaken during the main stages of work at neighbouring noise sensitive properties in order to keep complaints to a minimum and to ensure that

noise from site works complies with the noise criteria contained within City's Construction Noise Code.

- (f) What course of action will be undertaken following receipt of a complaint concerning offensive noise.
- (g) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupiers of neighbouring noise sensitive property to a minimum.
- (h) What plant and equipment is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on the occupiers of neighbouring property and other less intrusive technologies available.

Reason

To ensure an adequate construction noise and vibration management plan is prepared.

(23) PARKING DESIGN

The design, layout, signage, line marking, lighting and physical controls of all off-street parking facilities must comply with the minimum requirements of Australian Standard AS/NZS 2890.1 Parking facilities Part 1: Off-street car parking, AS/NZS 2890.2 Parking facilities Part 2: Off-commercial vehicle facilities and AS/NZS 2890.6 Parking facilities Part 6: Off-street parking for people with disabilities. The details must be submitted to and approved by the Registered Certifier prior to a Construction Certificate being issued.

Reason

To ensure parking facilities are designed in accordance with the Australian Standards.

(24) ALLOCATION OF PARKING

The number of car parking spaces to be provided for the development must comply with the table below. Details confirming the parking numbers must be submitted to the satisfaction of the Registered Certifier prior to the issue of a Construction Certificate.

Car Parking Type	Number
Residential spaces	23
Residential small car spaces	9
Accessible residential spaces	5
Service vehicle spaces	1

Car Parking Type	Number
Motorcycle parking	1

Reason

To ensure the allocation of parking is in accordance with the Council's DCP.

(25) BICYCLE PARKING AND END OF TRIP FACILITIES

- (a) The minimum number of bicycle parking spaces and end of trip facilities to be provided within the site boundary for the development must comply with the table below.

Bicycle Parking Type	Number	Requirements
Residential	30	Spaces must be a class 1 bicycle locker [1]
Residential visitor	3	Spaces must be Class 3 bicycle rails

All bicycle parking spaces and end of trip facility must be provided on private land. The public domain cannot be used to satisfy this condition.

Notes:

- (i) If a basement storage area on title that is large enough to store a bike and is no smaller than a class 1 bike locker this can be counted as a space.
- (b) The layout, design and security of bicycle facilities must comply with the minimum requirements of Australian Standard AS 2890.3 Parking Facilities Part 3: Bicycle Parking Facilities. The details must be submitted to and approved by the Registered Certifier confirming prior to and form part of the Construction Certificate being issued.

Reason

To ensure the allocation of bicycle parking onsite that is in accordance with Australian Standards and the Council's DCP.

(26) HERITAGE INTERPRETATION PLAN

- (a) An interpretation plan for the site must be submitted to and approved by Council's Urban Design and Heritage Manager / Area Planning Manager prior to a Construction Certificate being issued. The plan is to be prepared by a suitably qualified and experienced heritage practitioner or historian.

- (b) The interpretation plan must detail how information on the history and significance of the site will be provided for the public and make recommendations regarding public accessibility, signage and lighting. Public art, details of the heritage design, the display of selected artefacts are some of the means that can be used.
- (c) The plan must specify the location, type, making materials and contents of the interpretation device being proposed.
- (d) Prior to an Occupation Certificate being issued the approved interpretation plan must be implemented to the satisfaction of Council's Urban Design and Heritage Manager / Area Planning Manager.

Reason

To ensure that the heritage of the site is appropriately interpreted and incorporated into the development.

(27) PHOTOGRAPHIC ARCHIVAL DOCUMENTATION (MAJOR WORKS)

Prior to a Construction Certificate being issued, an archival photographic recording of the site is to be prepared to Council's satisfaction. The recording is to be in digital form, prepared in accordance with the Guidelines for 'Photographic Recording of Heritage Sites, Buildings and Structures', published by Department of Climate Change, Energy, the Environment and Water in April 2025. One digital copy of the record is to be submitted to Council.

Procedure

For buildings or structures with heritage significance, the archival documentation, and the number and type of selected enlarged photographs required will be determined by the significance and quality of the building or structure. For a scope of work, refer to Council's Heritage Specialist to determine the particular architectural/design features of the building/site that may need to be recorded.

For buildings or structures with no heritage significance the archival documentation requirements are less comprehensive and may just be limited to contextual and exterior photographs only. However, this will depend upon the type, complexity and significance of the building, and should be confirmed with Council's Area Coordinator Planning Assessments / Area Planning Manager.

Because significant fabric may remain concealed and only be exposed during construction works, the archival recording is to be undertaken in stages, prior to the removal of any significant building fabric or furnishings from the site, during the removal of fabric on site that exposes significant building fabric or furnishings, and after work has been completed on site, as considered appropriate by the conservation architect commissioned for the project, and submitted as two parts as follows.

- (a) The first submission of the archival recording of significant building fabric or furnishings is to be prior to the removal of any significant building fabric or furnishings from the site and must be submitted to

and approved by Council prior to the commencement of any work on site and prior to a Construction Certificate being issued.

- (b) The second submission of the archival recording is of significant building fabric or furnishings that is exposed during demolition or construction and after work has been completed on site and must be submitted to Council prior to any Occupation Certificate being issued.

The form of recording is to be a photographic documentation of the site and its context, and the exteriors and interiors of the existing building(s) photographed, where appropriate, using a camera/lens capable of 'perspective correction'.

- (c) For each of the two submissions listed above in (a) and (b), the digital form of the recording is to be as follows:
 - (i) The Development Application number and the Condition of Consent number must be noted.
 - (ii) Include a summary report detailing the project description, date and authorship of the photographic record, method of documentation and limitations of the photographic record.
 - (iii) The electronic images are to be saved as JPEG TIFF or PDF files with a size of approximately 4-6MB, and cross referenced to the digital catalogue sheets and base plans. Choose only images that are necessary to document the process and avoid duplicate images.
 - (iv) Include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive licence to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.
 - (v) The report is to be submitted via digital file transfer in PDF/A format (created directly from the digital original), with a digital catalogue of images with the following data for each location, image subject/description and date.

Reason

To ensure appropriate archival documentation of the building. Guidelines for preparing archival recordings of heritage items as a condition of consent.

(28) BUILDING WORKS TO COMPLY WITH NATIONAL CONSTRUCTION CODE – HERITAGE BUILDINGS OR BUILDINGS WITHIN CONSERVATION AREA

Any building works required to ensure compliance with the NCC (previously known as BCA) or new building standards not specified in the submitted/approved plan must not damage existing fabric and building features. If such upgrading works have impact or potentially have impact on existing fabric and features, details of the works must be submitted and

approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to issue of any Construction Certificate.

Reason

To ensure an appropriate heritage outcome.

(29) CONSTRUCTION TRAFFIC MANAGEMENT PLAN

- (a) A Construction Traffic Management Plan must be submitted to and approved by Council prior to a Construction Certificate being issued.
- (b) The approved plan must be complied with during any demolition and/or construction work.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure that the impacts of construction traffic is appropriately managed.

(30) DILAPIDATION REPORT – MINOR

Subject to the receipt of permission of the affected landowner, dilapidation report/s of adjoining buildings are to be prepared by an appropriately qualified practising structural engineer and submitted for the approval of the Registered Certifier prior to the issue of a construction certification.

Reason

To ensure that dilapidation reports are prepared and to identify damage to for adjoining/nearby properties resulting from building work on the development site.

(31) LANDSCAPE OF THE SITE

- (a) A detailed landscape design including plans and details drawn to scale, and technical specification, by a registered landscape architect must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the issue of a Construction Certificate. These documents must include:
 - (i) Location of existing and proposed planting on the site including existing and proposed trees, planting in natural ground, and planting on structure.
 - (ii) Location and details of existing and proposed structures on the site including, but not limited to, paving, walls, services, furniture, shade structures, lighting and other features.
 - (iii) Details of earthworks and soil depths including finished levels and any mounding. The minimum soil depths for planting on structure must be 1000mm for trees, 450mm for shrubs and 200mm for groundcovers, excluding mulch and drainage layers.

- (iv) Planting details, and location, numbers, type and supply size of plant species, with reference to Australian Standards and preference for drought resistant species that contribute to habitat creation and biodiversity. Note: Substitution of the *Banksia serrata* (Old Man Banksia) is to be made for a more reliable species. The City of Sydney Tree Species List should be used as guide when selecting an appropriate species.
 - (v) Details of drainage, waterproofing and watering systems.
 - (vi) Landscape maintenance plan. This plan is to be complied with during occupation of the property.
- (b) Relevant drawings cross referenced in the landscape package, such as architectural details, stormwater and hydraulic plans etc, should also be submitted to demonstrate a fully coordinated design.
 - (c) All landscaping in the approved plan is to be complete prior to any Occupation Certificate being issued.
 - (d) The landscape maintenance plan is to be complied with during occupation of the property.

Reason

To ensure the development is supported by a good quality, buildable landscape scheme that meets the City's controls.

(32) SPECIAL CONDITION – UPDATED ARCHITECTURAL PLANS

The Architectural Plans must be updated, submitted and approved by City of Sydney Urban Forest Team prior to the issue of any Construction Certificate. The updated plans must show:

- (a) Existing levels are to be retained within the proposed court yard area within the TPZ of Trees 21, 21A, 23 and 24.
- (b) The court yard area in this vicinity is to be constructed on or above grade.

A qualified Arborist (minimum AQF Level 5) must assess the design prior to the updated plans being submitted to the City of Sydney.

(33) DESIGN FOR ENVIRONMENTAL PERFORMANCE

- (b) Prior to the issue of any Construction Certificate, the Registered Certifier must be satisfied that those matters listed in the following sections of the approved Design for Environmental Performance report are incorporated into the relevant construction plans and accompanying documentation:

- (i) Section 3 – BASIX

A copy of the required completed BASIX certificate(s) accepted as part of this consent/as amended above must be lodged with an application for a construction certificate and the items nominated as part of the subject BASIX certificate(s) must be

specified on the plans submitted with the Construction Certificate application.

Note: Any requirement detailed in the accompanying BASIX Certificate must be included as a specific notation or inclusion on any future Construction Certificate plans and specification in accordance with Division 1 of Part 6 of the EP&A Regulation, 2021.

Reason

To ensure the environmental performance of the development.

(34) PUBLIC DOMAIN DAMAGE BOND

- (a) A Public Domain Damage Deposit calculated on the basis of 215 square metres of asphalt Glebe Point Road, and 60 square metres of asphalt and concrete Leichhardt Street site frontage must be lodged with Council in accordance with the City of Sydney's adopted Schedule of Fees and Charges. The bond must be provided as security for repairing any damage to the public domain in the vicinity of the site.
- (b) The City's Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The Bond must be lodged with the City prior to an approval for demolition being granted or any Construction Certificate being issued, whichever is earlier.
- (c) The bond in this condition will be released in full when the Public Domain Works Security Bond is lodged with the City.

Reason

To allow for the appropriate management and rectification of damage to the public domain.

(35) PROTECTION OF STONE KERBS

- (a) The existing stone kerbs on the Glebe Point Road and Leichhardt Street frontages of the site are to be retained and properly protected during demolition, excavation and construction works.
- (b) To avoid damage to stone kerbs during excavation and construction works for the development, temporary removal and storage of the stone kerbs may be approved by Council. Removed, serviceable stone kerbs (i.e. those that are in good condition as agreed by Council officers) must be re-installed in accordance with the City of Sydney's standard details and specifications after the construction works have been completed. A temporary concrete kerb will need to be constructed to retain the footpath until the stone kerbs can be reinstalled.
- (c) Note the following:
 - (i) all costs associated with the works are to be borne by the developer.

- (ii) Damaged kerbs are to be replaced to match existing to Council's satisfaction or as otherwise advised by Council officers.
- (iii) Where new vehicle crossings or temporary crossings are to be constructed to access the property, the affected kerb stones should be salvaged and reused wherever possible.
- (iv) All new driveway laybacks and kerbs are to be constructed with stone kerbs to match existing stones or as specified by City officers.
- (v) Council approval is required before kerbs are removed.
- (vi) Council approval is required prior to the cutting of existing stone kerbs for stormwater kerb outlets.
- (vii) Stone kerbs and gutters may be bonded in accordance with the City of Sydney's adopted Schedule of Fees and Charges. If so, this will be included with the Public Domain Damage Bond.
- (viii) Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure the protection of stone kerbs.

(36) SURVEY INFRASTRUCTURE – IDENTIFICATION AND RECOVERY

Under Section 24 of the Surveying and Spatial Information Act 2002, it is an offence to remove, damage, destroy, displace, obliterate or deface any survey mark unless authorised to do so by the Surveyor-General. Accordingly, the applicant must, where possible, ensure the preservation of existing survey infrastructure undisturbed and in its original state or else provide evidence of the Surveyor-General's authorisation to remove or replace marks.

Prior to the issue of any Construction Certificate, documentary evidence must be prepared by a Registered Surveyor and submitted to and approved by Council's Area Planning Manager / Coordinator. This evidence must include either:

- (a) A copy of any Surveyor-General's Approval for Survey Mark Removal granted by NSW Spatial Services for the subject site, including all documentation submitted as part of that application (for example the survey mark audit schedule, strategy plan and strategy report); or
- (b) A letter, signed by a current NSW Registered Land Surveyor and including his or her Board of Surveying and Spatial Information (BOSSI) identification number, stating that all investigations required under Surveyor-General's Direction No.11 have been made for the subject site and that no survey infrastructure will be affected by the proposal.

Council's Principal Surveyor may request further information and/or add conditions to any Surveyor-General's Approval at their discretion.

Note: Refer to Clause 4.7 in the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure the preservation of existing survey infrastructure.

(37) PUBLIC DOMAIN CONCEPT PLAN

A public domain concept plan, showing all the site frontages and extending a minimum of 5m past the boundary and to the road centreline, must be prepared in accordance with the City's *Public Domain Manual* and *Sydney Streets Code*. It must be submitted to and approved by the City's Public Domain Unit prior to the issue of any Construction Certificate for the development other than for demolition or excavation.

Note: A detailed Public Domain Plan will be required prior to construction (refer to Public Domain Plan Detailed Documentation for Construction condition).

Reason

To ensure public domain works comply with Council's requirements.

(38) PUBLIC DOMAIN LEVELS AND GRADIENTS

The Public Domain Levels and Gradients submission prepared by TKD Architects, Issue Date Sep 2025 provided with the Development Application is approved in principle.

If a *Public Domain Plan Detailed Documentation For Construction* condition applies to the development consent and or changes to the development entrances / floor levels occur after approval has been issued, a Public Domain Levels and Gradients submission must be submitted to and approved by the City's Public Domain Unit. The submission must be prepared in accordance with the City's *Public Domain Manual* and submitted with a completed *Application for Public Domain Levels and Gradients* prior to an approval being issued for the construction of public domain work.

Any requirements to comply with Disability Discrimination Act at the entrance to a building or publicly accessible space must be resolved inside the site boundary.

Reason

To ensure public domain levels and gradients comply with Council's requirements.

(39) STORMWATER DRAINAGE DESIGN

Prior to issue of any Construction Certificate a detailed stormwater management plan prepared by suitable qualified and experienced professionals must be submitted to and approved by the City's Public Domain Unit and must include:

- (i) Council's Sydney Streets Technical Specifications, Part A4 Drainage Design;
- (ii) Council's Sydney Streets Technical Specifications, Standard Drawings;
- (iii) Council's Sydney Streets Technical Specifications, Part B10: Stormwater Drainage Construction;
- (iv) Council's Stormwater Drainage Manual; and
- (v) All relevant Australian Standards.

This information is available for download from the City's website at <https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

Note: A Deed of Agreement (Stormwater Deed) for all proposed connections to the City's drainage system, and a Positive Covenant for all OSD systems may be required prior to issue of any Occupation Certificate.

Reason

To ensure stormwater drainage design complies with Council's requirements.

(40) PUBLIC DOMAIN LIGHTING UPGRADE

Prior to issue of any Construction Certificate for excavation, civil construction, drainage or building work (whichever is earlier), a concept Public Domain Lighting Upgrade Plan for pedestrian and street lighting in the public domain must be submitted to and approved by City's Public Domain Unit. The Lighting Plan must be prepared in accordance with the *Sydney Streets Technical Specifications A5 and B8*, *Sydney Lights Design Code* and *Public Domain Manual*. This information is available for download from the City's website at <https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

The lighting upgrade plan must cover all adjacent street frontages, being Leichhardt Street and Glebe Point Road and shall be designed to include the following requirements:

- Upgrade existing Ausgrid streetlights using Ausgrid network standard LED luminaires to achieve the lighting compliance and consider installing suitable glareshields to avoid glare issues for neighbouring properties (if required).
- Leichhardt Street: Lighting shall comply with requirement of AS 1158.3.1 Category PR2 on the roadway and PP2 on the footways
- Glebe Point Road: Lighting shall comply with requirement of AS 1158.3.1 Category PR1 on the roadway and PP2 on the footways
- Obtrusive lighting assessment shall comply with requirement of AS 4282

Dedicated Cyclist Way:

- Lighting shall comply with requirement of AS1158.3.1 Category PP2 + 0.7lux (minimum vertical illuminance)

Advice on site specific lighting requirements must be obtained from City's Public Domain Unit before proceeding with the preparation of any final lighting design proposals.

Reason

To ensure pedestrian and street lighting in the public domain complies with Council's requirements.

(41) DILAPIDATION REPORT - PUBLIC DOMAIN

Prior to an approval for demolition and preparatory works being granted or the issue of any Construction Certificate, whichever is earlier, a photographic recording of the public domain site frontages is to be prepared as described in the Public Domain Manual and submitted for approval by Council's Public Domain Unit. The City's *Public Domain Manual* is available for download from the City's website at <https://www.cityofsydney.nsw.gov.au/>

The submission is to include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

Reason

To establish and document the condition of the public domain for comparison as building work progresses and is completed.

Reason

To ensure the ventilation complies with relevant standards.

(42) WASTE AND RECYCLING MANAGEMENT – RESIDENTIAL

The Operational Waste Management Plan accompanying this Development Application has not been approved by this consent. An Operational Waste Management Plan is to be submitted to and reviewed by Council's City Cleansing & Resource Recovery Unit and approved by Council's Area Planning Manager prior to the issue of a **Construction Certificate**. The plan must comply with Council's Development Control Plan and *Guidelines for Waste Management in New Developments*. The plan must address:

- (a) Include a note confirming that building management staff will be available during waste collection to assist with bin transfer as requested by the City of Sydney or its contractors.
- (b) Confirm provision of ride on bin moving equipment and flat trailer to support bin management and movement to collection point.
- (c) Waste and recycling stream(s) bins must not be placed on the street for collection. The waste contractor must wheel the bins from the waste

storage area of the property to the waste collection vehicle upon arrival and return them to the waste storage area following collection. Unimpeded access must be provided to the waste and recycling storage area(s) at all times.

- (d) Unobstructed access is to be provided for waste collection vehicles to set down within 10m of the waste storage and collection area(s) during zone collection times on collection days.

Reason

To document agreed waste management facilities and arrangements and ensure good waste management outcomes.

(43) WASTE INFRASTRUCTURE – RESIDENTIAL

Prior to the issue of **Construction Certificate**, detailed plans, and specifications for the construction of waste management facilities must be submitted for review by Council's City Cleansing & Resource Recovery Unit and approved by Council's Area Planning Manager. The waste management facilities to be provided responsive to Council's controls, policies, and guidelines, including but not limited to:

- (a) Waste and recycling stream(s) storage area(s) to be designed and constructed in accordance with Reference D of *Council's Guidelines for Waste Management in New Developments*. Floors to be waterproofed across all intersections that extend a minimum 1200mm high on the walls.
- (b) Waste chute system to be designed in accordance with Section B and Reference E of the City of Sydney Guidelines for Waste Management in New Developments.

Reason

To allow for the safe and hygienic storage of waste and recycling and support provision of a safe and efficient waste collection service.

BEFORE BUILDING WORK COMMENCES

(44) DEMOLITION AND CONSTRUCTION MANAGEMENT

- (a) Prior to the commencement of demolition and/or excavation work the following details must be submitted to and be approved by the Principal Certifier:
 - (i) Plans and elevations showing distances of the subject building from the location of adjoining and common/party walls, and (where applicable) the proposed method of facade retention.
 - (ii) A Demolition Work Method Statement prepared by a licensed demolisher who is registered with SafeWork NSW. (The demolition by induced collapse, the use of explosives or on-site burning is not permitted.)
 - (iv) A Waste and Recycling Management Plan – Demolition and Construction for the demolition and or excavation of the proposed development. The plan is to include details of materials that will be excavated and their proposed destination or reuse.
 - (v) Plans and elevations showing the location, construction and installation of temporary site fencing and any construction related temporary structures placed on and/or above roads used in connection with the development.

Note: Construction related temporary structures, including hoardings and scaffolding, proposed for erection on and/or above City-owned and controlled land (footways and roadways), and other activities, must comply with Council's Code of Practice: Construction related Temporary Structures On and Above Roads and the Code of Practice: Hoisting and Construction Activities On and Above Roads including obtaining all required approvals from Council under the provisions of the Local Government Act 1993 and the Roads Act 1993 prior to installation.

- (b) Such statements must, where applicable, be in compliance with AS2601-2001 Demolition of Structures, the *Work, Health and Safety Act 2011* and Regulation; Council's *Guidelines for Waste Management in New Developments 2018*, the *Waste Avoidance and Resource Recovery Act 2001*, and all other relevant acts and regulations and must include provisions for:
 - (i) A Materials Handling Statement for the removal of refuse from the site in accordance with the *Waste Avoidance and Resource Recovery Act 2001*.
 - (ii) The name and address of the company/contractor undertaking demolition/excavation works.
 - (iii) The name and address of the company/contractor undertaking off site remediation/disposal of excavated materials.
 - (iv) The name and address of the transport contractor.

- (v) The type and quantity of material to be removed from site.
- (vi) Location and method of waste disposal and recycling.
- (vii) Proposed truck routes, in accordance with this development consent.
- (viii) Procedures to be adopted for the prevention of loose or contaminated material, spoil, dust and litter from being deposited onto the public way from trucks and associated equipment and the proposed method of cleaning surrounding roadways from such deposits. (Note: With regard to demolition of buildings, dust emission must be minimised for the full height of the building. A minimum requirement is that perimeter scaffolding, combined with chain wire and shade cloth must be used, together with continuous water spray during the demolition process. Compressed air must not be used to blow dust from the building site).
- (ix) Measures to control noise emissions from the site.
- (x) Measures to suppress odours.
- (xi) Enclosing and making the site safe.
- (xii) Induction training for on-site personnel.
- (xiii) Written confirmation that an appropriately qualified Occupational Hygiene Consultant has inspected the building/site for asbestos, contamination and other hazardous materials, in accordance with the procedures acceptable to SafeWork NSW.
- (xiv) An Asbestos and Hazardous Materials Clearance Certificate by a person approved by the SafeWork NSW.
- (xv) Disconnection of utilities.
- (xvi) Fire Fighting. (Fire fighting services on site are to be maintained at all times during demolition work. Access to fire services in the street must not be obstructed).
- (xvii) Access and egress. (Demolition and excavation activity must not cause damage to or adversely affect the safe access and egress of the subject building or any adjacent buildings).
- (xviii) Waterproofing of any exposed surfaces of adjoining buildings.
- (xix) Control of water pollution and leachate and cleaning of vehicles tyres (proposals must be in accordance with the *Protection of the Environmental Operations Act 1997*).
- (xx) Working hours, in accordance with this development consent.
- (xxi) Any SafeWork NSW requirements.

- (c) The approved work method statements and a waste management plan as required by this condition must be implemented in full during the period of construction.
- (d) All waste records from the recycling and/or disposal of any demolition and construction waste generated from the works must be retained on site. These records must be available for sighting on request by an authorised Council officer.

Reason

To ensure that impacts arising from demolition, excavation and construction are appropriately managed.

(45) RUN-OFF, EROSION AND SEDIMENT CONTROL

- (a) Before the commencement of any works, all sediment and erosion controls must be implemented and maintained in accordance with the document titled Managing Urban Stormwater Soils & Construction Volume 1 (Landcom, 2004).
- (b) Sediment control structures must be maintained throughout remediation works to prevent runoff of any potentially contaminated water or soil to the surrounding environment.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure that construction is appropriately managed to prevent pollution impacts.

(46) TREE PROTECTION ZONES (FOR PRIVATE/PROPERTY TREES)

- (a) Tree protection zones (s) (TPZs) must be established in accordance with the Australian Standard 4970 'Protection of trees on development sites' before the commencement of and until completion of the development works.

Table 3- Tree Protection Zones

Tree No.	Species	Location	Radius (m) from trunk
4	Callistomen viminalis (Weeping Bottlebrush)	NW corner boundary	3.6
5	Eucalyptus robusta (Swamp Mahogany)	Northern boundary - Leichhardt St	4.1

Tree No.	Species	Location	Radius (m) from trunk
8	Corymbia cirtiodora (Lemon-scented Gum)	Northern boundary - Leichhardt St	3.1
9	Sapium sebiferum (Chinese Tallowood)	Northern boundary - Leichhardt St	4.1
11	Casuarina glauca (Swamp Sheoak)	Northern boundary - Leichhardt St	5.4
15	Eucalyptus paniculata (Grey Iron Bark)	Northern boundary - Leichhardt St	2.5
16	Corymbia cirtiodora (Lemon-scented Gum)	Northern boundary - Leichhardt St	4.4
17	Eucalyptus paniculata (Grey Iron Bark)	Northern boundary - Leichhardt St	4.4
18	Corymbia cirtiodora (Lemon-scented Gum)	Northern boundary - Leichhardt St	5.9
19	Corymbia cirtiodora (Lemon-scented Gum)	NE boundary - Leichhardt St	3.6
21	Banksia integrifolia (Coastal Banksia)	Southern boundary	2.0
21A	Banksia integrifolia (Coastal Banksia)	Southern boundary	2.0
22	Jacaranda mimosifolia (Jacaranda)	Southern boundary	7.2
23	Corymbia cirtiodora (Lemon-scented Gum)	Southern boundary	5.0
24	Jacaranda mimosifolia (Jacaranda)	Southern boundary	4.2

(b) The following works must be excluded from within any TPZs:

- (i) Soil cultivation, disturbance or compaction.
 - (ii) Stockpiling, storage or mixing of materials, washing and repairing of tools.
 - (iii) The parking (except existing on street parking) of vehicles, equipment and machinery.
 - (iv) The disposal of liquids and refuelling.
 - (v) The disposal of building materials.
 - (vi) Any action leading to an impact on tree health or structure.
- (c) Tree protection fencing (1.8m steel mesh fencing, secured and fastened to prevent movement) must be installed at the perimeter of the TPZs or as per the approved Tree Protection Plan and Tree Protection Specification prior to the commencement of the development works. Roots must not be damaged during the establishment or maintenance of the fencing.
 - (d) Where tree protection fencing (or sections of) cannot be installed due to site constraints, written approval must be obtained from a qualified Arborist (minimum AQF Level 5) and trunk and ground protection installed as per AS4970. Compliance with this condition must be addressed in the Tree Protection Compliance Certificate prepared by the Arborist.
 - (e) Tree protection fencing must not be moved or relocated unless written approval is obtained from a qualified Arborist (minimum AQF Level 5) and alternate protection measures are installed to ensure the trees the viability of the tree(s) is not impacted. Compliance with this condition must be addressed in the Tree Protection Compliance Certificate prepared by the Arborist.
 - (f) Where site sheds cannot be installed outside of the TPZs due to site constraints, written approval must be obtained from a qualified Arborist (minimum AQF Level 5) and appropriate tree protection measures installed as per AS4970. Compliance with this condition must be addressed in the Tree Protection Compliance Certificate prepared by the Arborist.
 - (g) Signage identifying the TPZs must be attached to the tree protection fencing. Signage must be placed in a visible position in remain in place throughout the development works.
 - (h) Ground protection in accordance with AS4970 must be installed if construction access is required within the TPZs. Existing pavements and hard stand areas can be used as ground protection.
 - (i) All approved work undertaken within the TPZs must be supervised by a qualified Arborist (minimum AQF Level 5).

Note: The work within the TPZ and installation of tree protection measures is only applicable within the subject development site.

Reason

To ensure the protection and ongoing health of trees for the duration of the development.

(47) STREET TREE PRUNING AND REMOVAL

- (a) The consent from Council's Tree Management Officer must be obtained prior to the undertaking of any street tree pruning works including tree roots greater than 40mm diameter. Only minor pruning works will be approved by Council.
- (b) Any pruning that has been approved by Council, must be carried out by an arborist with a minimum AQF Level 3 qualification in arboriculture and must be in accordance with AS4373 Australian Standards 'Pruning of Amenity Trees'.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure that approval is obtained for any pruning works to, or removal of, street trees and that such works are carried out in an appropriate manner.

(48) TREE PROTECTION ZONES (FOR STREET TREES)

- (a) Tree Protection Zone(s) (TPZs) must be established in accordance with Australian Standard 4970 'Protection of trees on development sites' before the commencement of and until completion of the development works.

Tree No.	Species	Tree Location	TPZ radius(m) from trunk	SRZ radius (m) from trunk
1	<i>Populus simonii</i> (Simon's Poplar)	Street Tree Glebe Point Rd	3.6	2.1
2	<i>Populus simonii</i> (Simon's Poplar)	Street Tree Glebe Point Rd	3.4	2.0

- (b) Tree trunk and major branch protection must be installed prior to the issuing of any Construction Certificate and maintained for the duration of all construction work, and must include:
 - (i) Tree trunk(s) and/or major branches to a height of 2 metres protected by wrapped thick underlay carpet or similar padding material to limit damage.
 - (ii) Timber planks (50mm x 100mm) placed around tree trunk(s). The timber planks must be spaced at 100mm intervals and must be

fixed against the trunk with tie wire, or strapping. The thick carpet underlay or padding material and timber planks must not be fixed to the tree in any instance, or in any fashion.

- (iii) Young street trees protected by the installation of three (3) wooden stakes around the edge of the tree pits or a minimum of 1 metre from the base of the trunk. Hessian must be wrapped around the stakes. If existing stakes or a metal tree guard are already in place, these suffice as tree protection.
- (iv) Tree trunk and major branch protection must remain in place for the duration of the development works and be removed at the completion of the development works.
- (c) Materials or goods, including sheds, must not be stored or placed:
 - (i) around or under the tree canopy or;
 - (ii) within two (2) metres of tree trunks or branches or any street trees.
- (d) Temporary signs or any other items must not be fixed or attached to any street tree.
- (e) Where installed, hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree pits. Supporting columns must not be placed on exposed tree roots.
- (f) Existing sections of kerbs adjacent to any street tree must not be removed without approval from the City of Sydney Tree Team.
- (g) Any trenching works for services / hydraulics / drainage etc must not be undertaken within any Tree Protection Zone (TPZ). Alternative installation methods for services, such as directional boring/drilling, or redirection of services shall be employed.
- (h) Any damage sustained to street tree(s) as a result of any construction activities (including demolition), must be immediately reported to the City of Sydney Urban Forest Team on 9265 9333. Any damage to street trees as a result of any construction activities may result in prosecution under the Local Government Act 1993 and the Environmental Planning and Assessment Act 1979.
- (i) Compliance with this condition must be addressed in the Tree Protection Compliance Certificate prepared by a qualified Arborist (minimum AQF Level 5).

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure the protection and ongoing health of the street trees.

(49) PUBLIC DOMAIN WORK – CONSTRUCTION APPROVAL UNDER SECTION 138 ROADS ACT 1993

Prior to the construction of any public domain works, approval under Section 138 / 139 of the Roads Act 1993 must be issued by the City's Public Domain Unit.

Reason

To ensure relevant approvals for public domain work are obtained.

DURING BUILDING WORK

(50) COMPLIANCE WITH DEMOLITION, CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

- (a) All works conducted on site which form part of this development must be carried out in accordance with the approved Demolition, Excavation and Construction Management Plan.
- (b) Where all such control measures have been implemented and the resultant noise and/ or vibration levels at any sensitive receiver still exceed the council's applicable criteria stated in the Construction Hours/Noise Code 1992 and are giving rise to sustained complaints then the contractor must provide regular, appropriate and sustained periods of respite in consultation with Council's Health and Building unit. Approval to vary the authorised noise and vibration levels must be received in writing by the proponent from Council prior to activities being undertaken that exceed sanctioned emission levels. (Use where respite periods not specified under the approved DEC NMP)

Such periods must be set and agreed to by Council's Health and Building Unit.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure all parties are aware of the supporting documentation that applies to the development.

(51) USE OF INTRUSIVE APPLIANCES – NOT APPROVED

This development consent does not extend to the use of appliances which emit noise of a highly intrusive nature (such as pile - drivers and hydraulic hammers) or are not listed in Groups B, C, D, E or F of Schedule 1 of the City of Sydney Code of Practice for Construction Hours/Noise 1992".

A separate Section 4.55 application must be submitted to the Council for the use of any equipment of a highly intrusive nature (such as pile - drivers and hydraulic hammers) or are not listed in Groups B, C, D, E or F of Schedule 1 of the *City of Sydney Code of Practice for Construction Hours/Noise 1992*.

Reason

To ensure the acoustic amenity of surrounding developments is maintained.

(52) USE OF HERITAGE CONSULTANT – MINOR DEVELOPMENT

- (a) A heritage consultant experienced in heritage restoration and renovation works is to be commissioned to work with the consultant team throughout the design development, contract documentation and construction stages of the project. The heritage consultant is to be involved in the resolution of all matters where existing significant fabric and spaces are to be subject to preservation, restoration, reconstruction, adaptive reuse, recording and demolition. The heritage

consultant is to be provided with full access to the site and authorised by the applicant to respond directly to Council where information or clarification is required regarding the resolution of heritage issues throughout the project. Evidence and details of the above commission on the above terms are to be submitted to Council's Area Coordinator Planning Assessments / Area Planning Manager prior to commencement of work on site.

- (b) The heritage consultant must sign off the completed project and submit a final report to Council's Area Coordinator Planning Assessments / Area Planning Manager specifying how the heritage conditions are satisfied prior to the issue of any Occupation Certificate or the commencement of the use, whichever is earlier.

Reason

To ensure that the implementation of the approved development is carried out in a manner that does not have adverse heritage impacts.

(53) ARCHAEOLOGICAL DISCOVERY DURING EXCAVATION

- (a) Should any relics be unexpectedly discovered on the site during excavation, all excavation or disturbance to the area is to stop immediately and the Heritage Council of NSW should be informed in accordance with section 146 of the Heritage Act 1977.
- (b) Should any Aboriginal objects be unexpectedly discovered then all excavation or disturbance of the area is to stop immediately and NSW Government Office of Environment and Heritage is to be informed in accordance with Section 89A of the *National Parks and Wildlife Act 1974*.
- (c) Should any archaeological remains or Aboriginal objects be discovered, a copy of recording of the finds and the final archaeological summary report is to be submitted to Council prior to the issue of any Occupational Certificate.
- (d) If the discovery is on Council's land, Council must be informed.

Reason

To ensure that the archaeology of the site is appropriately managed and protected.

(54) NOTIFICATION – NEW CONTAMINATION EVIDENCE

- (a) Council and the Certifier must be notified immediately of any new information which arising during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination.
- (b) Once identified, remediation, demolition or construction work must immediately cease.

- (c) A certified environmental consultant must be appointed to undertake an assessment of the potential contaminants and works required to make the site safe from potential human health and environmental harm.
- (d) If the duty to report contamination to the NSW EPA under Section 60 of the Contaminated Land Management Act 1997 is triggered, the NSW EPA and Council must be notified immediately.

Reason

To ensure that any new contamination evidence or unexpected finds is reported and the site is appropriately remediated.

(55) IMPORTED FILL MATERIALS

- (a) All fill material imported to the site must be certified and validated by a certified environmental consultant. It should be accompanied by documentation from the consultant that confirms its classification and suitability for the intended use. The fill must also be compatible with the existing soil characteristics to support site drainage.
- (b) Imported fill must be limited to the following:
 - (i) Virgin excavated natural material (VENM), classified in accordance with the Protection of the Environment Operations Act 1997.
 - (ii) Excavated natural material (ENM), certified in accordance with the Protection of the Environment Operations (Waste) Regulation 2014.
 - (iii) Waste-derived materials subject to a Resource Recovery Exemption under Clauses 91 and 92 of the Protection of the Environment Operations (Waste) Regulation 2014 and recognised by the NSW EPA as “fit for purpose” for the proposed development.
- (c) Any waste-derived material received under a resource recovery exemption must be accompanied by documentation from the NSW EPA confirming compliance with the exemption conditions. This documentation must be provided to the Certifier and Council:
 - (i) Upon request.
 - (ii) Before the commencement of works under the Protection of the Environment Operations Act.
 - (iii) Before the issue of a construction certificate or occupation certificate or
 - (iv) As part of the validation report for the remediation, as applicable.
- (d) All imported fill must be accompanied by certification from the supplier confirming the material is not contaminated, based on analysis of the source site’s history and/or sampling and analysis must be conducted in accordance with the NSW EPA (2022) Sampling Design Guidelines.

- (e) Any existing soils proposed for reuse onsite must be analysed and classified by a suitably qualified and experienced environmental consultant. This assessment must follow the relevant NSW EPA guidelines and the National Environment Protection (Assessment of Site Contamination) Measure 1999 (as amended in 2013), to confirm suitability for the proposed land use. The results must be included in the validation report for the remediation

Reason

To ensure that imported fill is not contaminated.

(56) CLASSIFICATION OF WASTE

- (a) All excavated material removed from the site must be classified in accordance with the EPA's Waste Classification Guidelines before it is disposed of at an approved waste management facility or otherwise lawfully managed.
- (b) The classification, and the volume of material removed, and the receival facility's details must be reported to the Certifier or Council (where a Certifier is not required).

Reason

To ensure that waste from site is classified and disposed of appropriately.

(57) STOCKPILES

- (a) Soil or other materials must not be stockpiled on footpaths or nature strips without prior written approval from Council.
- (b) All stockpiles must be managed to prevent contamination of the underlying soil.
- (c) Potentially contaminated soil must be stockpiled on a hardstand surface or over polyethylene sheeting.
- (d) Stockpiles must:
 - (i) Be bunded to prevent runoff of potentially contaminated materials.
 - (ii) Be stabilised through compaction and contouring to minimise wind exposure and allow access for water trucks.
 - (iii) Not exceed the height of perimeter fencing to assist in controlling dust and odour emissions.
 - (iv) Be clearly labelled with a unique identification number and include records of the soil's volume and origin to enable tracking from excavation to final disposal or reuse.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure that stockpiles of soil or other materials are appropriately managed.

(58) COMPLIANCE WITH ARBORIST'S REPORT

- (a) All recommendations, Tree Protection Specifications (TPS), Tree Protection Plan (TPP) and Methodology Statements contained in the approved Arboricultural Report prepared by Tree Wise Me., Dated 4 July 2025, must be implemented during the demolition, construction and use of the development.

Reason

To ensure that works affecting trees are carried out in an appropriate manner and in accordance with the approved arborist's report.

(59) SITE SUPERVISION AND REPORTING

- (a) A qualified Arborist (minimum AQF Level 5) must oversee various stages of work within the Tree Protection Zone(s) (TPZs) of any tree listed for retention.
- (b) The Arborist must undertake 2 monthly inspections through the development works.
- (c) The Arborist must certify compliance with each key milestone detailed below:
 - (i) Installation of tree protection measures (i.e. tree protection fencing, trunk and branch protection, ground protection, tree protection signage) prior to the commencement of the development works;
 - (ii) Demolition of ground surface materials (pavers, concrete, grass etc.) or inground structures within the TPZs of any tree to be retained. The demolition of stairs and walling within the TPZ of Trees 1 and 2, demolition of the concrete paving within the TPZ of Trees 19, 21, 21A, 23 and 24;
 - (iii) Excavation and trenching within the TPZs, (including stormwater within TPZ of Trees 11, 15 and 16);
 - (iv) Construction of stormwater within TPZ of Trees 11, 15 and 16.
 - (v) Landscape works within the TPZs;
 - (vi) Other times as specified in the Arboricultural Impact Assessment Report, Tree Protection Specifications (TPS) and Tree Protection Plan (TPP) or these conditions.
- (d) A Tree Protection Compliance Report, which includes photographic evidence and provides details on the health and structure of tree(s), must be submitted within one week following each scheduled inspection and key milestone listed above. The report is to be submitted to, and

acknowledged, by the City of Sydney Urban Forest Team. The Tree Protection Compliance Report must include:

- (i) Confirmation that the tree protection measures have been installed in accordance with these conditions;
 - (ii) Details of any additional tree protection recommendations and subsequent implementation to ensure the tree(s) remain in a healthy condition;
 - (iii) Details of works undertaken on any tree to be retained or any works within the TPZs.
- (e) A final Tree Protection Compliance Certificate demonstrating that all Tree Protection Compliance Reports have been submitted at each scheduled inspection and key milestone listed above must be submitted and approved by the City of Sydney Area Planning Manager prior to the issue of any Occupational Certificate.

Reason

To ensure the protection and ongoing health of trees on the site.

(60) TREE PRUNING – FURTHER APPROVAL REQUIRED

- (a) Consent from the City of Sydney Urban Forest Team must be obtained prior to undertaking the pruning of any tree to be retained, including trees roots greater than 40mm diameter.
- (b) Construction access and the location of the works zone must be planned to avoid adversely impacting any tree to be retained. Alternative work zone locations must be provided and suitable size cranes/machinery/equipment utilised to minimise tree pruning requirements. Only minor pruning works will be approved by the City's Urban Forest Team.
- (c) Any approved pruning must be carried out by a qualified Arborist (minimum AQF Level 3) in accordance with Australian Standard 4373 'Pruning of Amenity Trees' and the SafeWork's Code of Practice - Amenity Tree Industry.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' and the 'Code of Practice: Construction related Temporary Structures On and Above Roads' for further information.

Reason

To ensure that pruning works to trees are carried out in an appropriate manner.

(61) PROTECTION OF NATIVE WILDLIFE IN TREES

- (a) In the event that wildlife is found during the course of tree removal works, work must stop until a trained wildlife handler attends the site or the animal relocates itself. In regards to tree pruning, works may only proceed if the animals will not come into direct harm.

- (b) In the event that the tree(s) have nesting birds or native animals, works must be delayed until after the nesting period has been completed, unless in the event of an emergency.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities on and Above Roads' and the 'Code of Practice: Construction related Temporary Structures On and Above Roads' for further information.

Reason

To ensure that wildlife is adequately protected during tree removal / pruning works.

(62) PUBLIC DOMAIN WORKS SECURITY BOND

A Public Domain Works Security Bond will be required for the public domain works and for repairing damage that may be caused to the public domain in the vicinity of the site, in accordance with the City of Sydney's adopted fees and charges and the Public Domain Manual.

The City's Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The bond must be lodged with the City prior to an approval being issued for the approval of the Public Domain Plan.

The bond will be retained in full until all public domain works, including rectification of damage to the public domain, are completed to City's standards and approval and the required works-as-executed documentation are approved. On satisfying the above requirements, and the issue of the Public Domain Works Letter of Completion Operational Acceptance by the City, 90% of the bond will be released. The remaining 10% will be retained for the duration of the specified Defects Liability Period.

Reason

To ensure public domain works are completed and any damage to the public domain is rectified.

(63) DRAINAGE AND SERVICE PIT LIDS

All existing or proposed drainage and service pit lids throughout the public domain must be to City of Sydney specifications and heel/bicycle safe, slip resistant, infill with material to match surrounding surface, finished flush with the adjacent pavement to avoid trip hazards and be clear of obstructions for easy opening and cleaning. Infill pit lids are to be detailed where specified by Council's Public Domain Officer. Private pits are not permitted within the public domain. All details of pit lids must be shown on the public domain plan and must be approved by the City's Public Domain Unit prior to the issue of an approval for public domain works.

Reason

To ensure drainage and service pit lids within the public domain are appropriately designed and installed.

(64) PUBLIC DOMAIN PLAN DETAILED DOCUMENTATION FOR CONSTRUCTION

A detailed public domain plan and all relevant documentation must be submitted to and approved by City's Public Domain Unit prior to the construction of any public domain works. This Plan must document all works required to ensure that the public domain upgrade work complies with the City's specifications and requirements, as outlined in documents such as City of Sydney's *Public Domain Manual*, *Sydney Streets Code*, *Sydney Street Tree Masterplan*, *Sydney Lights: Public Domain Design Code* and *Sydney Streets Technical Specification*. The documentation must be checked, accurate, and comply with specified requirements. Plans must be based on an accurate survey prepared, signed and dated by a registered surveyor, to scale and fully coordinated across all disciplines and submissions. The supplied documentation must be for Construction issue and will be approved under Section 138 of the Roads Act.

The Public Domain Manual and all other relevant documents are available for download from Council's website at

<https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

The Public Domain Plan documentation must be submitted with an Application for Public Domain Plan Assessment and include the approved Public Domain Levels and Gradients documentation. If the proposed detailed design of the public domain requires changes to any previously approved levels, details must be submitted for approval with the public domain plan and additional fees may apply.

Reason

To ensure the public domain complies with Council's requirements.

(65) HOLD POINTS

Prior to an approval being issued for the construction of public domain and / or planning agreement works, including civil, drainage and subsurface works, a set of hold points will be provided by the City's Public Domain Unit in accordance with the City's Public Domain Manual and Sydney Streets Technical Specification. The list of hold point inspections will be included in the Public Domain works approval letter.

These hold point inspections must be adhered to during construction works. Prior to the issue of any Occupation Certificate, confirmation from the City's Public Domain Unit, that hold point inspections have been completed and works have been accepted by the City must be provided to the Principal Certifier.

Reason

To ensure hold points are adhered to during construction works.

(66) STORMWATER DRAINAGE CONNECTION

For approval of a connection into the City of Sydney's drainage system an "*Application for Approval of Stormwater Drainage Connections*" must be

submitted to the City, together with an application fee in accordance with the City of Sydney's adopted Schedule of Fees and Charges. This must be approved prior to approval being issued for the construction of public domain work.

Reason

To ensure approval of connection into the Council's drainage system is sought.

(67) PUBLIC DOMAIN LIGHTING RETICULATION

Prior to the issue of any relevant approval for the construction of public domain works, a detailed Public Domain Lighting Reticulation Plan for pedestrian and street lighting in the public domain must be submitted to and approved by the City's Public Domain Unit in accordance with the City's *Sydney Lights Design Code*, *Sydney Streets Code*, *Sydney Streets Technical Specification* and *Public Domain Manual*.

The Public Domain Manual and all other relevant documents are available for download from Council's website at

<https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

If applicable, this public domain lighting documentation must include pole footing locations and structural details, location and details of underground electrical reticulation including connections and conduits, pit cabling and certifications as described in the City's *Public Domain Manual*. The public domain lighting is to be superimposed on the public domain plan to show any conflicts between lighting and the proposed landscape design.

Reason

To ensure the public domain lighting documentation complies with Council requirements.

(68) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.

- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on-site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Team, prior to works proceeding.

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

Note: Refer also to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To protect the amenity of the surrounding area.

(69) EROSION AND SEDIMENT CONTROL

The Soil and Water Management Plan (SWMP) or Erosion and Sediment Control Plan (ESCP) which has been approved by the Principal Certifier must be implemented in full during the construction period.

During the construction period:-

- (a) erosion and sediment controls must be regularly inspected, repaired and maintained in working order sufficient for a 10 year Average Recurrence Interval (ARI) rainfall event;
- (b) erosion and sediment control signage available from Council must be completed and attached to the most prominent structure visible at all times when entering the site for the duration of construction; and
- (c) building operations and stockpiles must not be located on the public footway or any other locations which could lead to the discharge of materials into the stormwater system.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To ensure no substance other than rainwater enters the stormwater system and waterways.

(70) HAZARDOUS AND INDUSTRIAL WASTE

Hazardous and/or industrial waste arising from the demolition/operational activities must be removed and/or transported in accordance with the requirements of the NSW Work Cover Authority pursuant to the provisions of the following:

- (a) *Protection of the Environment Operations Act 1997*
- (b) *Protection of the Environment Operations (Waste) Regulation 2005*
- (c) *Waste Avoidance and Resource Recovery Act 2001*
- (d) *Work Health and Safety Act 2011*
- (e) *Work Health and Safety Regulation 2017.*

Reason

To ensure hazardous/ industrial waste is managed appropriately.

(71) COVERING OF LOADS

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information and requirements.

Reason

To ensure loads are managed appropriately and do not impact local amenity.

(72) LOADING AND UNLOADING DURING CONSTRUCTION

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site, where possible.
- (b) If, it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.
- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.
- (d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate application under Section 68 of the Local Government Act 1993 and

Sections 138/139 of the Roads Act 1993 must be submitted to and approved by Council.

Note: Refer also to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To protect the amenity of the public domain.

(73) NO OBSTRUCTION OF PUBLIC WAY

Unless otherwise approved by Council, the public way must not be obstructed by any materials, vehicles, waste receptacles, skip-bins or the like. Non-compliance with this requirement may result in the issue of a notice by Council to stop all work on the site.

Note: Refer to the City's 'Code of Practice: Hoisting and Construction Activities On and Above Roads' for further information.

Reason

To protect the amenity of the public domain.

BEFORE ISSUE OF AN OCCUPATION CERTIFICATE

(74) PHYSICAL MODELS

- (a) Prior to the issue of any Occupation Certificate an accurate 1:500 scale model of the development as constructed must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the City Model in Town Hall House.

Note:

- (i) The models must be constructed in accordance with the Model Specifications available online at <http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements> Council's modellers must be consulted prior to construction of the model.
- (ii) The models are to comply with all of the conditions of the Development Consent.
- (iii) The models must be amended to reflect any further modifications to the approval (under Section 4.55 of the *Environmental Planning and Assessment Act*) that affect the external appearance of the building.

Reason

To ensure the provision of an appropriate physical model of the development.

(75) SUBMISSION OF ELECTRONIC CAD MODELS PRIOR TO OCCUPATION CERTIFICATE

- (a) Prior to any Occupation Certificate being issued, an accurate 1:1 electronic CAD model of the completed development must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the electronic Visualisation City Model.
- (b) The data required to be submitted within the surveyed location must include and identify:
 - (i) building design above and below ground in accordance with the development consent;
 - (ii) all underground services and utilities, underground structures and basements, known archaeological structures and artefacts;
 - (iii) a current two points on the site boundary clearly marked to show their Northing and Easting MGA (Map Grid of Australia) coordinates, which must be based on Established Marks registered in the Department of Lands and Property Information's SCIMS Database with a Horizontal Position Equal to or better than Class C.

The data is to be submitted as a DGN or DWG file on a Compact Disc. All modelling is to be referenced to the Map Grid of Australia (MGA) spatially located in the Initial Data Extraction file.

- (c) The electronic model must be constructed in accordance with the City's 3D CAD electronic model specification. The specification is available online at <http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements> Council's Modelling staff should be consulted prior to creation of the model. The data is to comply with all of the conditions of the Development Consent.

Reason

To ensure the provision of an appropriate electronic model of the development.

(76) WASTE AND RECYCLING MANAGEMENT – RESIDENTIAL

- (a) Prior to the issue of an **Occupation Certificate**, Council's review and written approval of the as-built waste infrastructure, facilities, and vehicle access is required. The City Cleansing & Resource Recovery Unit of Council must be satisfied that:
 - (i) All waste management facilities, storage, and collection infrastructure comply with the stamped plans, approved Operational Waste Management Plan and Council's *Guidelines for Waste Management in New Developments*, the City of Sydney's DCP, and the developments Conditions of Consent.
 - (ii) All waste rooms, corridors, doors, and gates to be accessed by Council's collection contractor(s) are to be fitted and accessible via Council's master key system. Specifications of locks, barrels, and supporting infrastructure are to be submitted to Council's City Cleansing & Resource Recovery Unit.
- (b) Site inspections are to be conducted by Council's City Cleansing & Resource Recovery Unit to review the site on-site waste collection, storage and loading bay infrastructure prior to the issue of an **Occupation Certificate**. The inspections are to be conducted a minimum 6-months prior to projects anticipated construction completion. Prior to the inspection an electronic copy of the latest architectural plans are to be submitted.
- (c) An updated Operational Waste Management Plan is to be submitted to Council's City Cleansing & Resource Recovery Unit that aligns with the latest version of architectural plans and waste related updates identified during the site inspections. The plan is to be reviewed by Council's City Cleansing & Resource Recovery Unit and approved by Council's Area Planning Manager prior to the issue of an **Occupation Certificate**.
- (d) The developer is to enter into a formal agreement with the City of Sydney Council for the utilisation of Council's Waste Collection Service. A signed agreement is to be submitted to Council's City Cleansing & Resource Recovery unit prior to the issue of an **Occupation Certificate**.

- (e) The assigned strata manager for the development and direct contact details are to be provided to Council's City Cleansing & Resource Recovery Unit prior to the issue of an **Occupation Certificate**.

Reason

To ensure that facilities and arrangements are in place to enable the provision of a safe and efficient waste collection service responsive to Council's policies and contractual service provisions.

(77) ADVANCE TREE PLANTING

- (a) Tree planting within the property must be to satisfaction of the City of Sydney Urban Forest Team prior to the issuing of any Occupation Certificate and in accordance with the following:
 - (i) A minimum of 4 tree(s) with a minimum container size of 100 litres must be planted. The tree species must have a minimum mature height of 6 metres and canopy spread classification of 4m. The City of Sydney Tree Species List must be used for referencing tree heights and canopy spread classifications, with further consideration of the other list attributes such as the reliability and recommended usage for urban forest, in order to select species appropriate for the site. Palms and fruit trees will only be accepted in constrained locations.
 - (iii) Tree selection must include a diverse range of species selected from the City of Sydney Tree Species List.
 - (iv) The new tree(s) must be planted in natural ground with adequate soil volumes to allow maturity to be achieved. Planter boxes will not be accepted for tree planting.
 - (v) The new tree(s) must be appropriately located away from existing buildings and structures to allow maturity to be achieved without restriction.
 - (vii) The new tree(s) must be planted at the completion of all construction works.
 - (viii) The tree(s) must be grown in accordance with Australian Standard 2303 'Trees stock for landscape use'.
 - (ix) The new tree(s) must be planted by a qualified Horticulturalist or Arborist (minimum AQF Level 3) and in such a manner as to promote good health during the establishment period, and must be maintained, as far as practicable to ensure tree growth into maturity.
 - (x) Prior to the issuing of any Occupation Certificate, suitable documentation (including a written statement and photographic evidence) is to be submitted to the City of Sydney for review and written confirmation is to be obtained from the City of Sydney Area Planning Coordinator or Area Planning Manager confirming all trees have been planted to their satisfaction (excluding tree maintenance).

- (xi) Any newly planted tree(s) which fail to establish within 2 years of the initial planting date must be replaced with tree(s) of comparable qualities, and maintained until it reaches a minimum height of 5 metres.

Reason

To ensure the provision and maintenance of adequate tree planting on site.

(78) PUBLIC DOMAIN WORKS COMPLETION

The Public Domain works are to be constructed in accordance with the Public Domain Works Approval letter, stamped plans for Public Domain Levels and Gradients, Stormwater, Public Domain Lighting, the City's *Public Domain Manual*, *Stormwater Drainage Manual*, *Sydney Lights Design Code* and *Sydney Streets Technical Specification*.

The public domain work must be inspected and a Public Domain Work Letter of Completion Operational Acceptance must be issued by Council's Public Domain Officer prior to the issue of any Occupation Certificate or before the commencement of use, whichever is earlier.

Reason

To ensure the public domain works are completed in accordance with the approved documents and Council's requirements.

(79) PUBLIC DOMAIN COMPLETION – WORK AS EXECUTED DOCUMENTATION

Prior to a Public Domain Works Letter of Completion Operational Acceptance being issued for public domain works, works-as-executed (As-Built) plans and documentation, must be submitted to and accepted by the City of Sydney for all public domain works, including where required Stormwater, Public Domain Lighting and road construction. These works must be certified by a suitably qualified, independent professional. Details of the documentation required for approval will be advised by the City's Public Domain Unit.

Reason

To ensure Council receives works-as-executed documentation for public domain works.

OCCUPATION AND ONGOING USE

(80) MANAGING NOISE

The premises must be operated and managed in accordance with the approved acoustic report for this consent.

All physical aspects of the building's structure must be installed to meet performance parameters in accordance with this condition, and requirements of this consent, must be maintained and correctly used at all times. Where

there is a conflict with the approved acoustic report and a requirement of this development consent, this consent prevails.

Reason

To protect the amenity of the local area.

(81) ON SITE LOADING AREAS AND OPERATION

All loading and unloading operations associated with servicing the site must be carried out within the confines of the site, at all times and must not obstruct other properties/units or the public way.

At all times the service vehicle docks, car parking spaces and access driveways must be kept clear of goods and must not be used for storage purposes, including garbage storage.

Reason

To maintain the orderly operation of vehicle parking areas and to ensure the public domain is kept free from physical obstructions.

(82) STACKED PARKING EMPLOYEES OR TENANTS ONLY

Any stacked parking spaces (maximum 2 spaces, nose to tail) must be attached to the same strata title comprising a single dwelling unit or commercial/retail tenancy, subject to the maximum parking limit applying. The stacked parking spaces must be designated (with appropriate signage) for employee or tenant parking only (not visitor parking), prior to any Occupation Certificate being issued. The moving of stacked vehicles must occur wholly within the property.

Reason

To maintain the orderly operation of vehicle parking areas.

(83) LOADING DOCK SCHEDULE/REGISTER

The on-site small rigid vehicle loading bay space is also to be available for all residents for use by removal vehicles, bulky good deliveries and similar. This shall be managed either by a schedule showing residents when they can use the dock, or by a register managed on site to allow residents to reserve a time period for their deliveries.

The size of vehicles accessing this loading bay must be a maximum length of 6.4m and maximum height of 2.2m.

This information is to be made available to all residents/tenants of the building.

Reason

To ensure that the loading bay space is appropriately managed.

(84) ONGOING WASTE MANAGEMENT – RESIDENTIAL

- (a) The ongoing use of development must be in accordance with the approved Operational Waste Management Plan, Council's *Guidelines for Waste Management in New Developments*, the City of Sydney's DCP, and the developments Conditions of Consent.
- (b) All general waste and recycling stream(s) materials emanating from the premises must be stored in the designated waste storage area(s) integrated within the built form and must not be stored outside the premises (including any public place) at any time.
- (c) The property manager is responsible for lodging requests for damaged/broken bins, managing the rotation of bins, ensuring the full allocation of relevant bins are available for scheduled collections, management of odour and the routine cleaning and maintenance of all waste storage areas.
- (d) Contracts (or agreements) with cleaners, building managers and tenants must clearly outline the waste management and collection arrangements, identifying clear roles and responsibilities outlined within the approved Operational Waste Management Plan.
- (e) The property manager is responsible for the installation and maintenance of all education signage for the respective waste stream(s) as requested by the City of Sydney Council responsive to the approved Operational Waste Management plan.

Reason

To support the safe and efficient scheduled Council waste collection service and ensure the impacts of waste management on the public domain and public health are minimised.

(85) MAINTENANCE OF TREES ON SITE

- (a) Tree maintenance must be implemented and complied with immediately following the tree planting, and until the tree reaches the required minimum height limit of 5 metres in height and 3 metres canopy width.
- (b) The newly planted tree on site must be appropriately maintained on an on-going basis.
- (c) Maintenance includes watering, weeding, removal of rubbish from tree bases, pruning (in accordance with AS4373), fertilizing, pest and disease control and any other operations required to maintain a healthy robust tree.
- (d) If the newly planted tree fails to establish or does not reach a height of 5 metres and canopy width of 3 metres it must be replaced with a tree of comparable qualities and container size of 100 litres.
- (e) The conditions of this consent will apply to all replacement trees, including the maintenance and reporting which re-starts at each replanting event.

Reason

To ensure the ongoing maintenance of trees planted on the site.

(86) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS

All works to the City's public domain, including rectification of identified defects, are subject to a 6 month defects liability period from the date of Completion. The date of Completion will be nominated by Council on the Public Domain Works – Letter of Completion Operational Acceptance.

Reason

To ensure all works to the City's public domain are protected under a liability period.

(87) CAR PARK VENTILATION

The car park must be ventilated in accordance with the *National Construction Code (previously known as Building Code of Australia)* and, where necessary, Australian Standard AS1668, Parts 1 and 2. Ventilation must be controlled by carbon monoxide monitoring sensors to ensure compliance with occupant health requirements.

Reason

To ensure car park ventilation complies with relevant standards.

(88) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

Reason

To protect the public way.