

Attachment A

Recommended Conditions of Consent
--

CONDITIONS OF CONSENT

SCHEDULE 1A

APPROVED DEVELOPMENT/DESIGN MODIFICATIONS/COVENANTS AND CONTRIBUTIONS/USE AND OPERATION

Note: Some conditions in Schedule 1A are to be satisfied prior to issue of a Construction Certificate and some are to be satisfied prior to issue of Occupation Certificate, where indicated.

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2017/1731 dated 13 December 2017 and the following drawings:

Drawing Number	Architect	Date
DA 01 Issue B	George El Khouri	May 2018
DA 02 Issue D	George El Khouri	July 2018
DA 04 Issue D	George El Khouri	July 2018
DA 05 Issue C	George El Khouri	July 2018
DA 06 Issue C	George El Khouri	July 2018

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the drawings will prevail.

(2) DESIGN MODIFICATIONS

The design of the building must be modified as follows:

- (a) The internal wall between the living/dining area and the bedroom in unit 15 shall be removed.
- (b) A 1.8m high privacy screen must be installed between the balconies of units 14 and 15 to minimise overlooking between the units.
- (c) 4m³ of storage shall be provided for unit 15 (studio) and 6m³ of storage shall be provided for unit 14 (1 bed).

The modifications and design details are to be submitted to and approved by Council's Area Planning Manager prior to the issue of any Construction Certificate.

(3) CONTRIBUTION TOWARDS PUBLIC AMENITIES – CITY OF SYDNEY DEVELOPMENT CONTRIBUTIONS PLAN 2015 – EAST PRECINCT

Council has identified the development will increase demand for public amenities and facilities. Pursuant to Section 7.11 of the Environmental Planning and

Assessment Act, 1979 (as amended), and the City of Sydney Development Contributions Plan 2015 the following monetary contributions are required towards the cost of public amenities.

<u>Contribution Category</u>	<u>Amount</u>
Open Space	\$16,529.80
Community Facilities	\$8,091.72
Traffic and Transport	\$518.18
Stormwater Drainage	\$0.00
Total	\$25,139.69

The City of Sydney will index the above contribution for inflation at the time of payment using the following formula.

$$C_{\text{payment}} = C_{\text{consent}} \times (CPI_{\text{payment}} \div CPI_{\text{consent}})$$

Where:

C_{payment} = Is the contribution at time of payment;

C_{consent} = Is the contribution at the time of consent, as shown above;

CPI_{payment} = Is the Consumer Price Index (All Groups Index) for Sydney published by the Australian Bureau of Statistics that applies at the time of payment; and

CPI_{consent} = Is the Consumer Price Index (All Groups Index) for Sydney at the date the contribution amount above was calculated being - 113.6 for the March 2018.

The contribution must be paid prior to the issue of any Construction Certificate in relation to this development.

Please contact Council's Planning Administration staff at planningsystemsadmin@cityofsydney.nsw.gov.au to request a letter confirming the indexed contribution amount payable.

Once the letter confirming the indexed contribution is obtained, payment may be made at any of the City's Neighbourhood Service Centres or the One Stop Shop at Town Hall House. Acceptable payment methods are EFTPOS (debit card only), cash or a bank cheque made payable to the City of Sydney. Personal or company cheques will not be accepted.

(4) ROOFLIGHTS

All rooflights are to be fully openable to achieve adequate cross ventilation. Details of the rooflights are to be submitted to and approved by Council's Area Planning Manager prior to issue of any Construction Certificate.

(5) ALTERATIONS TO UNIT 2 NOT APPROVED

The amendments to the layout and terrace of unit 2 are not approved under this development consent.

(6) MATERIALS AND SAMPLES BOARD

A materials sample board detailing all proposed external finishes must be submitted to and approved by Council's Area Planning Manager prior to any Construction Certificate being issued.

(7) RESTRICTION ON RESIDENTIAL DEVELOPMENT

The following restriction applies to buildings approved for residential use:

- (a) The accommodation must be used as permanent residential accommodation only and not for the purpose of a hotel, motel, serviced apartments, private hotel, boarding house, tourist accommodation or the like, other than in accordance with the Sydney Local Environmental Plan 2012.
- (b) A restrictive covenant is to be registered on the title of the development site in the above terms and restricting any change of use of those levels from residential accommodation as defined in the Sydney Local Environmental Plan 2012. The covenant is to be registered on title prior to an Occupation Certificate being issued or the use commencing, whichever is earlier, to the satisfaction of the Council. All costs of the preparation and registration of all associated documentation are to be borne by the applicant.
- (c) If a unit contains tenants, it must be subject to a residential tenancy agreement for a term of at least three months.
- (d) No person can advertise or organise the use of residential apartments approved under this consent for short term accommodation or share accommodation.

(8) NO AIR CONDITIONING UNITS TO FACADE OR BALCONIES OF BUILDING

Approval is not granted for the installation of individual air conditioning units to the facade or balconies of the building.

(9) BASIX CERTIFICATE – DETAILS TO BE LODGED WITH A CC

A copy of the required completed BASIX certificate accepted as part of this Development Consent with respect to the proposed residential building works, must be lodged with any application for a construction certificate and the items nominated as part of the subject BASIX certificate must be specified on the plans submitted with the construction certificate application. – See Note.

IMPORTANT NOTE:

Any requirement detailed in the accompanying BASIX Certificate, MUST be included as a specific notation or inclusion on any future Construction Certificate plans and specification in accordance with Part 3 of Schedule 1 of the EP&A Regulation, 2000.

SCHEDULE 1B

PRIOR TO CONSTRUCTION CERTIFICATE/COMMENCEMENT OF WORK/HEALTH AND BUILDING

(10) NUMBER OF ADULTS PER ROOM

- (a) No more than two adult people shall permanently occupy any bedroom and no bedroom shall contain more than two beds. This excludes children and children's beds, cots or bassinets.
- (b) The total number of adults residing in one unit shall not exceed twice the number of approved bedrooms.

(11) ACOUSTIC PRIVACY BETWEEN UNITS

- (a) The development must be designed and constructed to satisfy the requirements of the *Sydney DCP 2012* acoustic privacy requirements. A report prepared by a suitable qualified acoustic professional must be prepared and submitted to the Principal Certifier prior to the issue of a Construction Certificate, and must be suitably referenced in the Construction Certificate documentation.
- (b) The report must:-
 - (i) quantify the level of impact (noise at the exposed facades) from the normal noise of the area on the development; and
 - (ii) identify acoustic mitigation measures to be incorporated into the building design to ensure compliance with the design goals contained within the *Sydney DCP 2012*.
- (c) The Principal Certifier (PC) must ensure that the acoustic mitigation measures identified in the subject report are suitable incorporated into the development as erected prior to the issue of an Occupation Certificate.

(12) FLOOR TO CEILING HEIGHT

Prior to a Construction Certificate being issued, the Principal Certifier must ensure that all living rooms and bedrooms in sole occupancy units must have a minimum finished floor to ceiling height of not less than 2.7 metres.

(13) ASBESTOS REMOVAL WORKS

- (a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non- Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence shall be made available to any authorised Council officer on request within 24 hours.

(14) COMPLIANCE WITH BUILDING CODE OF AUSTRALIA

All proposed work must comply with the *Building Code of Australia* (BCA).

Note: The applicant's attention is drawn to the requirement of Section D of the BCA in relation to access and egress to and from the proposed level 6 units.

(15) EXTERNAL WALLS AND CLADDING FLAMMABILITY

The external walls of the building including attachments must comply with the relevant requirements of the *National Construction Code (NCC)*. Prior to the issue of a Construction Certificate and Occupation Certificate the Principal Certifier must:

- (a) Be satisfied that suitable evidence is provided to demonstrate that the products and systems proposed for use or used in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the relevant requirements of the NCC; and
- (b) Ensure that the documentation relied upon in the approval processes include an appropriate level of detail to demonstrate compliance with the NCC as proposed and as built.

(16) VENTILATION MINOR WORKS

The premises must be ventilated in accordance with the *Building Code of Australia* and AS1668.1-1998 and AS1668.2-1991.

(17) STORMWATER AND DRAINAGE - MINOR DEVELOPMENT

- (a) The drainage system is to be constructed in accordance with the City's standard requirements as detailed in the City of Sydney's Stormwater Drainage Manual, as amended from time to time.

The development is to be designed so that the flow of pollutants from the site due to stormwater is reduced.

- (b) Where a drainage system includes On-site Detention (OSD), the following requirements must be satisfied prior to the issue of any Occupation Certificate, including any Interim Occupation Certificate:
 - (i) A Positive Covenant must be registered on the title for all drainage systems involving OSD to ensure the maintenance of the approved OSD system regardless of the method of connection;
 - (ii) A Works-As-Executed survey must be prepared, signed, dated and certified by a Registered Surveyor and must be submitted to and accepted by the Principal Certifier. The Works-As-Executed plan must be overlaid on a copy of the approved stormwater drainage plans issued with the Construction Certificate, with variations to locations, dimensions, levels and storage volumes clearly marked;
 - (iii) A Hydraulic Compliance Certificate and Calculation Sheet must be prepared by a suitably qualified hydraulic engineer (minimum NER), showing approved versus installed hydraulic calculations, and must be submitted to and be accepted by the Principal Certifier;

- (iv) Evidence of Sydney Water's acceptance of the Works-As-Executed documentation, certification and Hydraulic Compliance Certificate and Calculation Sheet must be provided to the Principal Certifier;
- (v) The Principal Certifier must submit a copy of the Works-As-Executed plans, certifications, Hydraulic Compliance Certificate and Calculation Sheet to the City of Sydney.

(18) WORKS REQUIRING USE OF A PUBLIC PLACE

Where construction/building works require the use of a public place including a road or footpath, approval under Section 138 of the *Roads Act 1993* is to be obtained from Council prior to the commencement of work. Details of any barricade construction, area of enclosure and period of work are required to be submitted to the satisfaction of Council.

(19) SYDNEY WATER CERTIFICATE (TAP-IN)

- (a) The approved plans must be submitted to Sydney Water's "Tap-in" online service to determine whether the development will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. Sydney Water's "Tap-in" online service is available at www.sydneywater.com.au, (see Plumbing, Building & Development and then Sydney Water "Tap-in").
- (b) The Consent Authority or a Principal Certifier must ensure that Sydney Water has appropriately stamped the plans before the commencement of work.

(20) WASTE AND RECYCLING MANAGEMENT - MINOR

The proposal must comply with the relevant provisions of Council's *Policy for Waste Minimisation in New Developments 2005* which requires facilities to minimise and manage waste and recycling generated by the proposal.

(21) STREET TREE PROTECTION

Street trees must be protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites. All street trees must be protected during the construction works as follows:

- (a) Tree trunk and major limb protection must be undertaken prior to or during the installation of any hoarding or scaffoldings. The protection must be installed by a qualified Arborist (AFQ 2 or 3) and must include:
 - (i) An adequate clearance, minimum 250mm, must be provided between the structure and tree branches, limbs and trunk at all times;
 - (ii) Tree trunk/s and/or major branches, located within 500mm of any hoarding or scaffolding structure, must be protected by wrapped hessian or similar material to limit damage, and
 - (iii) Timber planks (50mm x 100mm or similar) must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals, and must be fixed against the trunk with tie wire, or strapping. The hessian

and timber planks must not be fixed to the tree in any instance, or in any fashion,

- (iv) Tree trunk and major branch protection is to remain in place for the duration of construction and development works, and must be removed at the completion of the project.
- (b) All hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree setts. Supporting columns must not be placed on any tree roots that are exposed.
- (c) Materials or goods, including site sheds, must not be stored or placed:
 - (i) around or under the tree canopy; or
 - (ii) within two (2) metres of tree trunks or branches of any street trees.
- (e) Any damage sustained to street tree/s as a result of the erection of hoardings, scaffolding, or due to the loading/unloading of vehicles adjacent the site, must be immediately reported to the Council's Street Tree Contract Coordinator on 9265 9333, in order to determine the appropriate action for maintaining the health and structural integrity of any damaged street tree.

SCHEDULE 1C

DURING CONSTRUCTION/PRIOR TO OCCUPATION/COMPLETION

(22) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a permit being issued by Council under Section 68 of the Local Government Act 1993 and/or Section 138 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Unit, prior to works proceeding

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

(23) ENCROACHMENTS – NEIGHBOURING PROPERTIES

No portion of the proposed structure shall encroach onto the adjoining properties.

(24) SURVEY

All footings, walls and floor slabs adjacent to a boundary must be set out by a registered surveyor. On commencement of brickwork or wall construction a survey and report, prepared by a Registered Surveyor, must be submitted to the Principal Certifier indicating the position of external walls in relation to the boundaries of the allotment. Any encroachments by the subject building over adjoining boundaries or roads must be removed prior to continuation of building construction work.

(25) SURVEY CERTIFICATE AT COMPLETION

A Survey Certificate prepared by a Registered Surveyor must be submitted at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

(26) COVERING OF LOADS

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

(27) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

(28) NO OBSTRUCTION OF PUBLIC WAY

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances. Non-compliance with this requirement will result in the issue of a notice by Council to stop all work on site.

(29) USE OF MOBILE CRANES

The following requirements apply:

- (a) Mobile cranes operating from the road must not be used as a method of demolishing or constructing a building.
- (b) For special operations including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes, permits must be obtained from Council for the use of a mobile crane. The permits must be obtained 48 hours beforehand for partial road closures which, in the opinion of Council will create minimal traffic disruptions and 4 weeks beforehand in the case of full road closures and partial road closures which, in the opinion of Council, will create significant traffic disruptions.
- (c) The use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of approved hours of construction can occur, subject to a permit being issued by Council under Section 68 of the Local Government Act 1993 and/or Section 138 of the Roads Act 1993.