

# **Attachment A**

<b>Recommended Conditions of Consent</b>
--

## CONDITIONS OF CONSENT

### SCHEDULE 1A

#### APPROVED DEVELOPMENT/DESIGN MODIFICATIONS/COVENANTS AND CONTRIBUTIONS/USE AND OPERATION

**Note:** Some conditions in Schedule 1A are to be satisfied prior to issue of a Construction Certificate and some are to be satisfied prior to issue of Occupation Certificate, where indicated.

#### (1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2019/504 dated 24 June 2019 and the following drawings prepared by Woods Bagot:

Drawing Number	Drawing Name	Date
A1010	Site Plan	10.04.2019
A2001	Demolition Plan – Urban Park Level	16.05.2019
A2002	Demolition – Kent Street Level	03.04.2019
A2212	Urban Park Level	16.05.2019
A2213	Kent Street Level	16.05.2019
A2214	Kent Street Roof Plan	02.10.2018
A5251	Facade Details – R12	03.04.2019
A5252	Facade Details – R15	03.04.2019
A2003	Demolition elevation – South Elevation	30.11.2018
A2004	Demolition Elevations – West Elevation	30.11.2018
A3230	Elevation – North Elevation	03.04.2019
A3231	Elevation – South Elevation	30.11.2018
A3232	West Elevation – Sussex Street	03.04.2019
A3233	Eastern Laneway – Internal Elevation A	30.11.2018
A3234	Eastern Laneway – Internal Elevation B	30.11.2018
A3235	Western Laneway – Internal Elevation A	30.11.2018
A3236	Western Laneway – Internal Elevation B	03.04.2019
A7000	Materials & Finishes	21.02.2019
120858	Materials & Finishes	15.05.2018
PD-SL-001	Cover Sheet	7.03.2019
PD-SL-002	Legend	26.03.2019
PS-SL-051	Removal + retention plans Sheet 1 of 2	1.04.2019
PS-SL-052	Removal + retention plans Sheet 2 of 2	7.03.2019

Drawing Number	Drawing Name	Date
PD-SL-101	General arrangement plans Sheet 1 of 2	9.04.2019
PD-SL-102	General arrangement plans Sheet 2 of 2	9.04.2019
PD-SL-201	Levels + grading plans Sheet 1 of 2	1.04.2019
PD-SL-202	Levels + grading plans Sheet 2 of 2	7.03.2019
PD-SL-601	Hardwork details - paving	7.03.2019
PD-SL-602	Hardwork details – paving junctions	
PD-SL-603	Hardwork details – stair and handrail	1.04.2019
PD-SL-604	Hardwork details – planter pots	7.03.2019
PD-SL-651	Softwork details – planter pots	7.03.2019

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the plans will prevail.

**(2) WORKS NOT APPROVED IN SUSSEX LANE**

The installation of 4 x circular steel framed planters, landscape planting and 3 x double sided concrete bench seats in Sussex Lane are not approved as part of this development consent.

**(3) SECTION 61 CONTRIBUTIONS PAYABLE - REGISTERED QUANTITY SURVEYOR'S DETAILED COST REPORT - SUBMITTED AND VERIFIED PRIOR TO ISSUE OF CONSTRUCTION CERTIFICATE**

A cash contribution comprising 1% of the total cost of the development is payable to the City of Sydney pursuant to section 61 of the *City of Sydney Act 1988* and the *Central Sydney Development Contributions Plan 2013* in accordance with the following:

- (a) Prior to a Construction Certificate being issued, evidence must be provided of Council's written verification of the amount of the contribution as required in (b) below, and then that the levy has been paid to the Council in accordance with this condition. Payment may be by EFTPOS (debit card only), CASH or a BANK CHEQUE made payable to the City of Sydney. Direct debit, personal or company cheques will not be accepted.
- (b) The contribution must not be paid to the City of Sydney until it is accompanied by separate written verification by the City of Sydney of the specific amount payable. In order to obtain such verification, the "City of Sydney Registered Quantity Surveyor's Detailed Cost Report" indicating the itemised cost of the development must be completed and submitted to

Council by the Principal Certifier, together with copies of the plans the subject of the application for the Construction Certificate. A copy of the required format for the "City of Sydney Registered Quantity Surveyor's Detailed Cost Report" may be obtained from the City of Sydney One Stop Shop, any of the Neighbourhood Service Centres and the City of Sydney's website ([www.cityofsydney.nsw.gov.au](http://www.cityofsydney.nsw.gov.au)).

- (c) The Council will consider the documentation submitted under subclause (b) and determine the cost of the proposed development having regard to the information submitted and to such other matters as it considers appropriate and will notify the Principal Certifier accordingly.
- (d) The items to be included in the calculation of the cost of development are demolition works, site remediation including decontamination, excavation and site preparation, construction costs, fit out, professional fees as part of the design (including design competitions) documentation and implementation process, fixed building machinery, equipment and appliances, kitchens and bar areas, car parking, air conditioning plant and equipment, services (fire, mechanical ventilation, electrical, hydraulic), ceilings, fire protection devices, installation of services (power, water, sewer, telephone), lifts and other essential machinery, floor coverings, *Building Code of Australia* compliance works, replacement of existing materials, fixtures and fittings, construction related insurance, assessment and construction related fees, charges and GST and any other matter not expressly excluded in (e) below. Any item for which an exemption has been granted is still to be included in the total cost of development, together with an itemised value to enable the City to calculate the value of the exemption.
- (e) The items to be excluded in the calculation of the cost of development are the cost of land, marketing expenses (excluding display suites etc), finance and interest, building insurance after practical completion, drapery, commercial stock inventory, loose furniture, loose equipment, loose electrical appliances, minor maintenance of existing retained fixtures (patching, repainting) and stamp duty.

Please contact Council's Planning Administration staff at [Planningsystemsadmin@cityofsydney.nsw.gov.au](mailto:Planningsystemsadmin@cityofsydney.nsw.gov.au) to confirm the amount payable, prior to payment.

#### **(4) STREET TREE PROTECTION**

Street trees must be protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites. All street trees must be protected during the construction works as follows:

- (a) Tree trunk and major limb protection must be undertaken prior to or during the installation of any hoarding or scaffoldings. The protection must be installed by a qualified Arborist (AFQ 2 or 3) and must include:
  - (i) An adequate clearance, minimum 250mm, must be provided between the structure and tree branches, limbs and truck at all times;
  - (ii) Tree trunk/s and/or major branches, located within 500mm of any hoarding or scaffolding structure, must be protected by wrapped hessian or similar material to limit damage, and

- (iii) Timber planks (50mm x 100mm or similar) must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals, and must be fixed against the trunk with tie wire, or strapping. The hessian and timber planks must not be fixed to the tree in any instance, or in any fashion,
  - (iv) Tree trunk and major branch protection is to remain in place for the duration of construction and development works, and must be removed at the completion of the project.
- (b) All hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree setts. Supporting columns must not be placed on any tree roots that are exposed.
- (c) Materials or goods, including site sheds, must not be stored or placed:
- (i) around or under the tree canopy; or
  - (ii) within two (2) metres of tree trunks or branches of any street trees.
- (d) Protective fencing (1.8 metre chain wire mesh fencing) must be erected on top of the hoarding [Tree Management Team to insert location of hoarding and affected trees] to protect branches during the construction works.
- (e) Any damage sustained to street tree/s as a result of the erection of hoardings, scaffolding, or due to the loading/unloading of vehicles adjacent the site, must be immediately reported to the Council's Street Tree Contract Coordinator on 9265 9333, in order to determine the appropriate action for maintaining the health and structural integrity of any damaged street tree.

## **SCHEDULE 1B**

### **PRIOR TO CONSTRUCTION CERTIFICATE/COMMENCEMENT OF WORK/HEALTH AND BUILDING**

#### **(5) LIAISON OF CONSTRUCTION PROGRAM WITH AFFECTED NEIGHBOURS**

Prior to the commencement of construction works, the contractor is must contact and liaise with affected property owners/occupiers to address and mitigate construction impacts on the operation of surrounding commercial tenancies.

#### **(6) ACCESS AND FACILITIES FOR PERSONS WITH DISABILITIES**

The building must be designed and constructed to provide access and facilities for people with a disability in accordance with the *Building Code of Australia*.

If, in complying with this condition, amendments to the development are required, the design changes must be submitted to and approved by Council prior to a Construction Certificate being issued.

#### **(7) CONSTRUCTION PEDESTRIAN AND TRAFFIC MANAGEMENT PLAN / TRANSPORT FOR NSW CONDITION**

(a) A detailed Construction Pedestrian and Traffic Management Plan (CPTMP) must be prepared in consultation with the submitted to and approved by the Sydney Coordination Office within Transport for NSW (TfNSW). The CPTMP needs to specify, but not limited to, the following:

- (i) Location of any proposed work zone(s), noting Kent Street is not a suitable location;
- (ii) Location of any crane(s);
- (iii) Haulage routes;
- (iv) A detailed plan identifying all construction vehicle access arrangements;
- (v) Estimated number of construction vehicle movements, including measures to reduce the number of movements during the AM and PM peak periods;
- (vi) Measures to avoid construction worker vehicle movements within the CBD;
- (vii) Construction program;
- (viii) Proposed construction hours;
- (ix) Consultation strategy for liaison with surrounding stakeholders, including other developments;

- (x) Any potential impacts to general traffic, cyclists, pedestrians and bus and light rail services within the vicinity of the site from the construction of the development;
  - (xi) Cumulative construction impacts of the development, Sydney Light Rail Project, Sydney Metro City and Southwest and other developments, including D/2016/1059. Existing CPTMPs for developments within or around the development site should be referenced in the CPTMP to ensure that coordination of work activities are managed to minimise impacts on the CBD road network; and
  - (xii) Proposed mitigation measures. Should any impacts be identified, the duration of the impacts and measures proposed to mitigate any associated general traffic, public transport, pedestrian and cyclist impacts should be clearly identified and included in the CPTMP.
- (b) Prior to the issue of any construction certificate or any preparatory, demolition or excavation works, whichever is the earlier, the applicant must provide the builder's direct contact number to small businesses adjoining or impacted by the construction work and the Transport Management Centre and Sydney Coordination Office within Transport for NSW to resolve issues relating to traffic, public transport, freight, servicing and pedestrian access during construction in real time. The applicant is responsible for ensuring the builder's direct contact number is current during any stage of construction.
  - (c) The applicant shall submit a copy of the final plan to the Coordinator General, Transport Coordination within TfNSW for endorsement, prior to the issue of any construction certificate or any preparatory, demolition or excavation works, whichever is the earlier.
  - (d) A Construction Pedestrian and Traffic Management Plan must be submitted to and approved by Council prior to a Construction Certificate being issued.

**(8) ALIGNMENT LEVELS – MAJOR DEVELOPMENT**

- (a) Proposed building floor levels, basement levels, basement car park entry levels and ground levels shown on the approved Development Application plans are indicative only and have not been approved by this consent.
- (b) Prior to a Construction Certificate being issued for any excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work, alignment levels for the building and site frontages must be submitted to and approved by Council. The submission must be prepared by a Registered Surveyor and designed by a suitably qualified engineer, must be in accordance with the City of Sydney's *Public Domain Manual* and must be submitted with a completed-and Levels and Gradients Approval Application form (available on the City's website).
- (c) These alignment levels, as approved by Council, are to be incorporated into the plans submitted with the application for a Construction Certificate for any civil, drainage and public domain work as applicable under this consent. If the proposed detailed design of the public domain requires changes to any previously approved Alignment Levels, then an amended Alignment Levels submission must be submitted to and approved by Council to reflect these

changes prior to a Construction Certificate being issued for public domain work

**(9) PAVING MATERIALS**

The surface of any material used or proposed to be used for the paving of colonnades, thoroughfares, plazas, arcades and the like which are used by the public must comply with AS/NZS 4586:2004 (including amendments) "Slip resistance classification of new pedestrian surface materials".

**(10) PHOTOGRAPHIC RECORD / DILAPIDATION REPORT - PUBLIC DOMAIN**

Prior to an approval for demolition being granted or a Construction Certificate being issued, whichever is earlier, a photographic recording of the public domain site frontages is to be prepared and submitted to Council's satisfaction.

The recording must include clear images of the building facade adjoining the footpath, the footpath, nature strip, kerb and gutter, driveway crossovers and laybacks, kerb ramps, road carriageway, street trees and plantings, parking restriction and traffic signs, and all other existing infrastructure along the street.

The form of the recording is to be as follows:-

- (a) A PDF format report containing all images at a scale that clearly demonstrates the existing site conditions;
- (b) Each image is to be labelled to identify the elements depicted, the direction that the image is viewed towards, and include the name of the relevant street frontage;
- (c) Each image is to be numbered and cross referenced to a site location plan;
- (d) A summary report, prepared by a suitable qualified professional, must be submitted in conjunction with the images detailing the project description, identifying any apparent existing defects, detailing the date and authorship of the photographic record, the method of documentation and limitations of the photographic record;
- (e) Include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

Any damage to the public way including trees, footpaths, kerbs, gutters, road carriageway and the like must immediately be made safe and functional by the applicant. Damage must be fully rectified by the applicant in accordance with the City's standards prior to a Certificate of Completion being issued for Public Domain Works or before an Occupation Certificate is issued for the development, whichever is earlier.



## **(11) PRESERVATION OF SURVEY MARKS**

All works in City streets must ensure the preservation of existing permanent survey marks (a brass bolt, or a lead plug holding a brass tack, covered by a cast iron box). At least forty-eight hours prior to the commencement of any works in the public way within 1 metre of a permanent survey mark contact must be made with the City's Project Manager Survey / Design Services to arrange for the recovery of the mark.

Prior to the issue of a Construction Certificate, a survey plan, clearly showing the location of all permanent survey marks fronting the site and within 5 metres on each side of the frontages must be submitted to Council.

At least forty-eight hours prior to the commencement of any works in the public way within 1 metre of a permanent survey mark contact must be made with the City's Senior Surveyor to arrange for the recovery of the mark.

A fee must be paid to the Council for the replacement of any permanent survey mark removed or damaged in accordance with the City's Schedule of Fees and Charges (Reinstatement of Survey Box).

## **(12) PROTECTION OF SURVEY INFRASTRUCTURE**

Prior to the commencement of any work on site, a statement prepared by a Surveyor registered under the *Surveying and Spatial Information Act 2002* must be submitted to Council verifying that a survey has been carried out in accordance with the Surveyor General's Direction No. 11 – Reservation of Survey Infrastructure. Any Permanent Marks proposed to be or have been destroyed must be replaced, and a "Plan of Survey Information" must be lodged at the NSW Land Registry Services.

Reason: To ensure that the survey control infrastructure and cadastral framework are preserved for the public benefit and in accordance with the *Surveying and Spatial Information Act 2002*.

## **(13) PUBLIC DOMAIN PLAN**

- (a) A detailed Public Domain Plan must be prepared by a suitably qualified architect, urban designer, landscape architect or engineer and must be lodged with Council's Public Domain Section and be approved by Council prior to a Construction Certificate being issued for public domain work or above ground building work, whichever is later.
- (b) The Public Domain Plan must document all works required to ensure that the public domain complies with the City of Sydney's *Public Domain Manual*, *Sydney Streets Code* and *Sydney Streets Technical Specification*, including requirements for road pavement, traffic measures, footway pavement, kerb and gutter, drainage, vehicle crossovers, pedestrian ramps, lighting, street trees and landscaping, signage and other public domain elements. If an Alignment Levels condition applies to the development, the Public Domain Plan submission must incorporate the approved Alignment Levels. If the proposed detailed design of the public domain requires changes to any previously approved Alignment Levels, then an amended Alignment Levels submission must be submitted to and approved by Council to reflect these

changes prior to a Construction Certificate being issued for public domain work.

- (c) The works to the public domain are to be completed in accordance with the approved Public Domain Plan and Alignment Levels plans and the *Public Domain Manual* before any Occupation Certificate is issued in respect of the development or before the use commences, whichever is earlier.

#### **(14) PUBLIC DOMAIN WORKS BOND**

Public Domain Works Deposit will be required as security for the public domain works and for repairing damage that may be caused to the public domain in the vicinity of the site, in accordance with the City of Sydney's adopted fees and charges and the Public Domain Manual. The Public Domain Works Deposit must be submitted as an unconditional bank guarantee or insurance bond as per the Council's Performance Bond Policy in favour of Council as security for completion of the obligations under this consent (Guarantee).

Council's Public Domain section must be contacted to determine the guarantee amount prior to lodgement of the guarantee. The guarantee must be lodged with Council prior to a Construction Certificate being issued.

The Guarantee will be retained in full until all Public Domain works, including rectification of damage to the public domain, are completed to City of Sydney standards and approval and the required certifications, warranties and works-as-executed documentation are submitted and approved by Council in writing. On satisfying the above requirements, 90% of the security will be released. The remaining 10% will be retained for the duration of the specified Defects Liability Period.

#### **(15) PUBLIC DOMAIN WORKS – HOLD POINTS AND HANDOVER**

- (a) Prior to a Construction Certificate being issued for public domain work, including civil, drainage and subsurface works, a set of hold points for approved public domain, civil and drainage work is to be determined with and approved by the City's Public Domain section in accordance with the City of Sydney's *Public Domain Manual* and *Sydney Streets Technical Specification*.
- (b) Prior to a Certificate of Completion being issued for public domain works and before the issue of any Occupation Certificate for the development or before the use commences, whichever is earlier, electronic works-as-executed (as-built) plans and documentation, certified by a suitably qualified, independent professional must be submitted to and accepted by Council for all public domain works. Completion and handover of the constructed public domain works must be undertaken in accordance with the City of Sydney's *Public Domain Manual* and *Sydney Streets Technical Specification*, including requirements for as-built documentation, certification, warranties and the defects liability period.

## **(16) STORMWATER AND DRAINAGE - MINOR DEVELOPMENT**

- (a) The drainage system is to be constructed in accordance with the City's standard requirements as detailed in the City of Sydney's Stormwater Drainage Manual, as amended from time to time.

The development is to be designed so that the flow of pollutants from the site due to stormwater is reduced.

- (b) For approval of a connection into the City of Sydney's drainage system an "Application for Approval of Stormwater Drainage Connections" must be submitted to the City, together with an application fee in accordance with the City of Sydney's adopted Schedule of Fees and Charges.
- (c) The application must be approved by the City of Sydney prior to an approval or Construction Certificate being issued for excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work.
- (d) All proposed connections to the City's underground drainage system require the owner to enter into a Deed of Agreement with the City of Sydney and obtain registration on Title of a Positive Covenant prior to an Occupation Certificate being issued, including an Interim Occupation Certificate.
- (e) Where a drainage system includes On-site Detention (OSD), the following requirements must be satisfied prior to the issue of any Occupation Certificate, including any Interim Occupation Certificate:
  - (i) A Positive Covenant must be registered on the title for all drainage systems involving OSD to ensure the maintenance of the approved OSD system regardless of the method of connection;
  - (ii) A Works-As-Executed survey must be prepared, signed, dated and certified by a Registered Surveyor and must be submitted to and accepted by the Principal Certifier. The Works-As-Executed plan must be overlaid on a copy of the approved stormwater drainage plans issued with the Construction Certificate, with variations to locations, dimensions, levels and storage volumes clearly marked;
  - (iii) A Hydraulic Compliance Certificate and Calculation Sheet must be prepared by a suitably qualified hydraulic engineer (minimum NER), showing approved versus installed hydraulic calculations, and must be submitted to and be accepted by the Principal Certifier;
  - (iv) Evidence of Sydney Water's acceptance of the Works-As-Executed documentation, certification and Hydraulic Compliance Certificate and Calculation Sheet must be provided to the Principal Certifier;

- (v) The Principal Certifier must submit a copy of the Works-As-Executed plans, certifications, Hydraulic Compliance Certificate and Calculation Sheet to the City of Sydney.

**(17) STRUCTURAL CERTIFICATION FOR EXISTING BUILDING – ALTERATIONS AND ADDITIONS**

A qualified practising certified structural engineer must provide structural certification to Council (where Council is the Certifying Authority) verifying that the existing structure can adequately support the proposed new loads and the structural design complies with the Structural Provisions of Part B1 (Vol 1) and Part 2.1 (Vol 2) of the Building Code of Australia prior to a Construction Certificate being issued. The proposed additional loads and/or alterations must not cause a decrease in the existing structural performance of the building.

**(18) EXTERNAL WALLS AND CLADDING FLAMMABILITY**

The external walls of the building including attachments must comply with the relevant requirements of the *National Construction Code (NCC)*. Prior to the issue of a Construction Certificate and Occupation Certificate the Principal Certifier must:

- (a) Be satisfied that suitable evidence is provided to demonstrate that the products and systems proposed for use or used in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the relevant requirements of the NCC; and
- (b) Ensure that the documentation relied upon in the approval processes include an appropriate level of detail to demonstrate compliance with the NCC as proposed and as built.

**(19) PRODUCTS BANNED UNDER THE BUILDING PRODUCTS (SAFETY) ACT 2017**

- (a) No building products that are banned, or products that are subject to a ban if used in a particular way, under the Building Products (Safety) Act 2017 are to be used in the construction of the development approved in this development consent.
- (b) Prior to the issue of any Occupation Certificate, the principal certifier is to confirm that none of the building products used on the building are subject to a building product use ban under the Building Products (Safety) Act 2017 or, if a product is only subject to a ban if used in a particular way that it is not used in any way contrary to the Building Products (Safety) Act 2017.

**(20) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS**

All works to the City's public domain, including rectification of identified defects, are subject to a 6 month defects liability period from the date of final completion. The date of final completion will be nominated by Council on the Certificate of Practical Completion for public domain works.

## **(21) DRAINAGE AND SERVICE PIT LIDS**

Drainage and service pit lids throughout the public domain shall be heelguard and bicycle safe, finish flush with the adjacent pavement to avoid trip hazards and be clear of obstructions for easy opening and cleaning. Pit lids shall be in accordance with the *City of Sydney's Sydney Streets Design Code* and *Sydney Streets Technical Specification*. Details of drainage and service pit lids shall be submitted and approved by Council prior to a Construction Certificate being issued for the relevant stage of work.

## **(22) PROTECTION OF STONE KERBS**

- (a) The existing stone kerbs on the Sussex and Kent St frontages of the site are to be retained and properly protected during excavation and construction works.
- (b) To avoid damage to stone kerbs during excavation and construction works for the development, temporary removal and storage of the stone kerbs may be approved by Council. Removed, serviceable stone kerbs (i.e. those that are in good condition as agreed by Council officers) must be re-installed in accordance with the City of Sydney's standard details and specifications after the construction works have been completed. Note: A temporary concrete kerb will need to be constructed to retain the footpath until the stone kerbs can be reinstalled. The removed stone kerbs are to be reinstalled prior to the issue of an Occupation Certificate. Note: all costs associated with the works are to be at no cost to the Council.
- (c) Damaged kerbs are to be replaced to match existing to Council's satisfaction or as otherwise advised by Council officers.
- (d) Where new crossings or temporary crossings are to be constructed to access the property, the affected kerb stones should be salvaged and reused wherever possible.
- (e) All new driveway laybacks and kerbs are to be constructed with stone kerbs to match existing stones or as specified by City officers. All unused stone kerbs are to be salvaged and returned to the City's store.
- (f) Council approval is required before kerbs are removed.
- (g) Council approval is required prior to the cutting of existing stone kerbs for stormwater kerb outlets.

## **(23) PUBLIC DOMAIN DAMAGE DEPOSIT (MODIFIED)**

- (a) A Public Domain Damage Deposit calculated on the basis of 66 square metres of asphalt, Kent St and Sussex St frontages, 330 square meters of asphalt, Sussex Lane site frontage must be lodged with Council in accordance with the City of Sydney's adopted Schedule of Fees and Charges. The Public Domain Damage Deposit must be submitted as an unconditional bank guarantee or insurance bond as per the Council's Performance Bond Policy in favour of Council as security for repairing any damage to the public domain in the vicinity of the site (Guarantee).

- (b) The Guarantee must be lodged with Council prior to an approval for demolition being granted or a Construction Certificate being issued, whichever is earlier.
- (c) The Guarantee in this condition will be retained in full until the Public Domain Works Deposit Guarantee required by this consent is lodged with Council. Upon lodgement of the Public Domain Works Deposit Guarantee, the Guarantee in this condition will be released.

**(24) TACTILE GROUND SURFACE INDICATORS AND HANDRAILS**

All tactile ground surface indicators, handrails and other elements required to provide access into the building / property must be located entirely within the private property boundary.

**(25) ENCROACHMENTS – PUBLIC WAY**

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

**(26) WORKS REQUIRING USE OF A PUBLIC PLACE**

Where construction/building works require the use of a public place including a road or footpath, approval under Section 138 of the *Roads Act 1993* is to be obtained from Council prior to the commencement of work. Details of any barricade construction, area of enclosure and period of work are required to be submitted to the satisfaction of Council.

**(27) WASTE AND RECYCLING MANAGEMENT - MINOR**

The proposal must comply with the relevant provisions of Council's *Guidelines for Waste Management in New Developments 2018* which requires facilities to minimise and manage waste and recycling generated by the proposal.

## SCHEDULE 1C

### DURING CONSTRUCTION/PRIOR TO OCCUPATION/COMPLETION

#### **(28) OCCUPATION CERTIFICATE TO BE SUBMITTED**

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

#### **(29) HOURS OF WORK AND NOISE – CBD**

The hours of construction and work on the development must be as follows:

- (a) All work, including demolition, excavation and building work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.00am and 7.00pm on Mondays to Fridays, inclusive, and 7.00am and 5.00pm on Saturdays, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the *City of Sydney Code of Practice for Construction Hours/Noise 1992* and Australian Standard 2436-2010 *Guide to Noise Control on Construction, Maintenance and Demolition Sites*.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a permit being issued by Council under Section 68 of the Local Government Act 1993 and/or Section 138 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Unit, prior to works proceeding.

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

#### **(30) LOADING AND UNLOADING DURING CONSTRUCTION**

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site.
- (b) If it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.

- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.
- (d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate approval under Section 68 of the Local Government Act 1993 must be obtained.

**(31) NO OBSTRUCTION OF PUBLIC WAY**

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances. Non-compliance with this requirement will result in the issue of a notice by Council to stop all work on site.

**(32) ENCROACHMENTS – NEIGHBOURING PROPERTIES**

No portion of the proposed structure shall encroach onto the adjoining properties.

**(33) SURVEY**

All footings, walls and floor slabs adjacent to a boundary must be set out by a registered surveyor. On commencement of brickwork or wall construction a survey and report, prepared by a Registered Surveyor, must be submitted to the Principal Certifier indicating the position of external walls in relation to the boundaries of the allotment. Any encroachments by the subject building over adjoining boundaries or roads must be removed prior to continuation of building construction work.

**(34) SURVEY CERTIFICATE AT COMPLETION**

A Survey Certificate prepared by a Registered Surveyor must be submitted at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

**(35) COVERING OF LOADS**

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.



## SCHEDULE 2

### PRESCRIBED CONDITIONS

The prescribed conditions in accordance with Division 8A of the *Environmental Planning and Assessment Regulation 2000* apply:

- Clause 98 Compliance with *Building Code of Australia* and insurance requirements under the *Home Building Act 1989*
- Clause 98A Erection of signs
- Clause 98B Notification of *Home Building Act 1989* requirements
- Clause 98C Conditions relating to entertainment venues
- Clause 98D Conditions relating to maximum capacity signage
- Clause 98E Conditions relating to shoring and adequacy of adjoining property

Refer to the NSW State legislation for full text of the clauses under Division 8A of the *Environmental Planning and Assessment Regulation 2000*. This can be accessed at: <http://www.legislation.nsw.gov.au>