Attachment A

Recommended Conditions of Consent

CONDITIONS OF CONSENT

SCHEDULE 1A

APPROVED DEVELOPMENT/DESIGN MODIFICATIONS/COVENANTS AND CONTRIBUTIONS/USE AND OPERATION

Note: Some conditions in Schedule 1A are to be satisfied prior to issue of a Construction Certificate and some are to be satisfied prior to issue of Occupation Certificate, where indicated.

(1) APPROVED DEVELOPMENT

(a) Development must be in accordance with Development Application No. D/2019/291 dated 26 March 2019 and the following drawings prepared by Andrew Burns Architects:

Drawing Number	Drawing Name	Date
1709-DA01-E	Register/Location Plan/Site Analysis	15 January 2020
1709-DA02-E	Site Plan/Context Elevation	20 December 2019
1709-DA03-E	Ground/First Floor Plan	20 December 2019
1709-DA04-E	Attic/Roof Plan	20 December 2019
1709-DA05-F	Elevations/Sections	15 January 2020
1709-DA06-F	Elevations/Sections	15 January 2020
1709-DA12-D	Window Schedule	10 January 2020

and as amended by the conditions of this consent.

(b) In the event of any inconsistency between the approved plans and supplementary documentation, the plans will prevail.

(2) SECTION 7.11 CONTRIBUTIONS PAYABLE - CONTRIBUTION TOWARDS PUBLIC AMENITIES – CITY OF SYDNEY DEVELOPMENT CONTRIBUTIONS PLAN 2015 – SOUTH PRECINCT

Council has identified the development will increase demand for public amenities and facilities. Pursuant to Section 7.11 of the Environmental Planning and Assessment Act, 1979 (as amended), and the City of Sydney Development Contributions Plan 2015 the following monetary contributions are required towards the cost of public amenities.

Contribution Category

<u>Amount</u>

Open Space	\$40,548.63
Community Facilities	\$9,672.12
Traffic and Transport	-\$26,975.94
Stormwater Drainage	-\$10,665.22
Total	\$12,579.60

The City of Sydney will index the above contribution for inflation at the time of payment using the following formula.

Cpayment	= Cconsent x (CPIpayment ÷ CPIconsent)
Where:	
Cpayment	= Is the contribution at time of payment;
Cconsent	= Is the contribution at the time of consent, as shown above;
CPIpayment	= Is the Consumer Price Index (All Groups Index) for Sydney published by the Australian Bureau of Statistics that applies at the time of payment; and
CPI1consent	 Is the Consumer Price Index (All Groups Index) for Sydney at the date the contribution amount above was calculated being – 117.1 for the December 2019 quarter.

The contribution must be paid prior to the issue of any Construction Certificate in relation to this development.

Please contact Council's Planning Administration staff at planningsystemsadmin@cityofsydney.nsw.gov.au to request a letter confirming the indexed contribution amount payable.

Once the letter confirming the indexed contribution is obtained, payment may be made at any of the City's Neighbourhood Service Centres or the One Stop Shop at Town Hall House. Acceptable payment methods are EFTPOS (debit card only), cash (up to 10K only), Credit Card (up to 50K only) or a bank cheque made payable to the City of Sydney. Personal or company cheques will not be accepted.

The contribution may be offset in accordance with the requirements and obligations identified in the Planning Agreement dated 25 July 2017 between The Council of the City of Sydney, Greenland Golden Horse Investment Pty Ltd and The Trust Company Limited.

(3) COMPLIANCE WITH VOLUNTARY PLANNING AGREEMENT

The development must be carried out in accordance with all of the obligations referenced within the Planning Agreement executed on 25 July 2017 and entered into by The Council of the City of Sydney, Greenland Golden Horse Investment Pty Ltd as trustee for The Greenland Golden Horse Investment Trust and The Trust Company Limited as custodian for the Goodman Industrial Europe Finance Trust.

(4) BASIX CERTIFICATE

- (a) A copy of the required completed BASIX certificate (Certificate number 901147M_06) accepted as part of this Development Consent with respect to the proposed residential building works, must be lodged with an application for a construction certificate and the items nominated as part of the subject BASIX certificate must be specified on the plans submitted with the construction certificate application. – See Note.
- (b) All rainwater tanks must be connected to toilets as stated in the BASIX certificate.
- (c) The NatHERS Certificates listed in Appendix C of the revised BASIX and ESD report prepared by Wood & Grieve Engineers dated 24 January 2020 are to be provided to the Certifier prior to the issue of any Construction Certificate for above ground works.

IMPORTANT NOTE:

Any requirement detailed in the accompanying BASIX Certificate, MUST be included as a specific notation or inclusion on any future Construction Certificate plans and specification in accordance with Part 3 of Schedule 1 of the EP&A Regulation, 2000.

(5) WASTE TRUCK TURNING ON METTERS STREET

Waste trucks are not permitted to enter Kooka Walk at any time. The public domain plans must not identify the bollards at the end of Copper Smith Lane and Metters Street as removable to accommodate vehicle turning.

(6) MODIFICATIONS TO PLANS

- (a) The maximum permitted height of east and west boundary fences (adjoining Kooka Walk and Copper Smith Lane respectively) beyond the northern elevation of the dwellings is 1.8 metres, measured from the adjoining public domain alignment level. The plans is to be amended and submitted to the satisfaction of Council's Area Planning Manager/Area Planning Coordinator prior to the issue of any Construction Certificate for above ground works.
- (b) The plans are to be amended to be consistent with the elevations regarding the window types to the east and west elevations to the satisfaction of the Principal Certifier prior to the issue of any Construction Certificate.

(7) LANDSCAPING OF THE SITE

- (a) A detailed landscape plan, drawn to scale, by a qualified landscape architect or landscape designer, must be submitted to and approved by Council's Director City Planning, Development and Transport prior to the issue of any Construction Certificate for above ground building works. The plan must include:
 - (i) One small tree with a minimum mature height of 6-8 metres within the front setback of every dwelling. The hardstand and bin storage areas are to be minimised to maximise soil volume.

Note: the species is to meet the definition of a small tree at page 37 of the City's Landscape Code Volume 2.

- (ii) A minimum of three small trees with a minimum mature height of 6-8 metres on the roof the dwellings.
- (iii) At the time of planting trees are to have a minimum container size of 200 litres and a minimum height of 3 metres.
- (iv) New trees must be planted in natural ground with adequate soil volumes to allow maturity to be achieved. Planter boxes will not be accepted for tree planting at ground level.
- (v) New trees must not be tied or fixed to stakes.
- (vi) Location of existing and proposed structures on the site including, but not limited to, existing and proposed trees, paved areas, planted areas on slab, planted areas in natural ground, lighting and other features.
- (vii) Details of earthworks and soil depths including mounding and retaining walls and planter boxes (if applicable). The minimum soil depths for planting on slab must be 1000mm for trees, 450mm for shrubs and 200mm for groundcovers.
- (viii) Details of soil build up on ground level above the remediation marker layer.
- (ix) Location, numbers, type and supply of plant species, with reference to Australian Standards.
- (x) Details of planting procedure and maintenance.
- (xi) Details of drainage, waterproofing and watering systems.
- (b) Prior to the issue of a Construction Certificate, a maintenance plan is to be submitted to and approved by the Accredited Certifier. The maintenance plan is to be complied with during occupation of the property.
- (c) All landscaping in the approved plan is to be completed prior to any Occupation Certificate (including interim) being issued.

(8) URBAN ECOLOGY

- (a) A revised flora and fauna assessment is to be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager in conjunction with the submission of documents to satisfy condition 7. This assessment must include:
 - A report on species of particular conservation significance, such as threatened and/or locally significant species identified in the Urban Ecology Strategic Action Plan.
 - (ii) Mitigation measures to minimise impacts on these species, including habitat provision for locally significant species such as

(but not limited to) small birds like the fairy wren and New Holland honeyeaters, reptiles and invertebrates.

(b) The requirements detailed in this report must be fully incorporated into the landscape designs and submitted for approval with condition 7.

(9) COMPLIANCE WITH THE ACOUSTIC REPORT PRIOR TO CONSTRUCTION AND OR OCCUPATION CERTIFICATES

- (a) All relevant performance parameters (including but not limited to requirements, engineering assumptions and recommendations) in the DA Acoustic Report prepared by c)Acoustic Report, prepared by Wood & Grieve Engineers, dated 01/03/2019 and referenced 30073-2 (TRIM REFERENCE: 2019/150574) must be implemented in the development prior to the commencement of its use.
- (b) Prior to the issue of any relevant Construction Certificate, the final construction drawings and final construction methodology must be assessed and reported to be in accordance with the requirements of the DA Acoustic Report in (a) above, with reference to relevant documentation. This must be done by a Suitably Qualified Acoustic Consultant* (see definition below). This work will be to the satisfaction of the certifier.
- (c) Prior to the issue of any Occupation Certificate, a Suitably Qualified Acoustic Consultant* is to provide a written Acoustic Verification Report to the satisfaction of the Principal Certifier/Principal certifying Authority that the development complies with the requirements set out in the Report and in (a) and (b) above.

Note: *Suitably Qualified Acoustic Consultant* means a consultant who possesses the qualifications to render them eligible for membership of the Australian Acoustics Society, Institution of Engineers Australia or the Association of Australian Acoustic Consultants at the grade of member.

(d) All physical aspects of the building's structure installed in order to meet performance parameters in accordance with this condition must be maintained at all times.

(10) DEMOLITION, EXCAVATION AND CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

A site specific noise management plan shall be submitted to the Council for comment and approval prior to issue of any Construction Certificate.

The Plan must be prepared by a suitably qualified person who possesses the qualifications to render them eligible for membership of the Australian Acoustic Society, Institution of Engineers Australia or the Australian Association of Acoustic Consultants.

The plan must include but not be limited to the following:-

- (a) identification of noise sensitive receivers near to the site.
- (b) A prediction as to the level of noise impact likely to affect the nearest noise sensitive receivers from the use and proposed number of high

noise intrusive appliances intended to be operated onsite. A statement should also be submitted outlining whether or not predicted noise levels will comply with the noise criteria stated within the *City of Sydney Construction Hours /Noise Code of Practice 1992* for the typical construction hours of 07.00am to 7.00pm. Where resultant site noise levels are likely to be in exceedance of this noise criteria then a suitable proposal must be given as to the duration and frequency of respite periods that will be afforded to the occupiers of neighbouring property.

- (c) A representative background noise measurement (L_{A90, 15 minute}) should be submitted, assessed in the vicinity of any potentially affected receiver locations and measured in accordance with AS 1055:1.2.1997.
- (d) Confirmation of the level of community consultation that has/is and will be undertaken with Building Managers/ occupiers of the main adjoining noise sensitive properties likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.
- (e) Confirmation of noise monitoring methodology that is to be undertaken during the main stages of work at neighbouring noise sensitive properties in order to keep complaints to a minimum and to ensure that noise from site works complies with the noise criteria contained within City's Construction Noise Code.
- (f) What course of action will be undertaken following receipt of a complaint concerning offensive noise.
- (g) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupiers of neighbouring noise sensitive property to a minimum.
- (h) What plant and equipment is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on the occupiers of neighbouring property and other less intrusive technologies available.

(11) COMPLIANCE WITH DEMOLITION, EXCAVATION & CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

- (a) All works conducted on site which form part of this development must be carried out in accordance with the demolition, excavation and construction noise management plan that is to be submitted to the Councils Health and Building department for approval.
- (b) Where all such control measures have been implemented and the resultant noise and/ or vibration levels at any sensitive receiver still exceed the council's applicable criteria stated in the Construction Hours/Noise Code 1992 and are giving rise to sustained complaints then the contractor must provide regular, appropriate and sustained periods of respite in consultation with Council's Health and Building unit. Approval to vary the authorised noise and vibration levels must be received in writing by the proponent from Council prior to activities being

undertaken that exceed sanctioned emission levels. (Use where respite periods not specified under the approved DEC NMP)

Such periods must be set and agreed to by Council's Health and Building Unit.

(12) ASSOCIATED ROADWAY COSTS

All costs associated with the construction of any new road works including kerb and gutter, road pavement, drainage system and footway shall be borne by the developer. The new road works must be designed and constructed in accordance with the City's "Sydney Streets Technical Specification" including amendments and "Sydney Streets Design Code".

(13) COST OF SIGNPOSTING

All costs associated with signposting for any kerbside parking restrictions and traffic management measures associated with the development shall be borne by the developer.

(14) TRAFFIC WORKS

Any proposals for alterations to the public road, involving traffic and parking arrangements, must be designed in accordance with RMS Technical Directives and must be referred to and agreed to by the Local Pedestrian, Cycling and Traffic Calming Committee prior to any work commencing on site.

(15) PARKING DESIGN

The design, layout, signage, line marking, lighting and physical controls of all off-street parking facilities must comply with the minimum requirements of Australian Standard AS/NZS 2890.1 Parking facilities Part 1: Off-street car parking, AS/NZS 2890.2 Parking facilities Part 2: Off-commercial vehicle facilities and AS/NZS 2890.6 Parking facilities Part 6: Off-street parking for people with disabilities. The details must be submitted to and approved by the Accredited Certifier prior to a Construction Certificate being issued.

(16) MATERIALS AND SAMPLES SCHEDULE

- (a) A detailed materials, colours and finishes schedule (including visible rainwater goods and services) keyed to each building elevation and consistent with the materials and samples board accompanying the application (Council reference 2019/162816) must be submitted to and approved by Council's Director City Planning, Development and Transport prior to any Construction Certificate being issued. The materials and samples schedule/board must not include generic material or colour descriptions, or use terminology such as 'or similar'.
- (b) The front door must be clearly visible and discernible from the street and must use a material and colour separate from the facade.

(17) COMPLIANCE WITH SUBMITTED MATERIALS AND SAMPLES BOARD

The design details of the proposed building facade including all external finishes, colours and glazing must be in accordance with the materials schedule and sample board, and specifications approved under condition 13.

(18) DESIGN QUALITY EXCELLENCE

- (a) In order to ensure the design quality excellence of the development is retained to completion:
 - The design architect Andrew Burns Architects is to have direct involvement in the design documentation, contract documentation and construction stages of the project including signing off any required certifications at DA, S4.55 applications, Construction Certificate and Occupation Certificate stages;
 - The design architect is to have full access to the site and is to be authorised by the applicant to respond directly to Council where information or clarification is required in resolving design issues throughout the life of the project;
 - (iii) Evidence of the design architect's commission must be provided to the Council prior to release of the Construction Certificate.
- (b) The design architect of the project is not to be changed without prior notice and approval of the Council's Director City Planning, Development and Transport.

The Accredited Certifier and Principle Certifier must be satisfied that the above matters are complied with prior to the issue of a relevant Construction and Occupation Certificates, in accordance with written confirmation from Council.

(19) NO AIR CONDITIONING UNITS TO FACADE OR BALCONIES OF BUILDING

Approval is not granted for the installation of individual air conditioning units to the facade or balconies of the building.

(20) FLOOD PLANNING LEVELS

- (a) All proposed habitable ground floor levels within the site shall be set at minimum RL 9.98 AHD.
- (b) A design certification report prepared by a suitably qualified practitioner engineer (NPER), for floor levels of buildings and structures demonstrating compliance of these requirements above shall be submitted to and be approved by the Principal Certifying Authority prior to the issue of any Construction Certificate. The approval report shall be provided to the City of Sydney prior to the commencement of the work.

SCHEDULE 1B

PRIOR TO CONSTRUCTION CERTIFICATE/COMMENCEMENT OF WORK/HEALTH AND BUILDING

(21) ASBESTOS REMOVAL WORKS

(a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence shall be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.
- (c) All work must be carried out in accordance with the Work Health and Safety Regulation 2017 and the NSW Government and SafeWork NSW document entitled How to manage and control asbestos in the work place: Code of Practice (Safework NSW) December 2011 and the City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.
- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.
- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).

- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.
- A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

(22) CLASSIFICATION OF WASTE

Prior to the exportation of waste (including fill or soil) from the site, the waste materials must be classified in accordance with the provisions of the Protection of the *Environment Operations Act 1997* and the *NSW DECC Waste Classification Guidelines, Part1: Classifying Waste (July 2009)*. The classification of the material is essential to determine where the waste may be legally taken. The *Protection of the Environment Operations Act 1997* provides for the commission of an offence for both the waste owner and the transporters if the waste is taken to a place that cannot lawfully be used as a waste facility for the particular class of waste. For the transport and disposal of industrial, hazardous or Group A liquid waste advice should be sought from the EPA.

(23) ENVIRONMENTAL MANAGEMENT PLAN

Prior to the commencement of any demolition and remedial works an Environmental Management Plan (EMP) must be prepared for the site and submitted to Council's Area Planning Manager for written approval prior to the commencement of work. The EMP must consider all potential environmental impacts from the approved works including but not limited to sedimentation control, contamination containment, stockpiles, noise and vibration, odours and dust emissions.

All works must be undertaken onsite in accordance with the approved Environmental Management Plan.

(24) IMPORTED FILL MATERIALS

All fill imported onto the site shall be validated to ensure the imported fill is suitable for the proposed land use from a contamination perspective. Fill imported on to the site shall also be compatible with the existing soil characteristic for site drainage purposes.

The City may require details of appropriate validation of imported fill material to be submitted with any application for future development of the site. Hence all fill imported onto the site should be validated by either one or both of the following methods during remediation works:

(a) Imported fill should be accompanied by documentation from the supplier which certifies that the material is not contaminated based upon

analyses of the material for the known past history of the site where the material is obtained; and/or

(b) Sampling and analysis of the fill material shall be conducted in accordance with NSW EPA (1995) Sampling Design Guidelines.

(25) LAND REMEDIATION

- (a) The site is to be remediated and validated in accordance with the Ashmore Estate (Park Sydney) Stage 3 Remedial Works Plan, prepared by JBS&G and Section B Site Audit Statement prepared by NSW Environment Protection Authority accredited Site Auditor Melissa Porter and dated 6th April 2018. All remediation work carried out shall be conducted in accordance with the guidelines in force from time to time under the *Contaminated Land Management Act 1997*.
- (b) Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination must be immediately notified to the Council's Area Planning Manager, the Site Auditor and the Principal Certifier.
- (c) Any variations to the approved Remediation Action Plan shall be approved in writing by the Site Auditor and Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the commencement of such work.

(26) LAND DEDICATION – REMEDIATION CAPPING LAYER

If the remediation of any land to be dedicated to Council includes a 'capping layer', that capping layer must be a minimum of 1.5m below the top most surface of the future road or park.

The Site Auditor is required to submit an interim report to Council for approval after the remediation has been completed and prior to the construction of the public domain works.

(27) SITE AUDIT STATEMENT – ENVIRONMENTAL MANAGEMENT PLAN

Where the ongoing land use suitability and release of the Final (Section A) Site Audit Statement is dependent upon the implementation of an Environmental Management Plan (EMP) in relation to any residual contamination remaining onsite, the EMP must be approved by the Site Auditor and Council's Area Planning Manager prior to the issue of the final Site Audit Statement.

The owner of the land is required to comply with the ongoing obligations of any EMP which form part of the final Site Audit Statement for the site.

A covenant shall be registered on the title of the land binding the owners and future owners to be responsible for ongoing maintenance and any future rehabilitation works required in terms of the encapsulated/remaining contaminated materials, including the discharge or prevention of discharge from any contaminants or for any works subsequently required by the NSW Environment Protection Authority

A copy of the revised certificate of land title recording the covenant must be submitted to Council's Area Planning Manager and the Principal Certifier prior to the issue of an Occupation Certificate.

(28) STOCKPILES

- (a) No stockpiles of soil or other materials shall be placed on footpaths or nature strips unless prior approval has been obtained from the City's Construction Regulation Unit.
- (b) All stockpiles of soil or other materials shall be placed away from drainage lines, gutters or stormwater pits or inlets.
- (c) All stockpiles of soil or other materials likely to generate dust or odours shall be covered.
- (d) All stockpiles of contaminated soil shall be stored in a secure area and be covered if remaining more than 24 hours

(29) REGISTRATION OF COVENANT

Prior to the issue of an Occupation Certificate, a covenant must be registered on the title of the land and a copy of the title submitted to the Council's Area Planning Manager and the Principal Certifier.

This covenant must be registered on the title of the land binding the owners and future owners with the responsibility for the ongoing maintenance and rehabilitation works required in terms of the encapsulated/remaining contaminated materials, including the discharge or prevention of discharge from any contaminants or for any works subsequently required by the NSW Environment Protection Authority

A copy of the revised certificate of land title recording the covenant must be submitted to Council's Area Planning Manager and the Principal Certifier prior to the issue of an Occupation Certificate.

(30) PHYSICAL MODELS

(a) Prior to the issue of any Occupation Certificate an accurate 1:500 scale model of the development as constructed must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the City Model in Town Hall House.

Note:

- The models must be constructed in accordance with the Model Specifications available online at <u>http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements</u> Council's modellers must be consulted prior to construction of the model.
- (ii) The models are to comply with all of the conditions of the Development Consent.
- (iii) The models must be amended to reflect any further modifications to the approval (under Section 4.55 of the *Environmental Planning*

and Assessment Act) that affect the external appearance of the building.

(31) SUBMISSION OF ELECTRONIC CAD MODELS PRIOR TO OCCUPATION CERTIFICATE

- (a) Prior to any Occupation Certificate being issued, an accurate 1:1 electronic CAD model of the completed development must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the electronic Visualisation City Model.
- (b) The data required to be submitted within the surveyed location must include and identify:
 - (i) building design above and below ground in accordance with the development consent;
 - (ii) all underground services and utilities, underground structures and basements, known archaeological structures and artefacts;
 - (iii) a current two points on the site boundary clearly marked to show their Northing and Easting MGA (Map Grid of Australia) coordinates, which must be based on Established Marks registered in the Department of Lands and Property Information's SCIMS Database with a Horizontal Position Equal to or better than Class C.

The data is to be submitted as a DGN or DWG file on a Compact Disc. All modelling is to be referenced to the Map Grid of Australia (MGA) spatially located in the Initial Data Extraction file.

(c) The electronic model must be constructed in accordance with the City's 3D CAD electronic model specification. The specification is available online at <u>http://www.cityofsydney.nsw.gov.au/development/applicationguide/application-process/model-requirements</u> Council's Modelling staff should be consulted prior to creation of the model. The data is to comply with all of the conditions of the Development Consent.

(32) CONSTRUCTION LIAISON COMMITTEE – ASHMORE PRECINCT

- (a) Prior to the commencement of any work, a Construction Liaison Committee or an alternative approved in writing by Council's Director City Planning, Development and Transport, is to be established by the developer to ensure that demolition and construction related impacts (including construction noise and vibration, loading, issues associated with construction workers and vehicles, traffic issues and management of the construction site) can be dealt with expeditiously and cooperatively.
- (b) The Committee is to be comprised of interested parties representing potentially affected properties adjacent to and surrounding the site and any interested group. A nominated representative of the Council may be an observer from time to time.

- (c) The Committee shall meet prior to the commencement of works on the site and prior to the submission of the final Construction Management Plan to Council to address initial areas of concern, and then at monthly intervals or as considered appropriate by the Committee throughout the construction process.
- (d) Prior to the commencement of work, the Site Manager is to provide the members of the Committee and Council with 24 hour contract details (including location of site offices and a 24 hour phone number) to ensure that any matters which arise during the construction process are addressed immediately. The Site Manager shall be available during normal business hours to provide information to the public about activities on site and to bring any complaints to the attention of the Applicant.
- (e) A register of all complaints shall be kept by the Applicant throughout the duration of the project and shall be made available to Council Officers on request.
- (f) The Committee meetings are to be recorded/minuted and such records/minutes are to be provided to Council within 14 days of the meeting.
- (g) The first Committee meeting should establish Terms of Reference, including purpose, size and membership, quorum, meeting frequency and duration, procedures for meetings, recording/distribution of comments and outcomes and the like.
- (h) The initial call for resident/worker nominations to be sent to the adjacent and adjoining property owners and tenants must be submitted to and approved by the Director City Planning, Development and Transport prior to sending.
- (i) The Site Manager is to inform each Committee meeting about the construction program, progress reports and impending work.

(33) CONSTRUCTION TRAFFIC MANAGEMENT PLAN

- (a) The Construction Traffic Management Plan accompanying this Development Application has not been approved by this consent.
- (b) A Construction Traffic Management Plan must be submitted to and approved by Council's Area Planning Manager/Area Planning Coordinator prior to the issue of any Construction Certificate. The CTMP must be prepared in accordance with Council's requirements, located at –

http://www.cityofsydney.nsw.gov.au/business/businessresponsibilities/traffic-management/construction-traffic-managementplans

(c) The development must be undertaken in accordance with the CTMP approved under (b) above.

(34) DEMOLITION, EXCAVATION AND CONSTRUCTION MANAGEMENT

- (a) Prior to the commencement of demolition and/or excavation work the following details must be submitted to and be approved by the Principal Certifier:
 - (i) Plans and elevations showing distances of the subject building from the location of adjoining and common/party walls, and (where applicable) the proposed method of facade retention.
 - A Demolition Work Method Statement prepared by a licensed demolisher who is registered with the Work Cover Authority. (The demolition by induced collapse, the use of explosives or on-site burning is not permitted.)
 - (iii) An Excavation Work Method Statement prepared by an appropriately qualified person.
 - (iv) A Waste Management Plan for the demolition and or excavation of the proposed development.
- (v) Plans and elevations showing the location, construction and installation of temporary site fencing and any temporary structures used in connection with the construction of the development.

<u>Note</u>: Temporary structures, including hoardings and scaffolding, proposed for erection on City-owned and controlled land (footways and roadways), must comply with the City's *Guidelines for Hoardings and Scaffolding* and be approved by Council under the provisions of the Local Government Act 1993 and the Roads Act 1993 prior to installation.

- (b) Such statements must, where applicable, be in compliance with AS2601-2001 Demolition of Structures, the Work, Health and Safety Act 2011 and Regulation; Council's Policy for Waste Minimisation in New Developments 2005, the Waste Avoidance and Resource Recovery Act 2001, and all other relevant acts and regulations and must include provisions for:
 - (i) A Materials Handling Statement for the removal of refuse from the site in accordance with the *Waste Avoidance and Resource Recovery Act 2001.*
 - (ii) The name and address of the company/contractor undertaking demolition/excavation works.
 - (iii) The name and address of the company/contractor undertaking off site remediation/disposal of excavated materials.
 - (iv) The name and address of the transport contractor.
 - (v) The type and quantity of material to be removed from site.
 - (vi) Location and method of waste disposal and recycling.
 - (vii) Proposed truck routes, in accordance with this development consent.

- (viii) Procedures to be adopted for the prevention of loose or contaminated material, spoil, dust and litter from being deposited onto the public way from trucks and associated equipment and the proposed method of cleaning surrounding roadways from such deposits. (Note: With regard to demolition of buildings, dust emission must be minimised for the full height of the building. A minimum requirement is that perimeter scaffolding, combined with chain wire and shade cloth must be used, together with continuous water spray during the demolition process. Compressed air must not be used to blow dust from the building site).
- (ix) Measures to control noise emissions from the site.
- (x) Measures to suppress odours.
- (xi) Enclosing and making the site safe.
- (xii) Induction training for on-site personnel.
- (xiii) Written confirmation that an appropriately qualified Occupational Hygiene Consultant has inspected the building/site for asbestos, contamination and other hazardous materials, in accordance with the procedures acceptable to SafeWork NSW.
- (xiv) An Asbestos and Hazardous Materials Clearance Certificate by a person approved by the SafeWork NSW.
- (xv) Disconnection of utilities.
- (xvi) Fire Fighting. (Fire fighting services on site are to be maintained at all times during demolition work. Access to fire services in the street must not be obstructed).
- (xvii) Access and egress. (Demolition and excavation activity must not cause damage to or adversely affect the safe access and egress of the subject building or any adjacent buildings).
- (xviii) Waterproofing of any exposed surfaces of adjoining buildings.
- (xix) Control of water pollution and leachate and cleaning of vehicles tyres (proposals must be in accordance with the *Protection of the Environmental Operations Act 1997*).
- (xx) Working hours, in accordance with this development consent.
- (xxi) Any SafeWork NSW requirements.
- (c) The approved work method statements and a waste management plan as required by this condition must be implemented in full during the period of construction.

(35) EROSION AND SEDIMENT CONTROL

Prior to the commencement of any works on site, including, but not limited to demolition, excavation or construction work, a Soil and Water Management Plan (SWMP) must be submitted to and be approved by the Principal Certifier.

- (a) The SWMP must identify and respond to all items for Erosion and Sediment Control Plans listed in the condition above, as well as:
 - (i) existing site contours;
 - location and diagrammatic representation of all necessary erosion and sediment control systems or structures used to mitigate or prevent pollution to stormwater;
 - (iii) location and engineering details with supporting design calculations for all necessary sediment basins, constructed wetlands, gross pollutant traps, trash racks or biofiltration swales (as relevant).

(36) ROAD OPENING PERMIT

A separate Road Opening Permit under Section 138 of the *Roads Act 1993* must be obtained from Council prior to the commencement of any:

- (a) Excavation in or disturbance of a public way, or
- (b) Excavation on land that, if shoring were not provided, may disturb the surface of a public road (including footpath).

(37) DEWATERING

- (a) If any dewatering of the site is to be undertaken, a bore licence may be required from the NSW Office of Water under the provisions of Part V of the Water Act 1912. The NSW Office of Water licences dewatering to allow excavation for construction for a temporary period, usually 12 months.
- (b) The development is required to comply with the conditions of Schedule 3, 1-30 of the concept approval D/2015/966 (as amended) with regard to any dewatering undertaken on site.
- (c) Approval must be gained from Council to discharge groundwater at any time and for any purpose into the City's stormwater system. If any dewatering of the site is to be undertaken, a bore licence may be required from the NSW Office of Water under the provisions of Part V of the Water Act 1912. The NSW Office of Water licences dewatering to allow excavation for construction for a temporary period, usually 12 months.

NOTE: The Department's instructions to Council are that they will not endorse the extraction of groundwater in perpetuity i.e. permanent dewatering around a development site, because it considers such development to be unsustainable. For this reason any proposed basement or other area that requires dewatering on an on-going basis may need to be fully tanked.

(38) APPLICATION FOR HOARDINGS AND SCAFFOLDING INSTALLED ON OR ABOVE A PUBLIC ROAD AND OPERATING HOISTING DEVICES INCLUDING BUILDING MAINTENANCE UNITS OVER A PUBLIC ROAD

(a) Where a hoarding and/or scaffolding (temporary structures) are proposed to be installed on or above a road reservation (footway and/or

roadway), a separate application under Section 68 of the *Local Government Act 1993* and Section 138 of the *Roads Act 1993* is to be made to Council for such structures.

- (b) Where an approval (Permit) is granted allowing the placement of temporary structures on or above a public road the structures must comply fully with Council's *Hoarding and Scaffolding Policy; Guidelines* for Hoardings and Scaffolding; and the conditions of approval (Permit) granted including:
 - (i) maintaining a current and valid approval for the full duration that the temporary structure/s is in place;
 - (ii) maintaining temporary structure/s in a structurally sound and stable condition for the full duration of installation (Clause 2.11.1);
 - (iii) bill posters and graffiti being removed within 24 hours of their placement (Clause 2.11.2);
 - (iv) maintaining temporary structures and the public place adjoining the work site in a clean and tidy condition including repainting and/or repair of graphics (Clauses 2.11.1, 2.11.4, 2.14.1 and 3.9.3);
 - (v) maintaining a watertight deck (Type B hoardings) to prevent liquids including rainwater, falling onto the footway/roadway surfaces (Clauses 3.9.1 and 3.9.4);
 - (vi) approved site sheds on the decks of a Type B hoarding being fully screened from the public place (Clause 3.9.5);
 - (vii) material and equipment not being placed or stored on the deck of Type B hoardings, unless specifically approved by Council (Clause 3.9.4);
 - (viii) providing and maintaining operational artificial lighting systems under Type B hoardings including at high-bay truck entry points (Clause 3.9.9); and
 - (ix) ensuring all required signage, artwork or historic images are provided and fully maintained to the City's requirements (Clauses 3.4, 3.9.3, 3.9.6, 3.9.8, 3.10.1 and 4.2).

If it is proposed to operate a hoisting device including a building maintenance unit above a public road which swings, hoists material/equipment and/or slews/wind vanes any part of the device over the public road, a separate application under Section 68 of the *Local Government Act 1993* and Section 138 of the *Roads Act 1993* must be made to Council to obtain approval.

Note: 'Building maintenance unit' means a power-operated suspended platform and associated equipment on a building specifically designed to provide permanent access to the faces of the building for maintenance (*Work Health and Safety Regulation 2017*).

(39) LAND SUBDIVISION – SUBDIVISION CERTIFICATE

A separate application must be made to Council to obtain the approval of the plan of subdivision and issue of a Subdivision Certificate under Section 6.15 of the *Environmental Planning and Assessment Act 1979*.

(40) STREET ADDRESSES OF LOTS

In accordance with Clause 60(c) of the Surveying and Spatial Information Regulation 2017, the street addresses for each lot must be shown on the final plan of subdivision. An application should be made to Council to obtain the correct street address for each lot.

(41) SYDNEY WATER CERTIFICATE - SUBDIVISION

Prior to the issue of a Subdivision/Strata Certificate, a Section 73 Compliance Certificate under the *Sydney Water Act 1994* must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Coordinator. Please refer to the Building Developing and Plumbing section on the web site www.sydneywater.com.au then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Coordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

The Section 73 Certificate must be submitted to Council or the Accredited Certifier prior to a Subdivision/Strata Certificate being issued.

(42) TELECOMMUNICATIONS IN NEW DEVELOPMENTS

Prior to the issue of the Subdivision or Construction Certificate in connection with a development, the developer (whether or not a constitutional corporation) is to provide evidence satisfactory to the Accredited Certifier that arrangements have been made for:

- (a) the installation of fibre-ready facilities to all individual lots and/or premises in a real estate development project so as to enable fibre to be readily connected to any premises that is being or may be constructed on those lots. Demonstrate that the carrier has confirmed in writing that they are satisfied that the fibre ready facilities are fit for purpose; and
- (b) the provision of fixed-line telecommunications infrastructure in the fibreready facilities to all individual lots and/or premises in a real estate development project demonstrated through an agreement with a carrier.

<u>Note</u>: real estate development project has the meanings given in section 372Q of the Telecommunications Act.

(43) UTILITY SERVICES

To ensure that utility authorities are advised of the development:

- (a) Prior to the issue of a Construction Certificate a survey is to be carried out of all utility services within and adjacent to the site including relevant information from utility authorities and excavation if necessary, to determine the position and level of services.
- (b) Prior to the commencement of work the applicant is to obtain written approval from the utility authorities (e.g. Energy Australia, Sydney Water, and Telecommunications Carriers) in connection with the relocation and/or adjustment of the services affected by the construction of the underground structure. Any costs in the relocation, adjustment or support of services are to be the responsibility of the developer.

(44) WASTE AND RECYCLING MANAGEMENT

- (a) The Waste and Recycling Management Plan (Council reference 2020/017160) must be amended to update the amount of soil to be removed from the site, in accordance with the Stage 3 Remedial Works plan prepared by JBS&G (Council reference 2019/150627).
- (b) The revised Waste and Recycling Management Plan is to be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager prior to a Construction Certificate being issued. The plan must comply with the Council's *Guidelines for Waste Management in New Developments 2018*. All requirements of the approved Waste and Recycling Management Plan must be implemented during construction of the development.
- (c) The building must incorporate designated areas or separate garbage rooms constructed in accordance with Council's *Guidelines for Waste Management in New Developments 2018*, to facilitate the separation of commercial waste and recycling from residential waste and recycling.

UPON COMPLETION OF THE DEVELOPMENT

(d) Prior to any Occupation Certificate being issued or the use commencing, whichever is earlier, the Principal Certifier must obtain Council's approval of the waste and recycling management facilities provided in the development and ensure arrangements are in place for domestic waste collection by Council.

(45) COMPLIANCE WITH ACID SULFATE SOILS MANAGEMENT PLAN

All recommendations contained in the Acid Sulphate Soils Management Plan prepared by JBS&G, reference 52002/107785 dated 11 April 2017 must be implemented.

(46) ARCHAEOLOGICAL DISCOVERY DURING EXCAVATION

- (a) Should any relics be unexpectedly discovered on the site during excavation, all excavation or disturbance to the area is to stop immediately and the Heritage Council of NSW should be informed in accordance with section 146 of the Heritage Act 1977.
- (b) Should any Aboriginal objects be unexpectedly discovered then all excavation or disturbance of the area is to stop immediately and NSW

Government Office of Environment and Heritage is to be informed in accordance with Section 89A of the *National Parks and Wildlife Act* 1974

- (c) Should any archaeological remains or Aboriginal objects be discovered, a copy of recording of the finds and the final archaeological summary report is to be submitted to Council prior to the issue of any Occupational Certificate;
- (d) if the discovery is on Council's land, Council must be informed.

DURING CONSTRUCTION/PRIOR TO OCCUPATION/COMPLETION

(47) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

(48) HOURS OF WORK AND NOISE

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the onstreet use of mobile cranes outside of above hours can occur, subject to a permit being issued by Council under Section 68 of the Local Government Act 1993 and/or Section 138 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Unit, prior to works proceeding

The City of Sydney Code of Practice for Construction Hours/Noise 1992 allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

(49) BASIX

All commitments listed in each relevant BASIX Certificate for the development must be fulfilled prior to any Occupation Certificate being issued.

(50) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

(51) SURVEY CERTIFICATE AT COMPLETION

A Survey Certificate prepared by a Registered Surveyor must be submitted to the Principal Certifier at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

(52) COVERING OF LOADS

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

(53) EROSION AND SEDIMENT CONTROL

The Soil and Water Management Plan (SWMP) or Erosion and Sediment Control Plan (ESCP) which has been approved by the Principal Certifier must be implemented in full during the construction period.

During the construction period:-

- erosion and sediment controls must be regularly inspected, repaired and maintained in working order sufficient for a 10 year Average Recurrence Interval (ARI) rainfall event;
- (b) erosion and sediment control signage available from Council must be completed and attached to the most prominent structure visible at all times when entering the site for the duration of construction; and
- (c) building operations and stockpiles must not be located on the public footway or any other locations which could lead to the discharge of materials into the stormwater system.

(54) VEHICLE CLEANSING

Prior to the commencement of work, suitable measures are to be implemented to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site. It is an offence to allow, permit or cause materials to pollute or be placed in a position from which they may pollute waters.

(55) LOADING AND UNLOADING DURING CONSTRUCTION

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site, where possible.
- (b) If, it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.
- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.

(d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate approval under Section 68 of the Local Government Act 1993 and Section 138 of the Roads Act 1993 must be obtained.

(56) NO OBSTRUCTION OF PUBLIC WAY

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances. Non-compliance with this requirement will result in the issue of a notice by Council to stop all work on site.

(57) HAZARDOUS AND INDUSTRIAL WASTE

Hazardous and/or industrial waste arising from the demolition/operational activities must be removed and/or transported in accordance with the requirements of the NSW Work Cover Authority pursuant to the provisions of the following:

- (a) Protection of the Environment Operations Act 1997
- (b) Protection of the Environment Operations (Waste) Regulation 2005
- (c) Waste Avoidance and Resource Recovery Act 2001
- (d) Work Health and Safety Act 2011
- (e) Work Health and Safety Regulation 2011.

SCHEDULE 1D – PUBLIC DOMAIN

The following conditions regard the public domain. Any requests to satisfy these conditions are to be sent to <u>publicdomain@cityofsydney.nsw.gov.au</u>

(58) NO OBSTRUCTIONS WITHIN THE PUBLIC DOMAIN

No above ground utility infrastructure such as meter boxes and the like, with the exception of drainage pits and services covers, are permitted within the public domain unless expressly permitted within the approved public domain plan under condition 62.

(59) ALIGNMENT LEVELS

- (a) Proposed building floor levels, basement levels, basement car park entry levels and ground levels shown on the approved Development Application plans are indicative only and have not been approved by this consent.
- (b) Prior to a Construction Certificate being issued for any excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work, alignment levels for the building and site frontages must be submitted to and approved by Council. The submission must be prepared by a Registered Surveyor and designed by a suitably qualified engineer, must be in accordance with the City of Sydney's *Public Domain Manual* and must be submitted with a completed and Levels and Gradients Approval Application form (available on the City's website).
- (c) These alignment levels, as approved by Council, are to be incorporated into the plans submitted with the application for a Construction Certificate for any civil, drainage and public domain work as applicable under this consent. If the proposed detailed design of the public domain requires changes to any previously approved Alignment Levels, then an amended Alignment Levels submission must be submitted to and approved by Council to reflect these changes prior to a Construction Certificate being issued for public domain work.

(60) PAVING MATERIALS PAVING MATERIALS

The surface of any material used or proposed to be used for the paving of colonnades, thoroughfares, plazas, arcades and the like which are used by the public must comply with AS/NZS 4586:2004 (including amendments) "Slip resistance classification of new pedestrian surface materials".

(61) PHOTOGRAPHIC RECORD / DILAPIDATION REPORT - PUBLIC DOMAIN

Prior to an approval for demolition being granted or a Construction Certificate being issued, whichever is earlier, a photographic recording of the public domain site frontages is to be prepared and submitted to Council's satisfaction.

The recording must include clear images of the building facade adjoining the footpath, the footpath, nature strip, kerb and gutter, driveway crossovers and laybacks, kerb ramps, road carriageway, street trees and plantings, parking restriction and traffic signs, and all other existing infrastructure along the street.

The form of the recording is to be as follows:-

- (a) A PDF format report containing all images at a scale that clearly demonstrates the existing site conditions;
- (b) Each image is to be labelled to identify the elements depicted, the direction that the image is viewed towards, and include the name of the relevant street frontage;
- (c) Each image is to be numbered and cross referenced to a site location plan;
- (d) A summary report, prepared by a suitable qualified professional, must be submitted in conjunction with the images detailing the project description, identifying any apparent existing defects, detailing the date and authorship of the photographic record, the method of documentation and limitations of the photographic record;
- (e) Include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

Any damage to the public way including trees, footpaths, kerbs, gutters, road carriageway and the like must immediately be made safe and functional by the applicant. Damage must be fully rectified by the applicant in accordance with the City's standards prior to a Certificate of Completion being issued for Public Domain Works or before an Occupation Certificate is issued for the development, whichever is earlier.

(62) PRESERVATION OF SURVEY MARKS

All works in City streets must ensure the preservation of existing permanent survey marks (a brass bolt, or a lead plug holding a brass tack, covered by a cast iron box). At least forty-eight hours prior to the commencement of any works in the public way within 1 metre of a permanent survey mark contact must be made with the City's Project Manager Survey / Design Services to arrange for the recovery of the mark.

Prior to the issue of a Construction Certificate, a survey plan, clearly showing the location of all permanent survey marks fronting the site and within 5 metres on each side of the frontages must be submitted to Council.

At least forty-eight hours prior to the commencement of any works in the public way within 1 metre of a permanent survey mark contact must be made with the City's Senior Surveyor to arrange for the recovery of the mark.

A fee must be paid to the Council for the replacement of any permanent survey mark removed or damaged in accordance with the City's Schedule of Fees and Charges (Reinstatement of Survey Box).

(63) PROTECTION OF SURVEY INFRASTRUCTURE

Prior to the commencement of any work on site, a statement prepared by a Surveyor registered under the *Surveying and Spatial Information Act 2002* must be submitted to Council verifying that a survey has been carried out in accordance with the Surveyor General's Direction No. 11 – Reservation of Survey Infrastructure. Any Permanent Marks proposed to be or have been destroyed must be replaced, and a "Plan of Survey Information" must be lodged at the NSW Land Registry Services.

Reason: To ensure that the survey control infrastructure and cadastral framework are preserved for the public benefit and in accordance with the *Surveying and Spatial Information Act 2002*.

(64) PUBLIC DOMAIN PLAN

- (a) A detailed Public Domain Plan must be prepared by a suitably qualified architect, urban designer, landscape architect or engineer and must be lodged with Council's Public Domain Section and be approved by Council prior to a Construction Certificate being issued for public domain work or above ground building work, whichever is later.
- (b) The Public Domain Plan must document all works required to ensure that the public domain complies with the City of Sydney's *Public Domain Manual, Sydney Streets Code* and *Sydney Streets Technical Specification*, including requirements for road pavement, traffic measures, footway pavement, kerb and gutter, drainage, vehicle crossovers, pedestrian ramps, lighting, street trees and landscaping, signage and other public domain elements. If an Alignment Levels condition applies to the development, the Public Domain Plan submission must incorporate the approved Alignment Levels. If the proposed detailed design of the public domain requires changes to any previously approved Alignment Levels, then an amended Alignment Levels submission must be submitted to and approved by Council to reflect these changes prior to a Construction Certificate being issued for public domain work.
- (c) The works to the public domain are to be completed in accordance with the approved Public Domain Plan and Alignment Levels plans and the *Public Domain Manual* before any Occupation Certificate is issued in respect of the development or before the use commences, whichever is earlier.

(65) PUBLIC DOMAIN WORKS BOND

Public Domain Works Deposit will be required as security for the public domain works and for repairing damage that may be caused to the public domain in the vicinity of the site, in accordance with the City of Sydney's adopted fees and charges and the Public Domain Manual. The Public Domain Works Deposit must be submitted as an unconditional bank guarantee or insurance bond as per the Council's Performance Bond Policy in favour of Council as security for completion of the obligations under this consent (Guarantee).

Council's Public Domain section must be contacted to determine the guarantee amount prior to lodgement of the guarantee. The guarantee must be lodged with Council prior to a Construction Certificate being issued.

The Guarantee will be retained in full until all Public Domain works, including rectification of damage to the public domain, are completed to City of Sydney standards and approval and the required certifications, warranties and works-as-executed documentation are submitted and approved by Council in writing. On satisfying the above requirements, 90% of the security will be released. The remaining 10% will be retained for the duration of the specified Defects Liability Period.

(66) PUBLIC DOMAIN WORKS – HOLD POINTS AND HANDOVER

- (a) Prior to a Construction Certificate being issued for public domain work, including civil, drainage and subsurface works, , a set of hold points for approved public domain, civil and drainage work is to be determined with and approved by the City's Public Domain section in accordance with the City of Sydney's *Public Domain Manual* and *Sydney Streets Technical Specification*.
- Prior to a Certificate of Completion being issued for public domain works (b) and before the issue of any Occupation Certificate for the development or before the use commences, whichever is earlier, electronic works-asexecuted (as-built) plans and documentation, certified by a suitably qualified, independent professional must be submitted to and accepted by Council for all public domain works. Completion and handover of the constructed public domain works must be undertaken in accordance with the City of Sydney's Public Domain Manual and Sydney Streets Specification, including requirements Technical for as-built documentation, certification, warranties and the defects liability period.

(67) STORMWATER AND DRAINAGE

- (a) Prior to an approval or Construction Certificate being issued for excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work a detailed drainage engineering design, calculations and design for the stormwater overland flow path for the development must be:
 - (i) prepared by a suitably qualified hydraulic or civil engineer to show the proposed method of collection and disposal of stormwater; and
 - (ii) prepared in accordance with the City of Sydney's *Stormwater Drainage Manual*, technical specifications, standards and policies, as amended from time to time; and
 - (iii) submitted to and be approved by the City of Sydney and a copy of the City's letter of approval must be provided to the Principal Certifying Authority.
- (b) For approval of a connection into the City of Sydney's drainage system an "Application for Approval of Stormwater Drainage Connections" must be submitted to the City, together with an application fee in accordance with the City of Sydney's adopted Schedule of Fees and Charges.
 - (i) The application must be approved by the City of Sydney prior to an approval or Construction Certificate being issued for excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work.

(ii) All proposed connections to the City's underground drainage system require the owner to enter into a Deed of Agreement with the City of Sydney and obtain registration on Title of a Positive Covenant prior to an Occupation Certificate being issued, including an Interim Occupation Certificate.

On-site Detention

- (c) The requirements of Sydney Water with regard to the on-site detention of stormwater must be ascertained and complied with.
 - (i) Evidence of the approval by Sydney Water of the detailed design of the on-site detention must be submitted to and be accepted by the City of Sydney and a copy of the City's letter of acceptance must be provided to the Principal Certifying Authority prior to a Construction Certificate being issued, excluding for any approved preparatory, demolition or excavation works.
 - (ii) Prior to the issue of an Occupation Certificate, including an Interim Occupation Certificate, a Positive Covenant must be registered on the property title for all drainage systems involving On-Site Detention (OSD) to ensure maintenance of the approved OSD system regardless of the method of connection.

Stormwater Quality Assessment

(d) Prior to a Construction Certificate being issued for any excavation, civil construction, drainage or building work (whichever is earlier), but excluding approved preparatory or demolition work, a stormwater quality assessment must be undertaken and must be approved by City of Sydney and a copy of the City's letter of approval must be provided to the Principal Certifying Authority. A stormwater quality assessment must be undertaken by a suitably qualified drainage engineer to demonstrate how the development will be designed to ensure that the flow of postdevelopment pollutants from the site due to stormwater will be reduced. The water quality assessment must be submitted to and be approved by the City of Sydney and a copy of the City's letter of approval must be provided to the Principal Certifying Authority prior to a Construction Certificate being issued for any excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work.

Prior to the issue of an Occupation Certificate, maintenance schedules of the proposed water sensitive urban design and drainage measures must be submitted to and be approved by the Principal Certifying Authority and a copy provided to the City of Sydney.

Completion / Works-as-Executed Documentation

- (e) Prior to a Certificate of Completion being issued by the City of Sydney for stormwater drainage works:
 - (i) All works for the disposal of stormwater and drainage are to be implemented in accordance with the approved plans, City of Sydney technical specifications. Standards and policies, approval letters and the requirements of this consent.

- (ii) a Works-As-Executed survey, prepared, signed and dated by a Registered Surveyor, must be submitted to and be accepted by the City of Sydney. The plan must be overlaid on a copy of the approved stormwater drainage plans issued with the Construction Certificate, with variations to locations, dimensions, levels and storage volumes clearly marked.
- (iii) Electronic works-as-executed (as-built) details, certifications, warranties, inspection reports (including Closed Circuit Television reports) and associated documentation for the completed work must be prepared and certified by a suitably qualified hydraulic engineer, in accordance with the requirements of the City of Sydney's technical specifications, the *Public Domain Manual*, the *Stormwater Drainage Manual*, the conditions of this consent and all letters of approval issued by the City of Sydney for works in the public domain, and must be submitted to and be accepted by the City of Sydney.
- (f) Prior to the issue of the first Occupation Certificate, including an Interim Occupation Certificate, or before the use commences (whichever is earlier):
 - A copy of the City's Certificate of Completion for all stormwater and drainage work undertaken in the public domain must be provided to the Principal Certifying Authority;
 - a Works-As-Executed survey, must be prepared, signed, dated and certified by a Registered Surveyor and must be submitted to and be accepted by the Principal Certifying Authority. The Worksas-Executed plan must be overlaid on a copy of the approved stormwater drainage plans issued with the Construction Certificate, with variations to locations, dimensions, levels and storage volumes clearly marked;
 - (iii) a Hydraulic Compliance Certificate and Calculation Sheet must be prepared by a suitably qualified hydraulic engineer (minimum NER), showing approved versus installed hydraulic calculations, and must be submitted to and be accepted by the Principal Certifying Authority;
 - (iv) evidence of Sydney Water's acceptance of the Works-As-Executed documentation, certification and Hydraulic Compliance Certificate and Calculation Sheet must be provided to the Principal Certifying Authority;

The Principal Certifying Authority must submit a copy of the Works-As-Executed plans, certifications, Hydraulic Compliance Certificate and Calculation Sheet to the City of Sydney.

(68) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS

All works to the City's public domain, including rectification of identified defects, are subject to a 6 month defects liability period from the date of final completion. The date of final completion will be nominated by Council on the Certificate of Practical Completion for public domain works.

(69) DRAINAGE AND SERVICE PIT LIDS DRAINAGE AND SERVICE PIT LIDS

Drainage and service pit lids throughout the public domain shall be heelguard and bicycle safe, finish flush with the adjacent pavement to avoid trip hazards and be clear of obstructions for easy opening and cleaning. Pit lids shall be in accordance with the *City of Sydney's Sydney Streets Design Code* and *Sydney Streets Technical Specification*. Details of drainage and service pit lids shall be submitted and approved by Council prior to a Construction Certificate being issued for the relevant stage of work.

(70) NOMINATED ENGINEERING WORKS SUPERVISOR – MAJOR INFRASTRUCTURE

Prior to issue of a Road Opening Permit for works in the public domain, the developer shall give Council written notification of the appointment of either:

- (a) A Chartered Civil Engineer, with National Professional Engineering Registration (NPER 3) in the construction of civil works, or
- (b) A survey company of Registered Surveyors with accreditation from the Institution of Surveyors NSW Inc, or
- (c) An accredited certifier in civil engineering, as its nominated engineering works supervisor, the responsibility of whom shall be to sufficiently supervise the works to ensure compliance with all relevant statutory requirements, all relevant conditions of development consent, construction requirements detailed in the above specification, and the requirements of all legislation relating to environmental protection and occupational health and safety.

On completion of the works the nominated engineering works supervisor shall certify that the works have been constructed in accordance with the approved plans, specifications and conditions of approval, and that the "Works as Executed" plans are a true and correct record of what has been built. The works supervisor shall be independent of the Principal Certifier.

(71) PUBLIC DOMAIN LIGHTING

- (a) Prior to a Construction Certificate for public domain works or above ground building works being issued, whichever is later, a detailed Public Domain Lighting Plan for pedestrian and street lighting in the public domain must be prepared by a suitably qualified, practicing lighting engineer or lighting designer and must be submitted to and approved by Council. The Lighting Plan must be prepared in accordance with the City of Sydney's Sydney Lights Design Code, Sydney Streets Code, Sydney Streets Technical Specification and Public Domain Manual and must include the following:
 - Vertical and horizontal illuminance plots for the public domain lighting design to demonstrate compliance with all relevant Australian Standards and to meet the lighting categories and requirements specified by the City;
 - (ii) The location, type and category of existing and proposed lights, including details of luminaire specifications, required to ensure compliance with City policies and Australian Standards;

- (iii) Footing locations and structural details;
- (iv) Location and details of underground electrical reticulation, connections and conduits;
- (v) Certification by a suitably qualified, practicing lighting engineer or lighting designer to certify that the design complies with City policies and all relevant Australian Standards including AS 1158, AS 3000 and AS4282;
- (vi) Structural certification for footing designs by a suitably qualified, practicing engineer to certify that the design complies with City of Sydney policies and Australian Standards.
- (b) The public domain lighting works are to be completed in accordance with the approved plans and the City of Sydney's *Public Domain Manual* before any Occupation Certificate is issued in respect of the development or before the use commences, whichever is earlier.

(72) ROAD NETWORK AND GEOMETRIC ROAD DESIGN ROAD NETWORK AND GEOMETRIC ROAD DESIGN

- (a) Preparation of the detailed design and construction documentation for the proposed public road system shall include all necessary liaison with and requirements of all relevant public utility authorities, Roads and Maritime Services, Council, the Local Pedestrian Cycling and Traffic Calming Committee and its nominated consultants in order to achieve design approvals and construction compliance. Written evidence of approval from relevant authorities must be submitted to Council with the road design submission.
- (b) The design and construction of all road works shall be undertaken in accordance with City of Sydney's Sydney Streets Technical Specification and the Public Domain Manual. Detailed plans, construction details and specifications for the works shall be prepared and submitted to Council for approval prior to issue of a Construction Certificate, excluding for approved preparatory or demolition work, or before issue of an approval under Section 138 of the Roads Act 1993 for the road and drainage, infrastructure work. The detailed plans and supporting documentation shall include as a minimum the following information;
 - (i) General subdivision plan with contour details, clearly indicating the extent of work;
 - Road cross sections showing road and footway widths, existing levels, design levels, cross fall grade pavement configuration, batter slopes, engineered retaining walls, kerb returns, kerb and gutter, vehicle crossovers, pedestrian ramps the location of public utility services and 900mm minimum road restoration to match smoothly into the existing road levels;
 - Plan drawing and longitudinal section showing gutter invert, kerb and boundary alignments with design grades of the existing and proposed future public road network including public utility services;

- (iv) Road design and drainage plans showing the following:
 - a. road pavement structure and design;
 - b. kerb, gutter and building alignment;
 - c. traffic management structures / measures;
 - d. traffic, pedestrian and parking signage;
 - e. details of intersections with existing roads including linemarking, pavement marking, sign-posting, swept paths for the largest expected vehicle;
 - f. on-road bicycle route infrastructure and facilities;
 - g. Drainage plans and schedule of drainage elements, showing the following:
 - i. The proposed location of all subsoil drains and subpavement drains, including the nominal width and depth of trenches, pipe diameters and materials, longitudinal design grades, and the locations of outlets and cleanouts;
 - ii. The location of public utility services;
 - iii. Details and specifications for the construction of all components of the system in accordance with the *City* of Sydney's Sydney Streets Technical Specification;
 - All assumptions and/or calculations made in the determination of the need or otherwise for subsurface drainage, including requirements of broader stormwater catchment analysis to undertaken beyond the site boundary;
 - v. Drainage details and longitudinal sections with hydraulic grade lines for the design storm and other standard features such as flow rates, pipe class, pipe grade and velocity;
 - vi. Adjustments/upgrades to utility services as required;
 - vii. Standard engineering and structural details plan;
 - viii. Erosion and sedimentation control plans;
 - ix. A design certification report for the road works prepared by an appropriately qualified civil engineer certifying that the design complies with the City of Sydney's policies, standards and specifications and those of all other relevant authorities as applicable. All design documentation shall be completed in accordance with the relevant standards and specifications as adopted by Council from time to time. All engineering plans and calculations shall be

checked, signed and certified by a suitably qualified practicing professional engineer.

(c) The road and drainage works are to be completed in accordance with the approved plans and the City of Sydney's *Public Domain Manual* before any Occupation Certificate is issued in respect of the development or before the use commences, whichever is earlier.

(73) TACTILE GROUND SURFACE INDICATORS AND HANDRAILS

All tactile ground surface indicators, handrails and other elements required to provide access into the building / property must be located entirely within the private property boundary.

SCHEDULE 2

PRESCRIBED CONDITIONS

The prescribed conditions in accordance with Division 8A of the *Environmental Planning and Assessment Regulation 2000* apply:

- Clause 98 Compliance with *Building Code of Australia* and insurance requirements under the *Home Building Act 1989*
- Clause 98A Erection of signs
- Clause 98B Notification of Home Building Act 1989 requirements
- Clause 98C Conditions relating to entertainment venues
- Clause 98D Conditions relating to maximum capacity signage
- Clause 98E Conditions relating to shoring and adequacy of adjoining property

Refer to the NSW State legislation for full text of the clauses under Division 8A of the *Environmental Planning and Assessment Regulation 2000*. This can be accessed at: <u>http://www.legislation.nsw.gov.au</u>