

Attachment A

Recommended Conditions of Consent

SCHEDULE 1 - DEFERRED COMMENCEMENT CONDITIONS (CONDITIONS TO BE SATISFIED PRIOR TO CONSENT OPERATING)

The following deferred commencement conditions must be satisfied prior to the consent becoming operative:

(A) PART A - DEFERRED COMMENCEMENT CONDITIONS

(CONDITIONS TO BE SATISFIED PRIOR TO CONSENT OPERATING)

The consent is not to operate until the following condition is satisfied, within **24 months** of the date of this determination:

(1) DESIGN MODIFICATIONS

The design of the building must be modified as follows:

- (a) The basement car parking layout is to be amended to comply with the following:
 - (i) Only for service and staff use and car parking is not to be allocated to visitors or hotel guests.
 - (ii) Valet car parking is not approved and any notations on the drawings to valet parking are to be deleted.
 - (iii) A minimum of one service vehicle car space is to be provided.
 - (iv) Tandem car parking spaces are only permitted for use by hotel staff and are to have a minimum length of 10.8m in accordance with Section 3.11.12 of Sydney Development Control Plan 2012.
- (b) All glazing on the west elevation is to contain fixed privacy screens or obscure fixed glazing up to a minimum height of 1.6m, as measured from the finish floor level.
- (c) A minimum of 1.2 cubic metres of lockable storage is to be provided in each hotel room and notated on the drawings.
- (d) The ground floor layout is to be amended to comply with the following:
 - (i) An acoustic rated cavity wall of separate masonry skins is to isolate room G01 from the noise and vibration of the car lift. Repeatable maximum LAeq(1 hour) must not exceed 35dB within room G01 while the car lift is in operation.
 - (ii) A recessed tree pit 2m x 2m x 1m deep is to be located in the ground floor courtyard. Any adjustments in the basement level to maintain head height clearances need to be considered.
- (e) The level 03 plan is to be amended to comply with the following:
 - (i) The non-accessible roof area is to be landscaped with an extensive green roof on the Elizabeth Lane wing and the Elizabeth Street wing.

- (ii) Parapets are to be increased in height to contain the green roof area.
- (f) The level 04 plan is to be amended to comply with the following:
 - (i) The area is to have photovoltaic cells as part of a renewable energy storage system for the common areas of the hotel.
 - (ii) The parapet to the roof top is to be masonry and extended to 1.1m above the finished roof.

The amended drawings are to be submitted to and approved by Council's Director City Planning, Development & Transport.

(2) PARKING MANAGEMENT PLAN

A Parking Management Plan must be submitted to and approved by Council's Director City Planning, Development & Transport. The Parking Management Plan must include the operational details for use of the car lift by staff and service vehicles to ensure the car lift does not result in queueing along Elizabeth Lane, including but not limited to details on the following:

- (a) User instructions for using the car lift;
 - (b) Access codes and/or remote controls for gate to car lift;
 - (c) Staff emergency contact number;
 - (d) Training manual for staff;
 - (e) Contingency plan in the event the car lift fails; and
 - (f) Manufacturer details of the selected vehicle lift.
- (2)** Evidence that will sufficiently enable Council to be satisfied as to those matters identified in deferred commencement conditions, as indicated above, must be submitted to Council within 24 months of the date of determination of this deferred commencement consent failing which, this deferred development consent will lapse pursuant to section 4.53(6) of the Environmental Planning and Assessment Act 1979.
 - (3)** The consent will not operate until such time that the Council notifies the Applicant in writing that deferred commencement consent conditions, as indicated above, have been satisfied.
 - (4)** Upon Council giving written notification to the Applicant that the deferred commencement conditions have been satisfied, the consent will become operative from the date of that written notification, subject to the conditions of consent, as detailed in Part B Conditions of Consent (Once the Consent is Operation).

(B) PART B – CONDITIONS OF CONSENT

SCHEDULE 1A

APPROVED DEVELOPMENT/DESIGN MODIFICATIONS/COVENANTS AND CONTRIBUTIONS/USE AND OPERATION

Note: Some conditions in Schedule A are to be satisfied prior to issue of a Construction Certificate and some are to be satisfied prior to issue of Occupation Certificate, where indicated.

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2018/774 dated 10 July 2018, as amended, and the following drawings prepared by Turner:

Drawing Number	Drawing Name	Date
DA-110-007, Rev H	Basement 01	15.08.19
DA-110-008, Rev H	Ground Level	15.08.19
DA-110-010, Rev H	Level 01	15.08.19
DA-110-020, Rev H	Level 02	15.08.19
DA-110-030, Rev H	Level 03	15.08.19
DA-110-040, Rev H	Roof Level	15.08.19
DA-250-001, Rev E	East Elevation	15.08.19
DA-250-101, Rev E	North Elevation	15.08.19
DA-250-201, Rev E	West Elevation	15.08.19
DA-250-301, Rev E	South Elevation	15.08.19
DA-350-001, Rev F	Section AA	15.08.19
DA-350-101, Rev F	Section BB	15.08.19
DA-350-201, Rev A	Section CC	15.08.19
DA-350-201, Rev A	Section DD	15.08.19

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the plans will prevail.

(2) SECTION 7.11 CONTRIBUTIONS PAYABLE - CONTRIBUTION TOWARDS PUBLIC AMENITIES – CITY OF SYDNEY DEVELOPMENT CONTRIBUTIONS PLAN 2015 – [EAST] PRECINCT

Council has identified the development will increase demand for public amenities and facilities. Pursuant to Section 7.11 of the Environmental Planning and Assessment Act, 1979 (as amended), and the City of Sydney Development Contributions Plan 2015 the following monetary contributions are required towards the cost of public amenities.

<u>Contribution Category</u>	<u>Amount</u>
Open Space	\$498,724.97
Community Facilities	\$20,372.08
Traffic and Transport	\$18,345.33
Stormwater Drainage	\$0.00
Total	\$537,432.37

The City of Sydney will index the above contribution for inflation at the time of payment using the following formula.

$$C_{\text{payment}} = C_{\text{consent}} \times (CPI_{\text{payment}} \div CPI_{\text{consent}})$$

Where:

C_{payment} = Is the contribution at time of payment;

C_{consent} = Is the contribution at the time of consent, as shown above;

CPI_{payment} = Is the Consumer Price Index (All Groups Index) for Sydney published by the Australian Bureau of Statistics that applies at the time of payment; and

CPI_{consent} = Is the Consumer Price Index (All Groups Index) for Sydney at the date the contribution amount above was calculated being 117.1. for the December 2019 quarter.

The contribution must be paid prior to the issue of any Construction Certificate in relation to this development.

Please contact Council's Planning Administration staff at planningsystemsadmin@cityofsydney.nsw.gov.au to request a letter confirming the indexed contribution amount payable.

Once the letter confirming the indexed contribution is obtained, payment may be made at any of the City's Neighbourhood Service Centres or the One Stop Shop at Town Hall House. Acceptable payment methods are EFTPOS (debit card only), cash (up to 10K only), Credit Card (up to 50K only) or a bank cheque made payable to the City of Sydney. Personal or company cheques will not be accepted.

(3) FLOOR SPACE RATIO - ALL OTHER AREAS

The following applies to Floor Space Ratio:

- (a) The Floor Space Ratio for the development must not exceed 1.47:1. For the purposes of the calculation of FSR, the Gross Floor Area of approved development is 1,2221.4sqm.
- (b) Prior to an Occupation Certificate being issued, a Registered Surveyor must provide certification of the total Gross Floor Area in the development, utilising the definition under Sydney Local Environmental Plan 2012, applicable at the time of development consent, to the satisfaction of the Principal Certifier.

(4) BUILDING HEIGHT

- (a) The height of the building must not exceed RL 55.00 (AHD) to the top of the rooftop plant, RL 54.50 (AHD) to the top of the lift overrun and RL 53.60 (AHD) to the parapet of the building, unless amended by the deferred commencement conditions.
- (b) Prior to any Occupation Certificate being issued, a Registered Surveyor must provide certification that the height of the building accords with (a) above, to the satisfaction of the Principal Certifier.

(5) APPROVED DESIGN ROOF - TOP PLANT

All roof-top plant and associated equipment must be located within the approved building envelope.

(6) MATERIALS AND SAMPLES BOARD – MAJOR DEVELOPMENT

A physical material sample board which specifies all proposed materials, finishes and colours, (including visible rainwater goods and services) keyed to each building elevation must be submitted to and approved by Council's Area Planning Manager prior to a Construction Certificate being issued. The materials and samples board must not include generic material or colour descriptions, or use terminology such as 'or similar'.

(7) REFLECTIVITY

Prior to issue of the Construction Certificate the Accredited Certifier must ensure that the visible light reflectivity from building materials used on the facade of the building does not exceed 20%.

(8) ALLOCATION OF PARKING

The number of car parking spaces to be provided for the development shall comply with the table below. Details confirming the parking numbers shall be submitted to the satisfaction of the Accredited Certifier prior to the issue of a Construction Certificate.

Car Parking Type	Number
Staff spaces Tandem spaces are only permitted for staff use	Maximum 11
Motorcycle staff parking	Maximum of 2
Service vehicle space	Minimum 1

(9) ON SITE LOADING AREAS AND OPERATION

All loading and unloading operations associated with servicing the site must be carried out within the confines of the site, at all times and must not obstruct other properties or the public way.

At all times the service vehicle docks, car parking spaces and access driveways must be kept clear of goods and must not be used for storage purposes, including garbage storage.

(10) WASTE COLLECTION AND DELIVERY VEHICLES

Waste collection and deliveries associated with the site that involve the movement of vehicles, must only occur between the hours of between 7.00am and 8.00pm Monday to Friday, and 9.00am and 5.00pm, Saturday to Sunday.

(11) WASTE/RECYCLING COLLECTION

Collection of the garbage and recycling must only occur within the basement of the subject development. Garbage and recycling must not be placed on the street.

(12) ASSOCIATED ROADWAY COSTS

All costs associated with the construction of any new road works including kerb and gutter, road pavement, drainage system and footway shall be borne by the developer. The new road works must be designed and constructed in accordance with the City's "Sydney Streets Technical Specification" including amendments and "Sydney Streets Design Code".

(13) BICYCLE PARKING AND END OF TRIP FACILITIES

- (a) The minimum number of bicycle parking spaces and end of trip facilities to be provided for the development must comply with the table below.

Bicycle Parking Type	Number	Requirements
Non-Residential staff	3	Spaces must be Class 2 bicycle facilities
Non-Residential visitor	3	Spaces must be Class 2 or Class 3 bicycle facilities
End of Trip Facility Type		
Showers with change area	1	
Personal lockers	6	

Note: Australian Standard AS 2890.3:2015 refers to class 1 as class 'A', class 2 as class 'B', and class 3 as class 'C'.

- (a) The layout, design and security of bicycle facilities must comply with the minimum requirements of:
- Australian Standard AS 2890.3:2015 Parking Facilities Part 3: Bicycle Parking Facilities,
 - 'Austroads Bicycle Parking Facilities: Guidelines for Design and Installation', and;
 - SydneyCP section 3.11.3.

The details must be submitted to and approved by the Accredited Certifier confirming compliance prior to the Construction Certificate being issued.

(14) COST OF SIGNPOSTING

All costs associated with signposting for any kerbside parking restrictions and traffic management measures associated with the development shall be borne by the developer.

(15) PARKING DESIGN

The design, layout, signage, line marking, lighting and physical controls of all off-street parking facilities must comply with the minimum requirements of Australian Standard AS/NZS 2890.1 Parking facilities Part 1: Off-street car parking, AS/NZS 2890.2 Parking facilities Part 2: Off-commercial vehicle facilities and AS/NZS 2890.6 Parking facilities Part 6: Off-street parking for people with disabilities. The details must be submitted to and approved by the Principal Certifying Authority prior to a Construction Certificate being issued.

(16) TRAFFIC WORKS

Any proposals for alterations to the public road, involving traffic and parking arrangements, must be designed in accordance with RMS Technical Directives and must be referred to and agreed to by the Local Pedestrian, Cycling and Traffic Calming Committee prior to any work commencing on site.

(17) LAND REMEDIATION (Where Site Auditor engaged)

The site is to be remediated and validated in accordance with the *Supplementary detailed site investigation and remediation action plan prepared by Epic environmental, 11th November 2019, Trim 2019/574533 and Letter of Interim advice prepared by NSW Environment Protection Authority accredited Site Auditor Peter J Ramsay, 11th November 2019, reference Ltr-001-979.2*

All remediation work carried out shall be conducted in accordance with the guidelines in force from time to time under the *Contaminated Land Management Act 1997*.

Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination must be immediately notified to the Council's Area Planning Manager, the Site Auditor and the Principal Certifier.

Any variations to the approved Remediation Action Plan shall be approved in writing by the Site Auditor and Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the commencement of such work.

(18) NOTIFICATION – NEW CONTAMINATION EVIDENCE

Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination shall be notified to Council's Area Planning Manager and the Principal Certifier.

(19) SITE AUDIT STATEMENT

Prior to the issue of a construction certificate associated with the built form of the development (excluding building work directly related to remediation), a Section A Site Audit Statement must be obtained from a NSW Environment Protection Authority accredited Site Auditor and submitted to the Council's Area Planning Manager at email address:-

hbapplications@cityofsydney.nsw.gov.au

The Site Audit Statement must confirm that the site has been remediated in accordance with the approved Remedial Action Plan and clearly state that site is suitable for the proposed use.

- (a) In circumstances where the Site Audit Statement is subject to conditions that require ongoing review by the Auditor or Council, these must be reviewed and must be approved by the Council's Health and Building

department in writing through the Area Planning Manager before the Site Audit Statement is issued.

- (b) In circumstances where the Site Audit Statement conditions (if applicable) are not consistent with the consent, the development must not proceed until the inconsistency has been resolved to the satisfaction of Council (such as via a S4.55 modification of the consent pursuant to the provisions of the *Environmental Planning & Assessment Act 1979*).
- (c) **No Occupation Certificate is to be issued** by the Principal Certifier unless a Site Audit Statement has been submitted to and approved by Council in accordance with this condition.

(20) NOISE – COMMERCIAL PLANT

- (a) Noise from commercial plant and industrial development must not exceed a project amenity/intrusiveness noise level or maximum noise level in accordance with relevant requirements of the NSW EPA [Noise Policy for Industry 2017 \(NPfI\)](#) unless agreed to by the City's Area Planning Manager. Further:
 - (i) Background noise monitoring must be carried out in accordance with the long-term methodology in [Fact Sheet B](#) of the NPfI unless otherwise agreed by the City's Area Planning Manager.
 - (ii) Commercial plant is limited to heating, ventilation, air conditioning, refrigeration and energy generation equipment.
- (b) An $L_{Aeq,15\text{ minute}}$ (noise level) emitted from the development must not exceed the $L_{A90, 15\text{ minute}}$ (background noise level) by more than 3dB when assessed inside any habitable room of any affected residence or noise sensitive commercial premises at any time. Further:
 - (i) The noise level and the background noise level shall both be measured with all external doors and windows of the affected residence closed.
 - (ii) Background noise measurements must not include noise from the development but may include noise from necessary ventilation at the affected premise.
- (b) Corrections in [Fact Sheet C](#) of the NPfI are applicable to relevant noise from the development measured in accordance with this condition, however duration corrections are excluded from commercial noise.

(21) VISITOR AND TOURIST ACCOMMODATION - USE AND OPERATION

The use and operation of the premises must comply with the requirements of Schedule 2 (Standards for Places of Shared Accommodation) of the Local Government (General) Regulation, 2005 under the Local Government Act 1993, the Public Health Act, 2010 and regulations thereunder and *Sydney Development Control Plan 2012 – 4.4.8*.

(22) NUMBER OF ADULTS PER ROOM

No more than two adults shall occupy any hotel room at any given time.

(23) MAXIMUM LENGTH OF STAY

The maximum permitted length of stay is 3 months.

(24) USE AS HOTEL ACCOMMODATION

No consent is given or implied to the use of the hotel accommodation as a backpacker's accommodation at any time.

(25) HOURS OF OPERATION – LICENSED CAFE

The hours of operation are restricted to between 7.00am – 9.00pm, Monday to Sunday.

(26) CAFE – USE

The primary purpose of the licensed cafe is as a cafe with the kitchen to be open and substantial food service to be available to patrons at all times during the approved hours of operation. The sale and supply of liquor shall cease when the kitchen ceases to operate.

(27) PLAN OF MANAGEMENT

- (a) The Plan of Management (POM) checklist accompanying this Development Application has not been approved by this consent.
- (b) A POM must be prepared to address all operational and management procedures to be employed, to ensure that the hotel and licensed cafe can operate without disturbance to the surrounding locality.
- (c) At a minimum the POM must address the requirements of Section 4.4.8 and Schedule 3 of the Sydney Development Control Plan 2012.
- (d) The POM must include but not be restricted to; compliance with all other operational conditions of this consent; hours of operation; noise; security management; and handling complaints.
- (e) The POM must be submitted to and approved by Council's Area Coordinator Planning Assessments or Area Planning Manager prior to a Construction Certificate being issued.
- (f) At all times, the use of the premises must be operated in accordance with the approved POM under part (e) of this condition.

(28) PARKING MANAGEMENT PLAN

Operation of the car lift must at all times comply with the approved Parking Management Plan prepared in accordance with deferred commencement condition 2 of this consent.

(29) MAXIMUM CAPACITY OF PERSONS – LICENSED CAFE

- (a) The maximum number of persons (including staff, patrons and performers) permitted in the licensed cafe at any one time is 40.
- (c) The manager/licensee is responsible for ensuring the number of persons in the premises does not exceed that specified above.
- (d) A sign in letters not less than 25mm in height must be fixed at the main entry point to the premises alongside the Licensee's name stating the maximum number of persons, as specified in the development consent, that are permitted in the building. Details are to be provided to the satisfaction of the Accredited Certifier prior to issue of a Construction Certificate and the Principal Certifier is to confirm compliance prior to the issue of an Occupation Certificate.

(30) NEIGHBOURHOOD AMENITY

- (a) Signs must be placed in clearly visible positions within the building requesting patrons upon leaving the premises to do so quickly and quietly, having regard to maintaining the amenity of the area. The signage shall be in bold letters not less than 25mm in height on a contrasting background.
- (b) The management/licensee must ensure that the behaviour of patrons entering and leaving the premises does not detrimentally affect the amenity of the neighbourhood.

(31) NO SPEAKERS OR MUSIC OUTSIDE

Speakers and/or noise amplification equipment must not be installed and music must not be played in any of the outdoor areas associated with the premises including the public domain. Speakers located within the premises must not be placed so as to direct the playing of music towards the outdoor areas associated with the premises.

(32) NOISE FROM GLASS REMOVAL

Glass must not be emptied or transferred from one receptacle to another anywhere in a public place. All glass must be emptied / transferred inside of the building on the premises and removed in containers.

(33) SURVEILLANCE CAMERAS

- (a) CCTV surveillance cameras shall be strategically installed, operated and maintained throughout the premises with particular coverage to:
 - (i) principal entrance/s and exits;
 - (ii) all areas within the premise occupied by the public (excluding toilets);
 - (iii) staircases in multilevel premises; and

- (iv) the area within a 10m radius external to the public entrance(s) to the premise.
- (b) Suitable and clearly visible signage shall be displayed at the principal entrance(s) to the premise and in a prominent position on each floor accessible to the public, in lettering not less than 50mm in height with the words "Closed Circuit Television in use on these premises".
- (c) All CCTV recording equipment and cameras shall be of high grade digital quality capable of establishing the population and identification of patrons, offenders and incidents within the depth of field view of the cameras. In this respect each surveillance camera shall be capable of recording a minimum rate of 10 frames per second and at high resolution.
- (d) CCTV recording discs or hard drive recordings shall be retained for 28 days before being re-used, destroyed or deleted. Time and date shall be auto recorded on the disc or hard drive. The CCTV recording equipment shall be capable of reproducing a CD, DVD, USB or other appropriate digital copy of recorded footage on demand of Council or Police Officers either immediately or within 12 hours of the request being made. Copy discs must be handed to Council, Police Officer or Special Inspectors as required.
- (e) All CCTV recording devices and cameras shall be checked daily to ensure the equipment is operating correctly. The Licensee shall record this daily checking activity in the security/incident register book that meets the standards required by the Licensing Police and Council. If it is discovered at any time that the equipment is not in full operating order all reasonable steps must be taken to repair the system as soon as practicable. Where the system will not be functioning in full operating order for a period of longer than 24 hours the manager/licensee is to notify the relevant Local Area Commander of the NSW Police.
- (f) All CCTV recording devices and cameras shall be operated at all times when the premises are open to the public and, where premises do not operate 24 hours a day, continuously for at least 1 hour prior to opening and closing times of the premises.
- (g) The CCTV recording device shall be secured within the premises and only be accessible to senior management personnel so as to maintain the integrity of the recorded footage. When the premises is operating there must be at least one staff member present at the premises who is authorised to access the CCTV system and able to immediately review recordings and produce copies.
- (h) Camera views are not to be obstructed by temporary or permanent structures, signage or other impediments.

(34) UNDER AWNING LIGHTING

Illumination from the under awning lighting, when measured from any place in the public domain, must comply with the following:

- (a) the horizontal luminance level must not exceed 200 lux (including reflectivity from exterior finishes). The lux level may be increased to 220 lux in some areas in Central Sydney CBD;
- (b) the horizontal illuminance uniformity ratio (E_{avg}/E_{min}) must not exceed 4:1 to ensure safe movement of pedestrians;
- (c) the intensity, colour, period of intermittency and hours of illumination must be varied if, at any time in the opinion of the Council, adverse impact or Obtrusive Light in accordance with the definition in Australian Standard AS4282-1997 *Control of the obtrusive effects of outdoor lighting* is being caused to the amenity of the area;
- (d) where nearby residents are located above the level of the under awning lighting, details are to be provided to show that light is not directed upwards toward such residences; and
- (e) batten type fluorescent lighting is not permitted to be used for under awning lighting.

(35) EXTERNAL LIGHTING

A separate development application is required to be lodged and approved prior to any external floodlighting or illumination of the building (except for under awning lighting specified in condition 35) or site landscaping.

(36) ALCOVE LIGHTING

The proposed alcoves adjacent to the northern side boundary on Elizabeth Street (north-west corner) and Elizabeth Lane (north-east corner) shall be fitted with a sensor-activated vandal proof security light. The light shall be maintained in good working order to Council's satisfaction. The intensity, colour, and illumination must be varied if, at any time in the opinion of the consent authority, adverse impact or Obtrusive Light in accordance with the definition in Australian Standard AS4282-1997 *Control of the obtrusive effects of outdoor is being caused to the amenity of the area.*

(37) AWNING MAINTENANCE

The awning must be inspected and regular maintenance be carried out to ensure the awning's structural integrity, aesthetic and functional qualities are maintained.

(38) NO AIR CONDITIONING UNITS TO FACADE OR BALCONIES OF BUILDING

Approval is not granted for the installation of individual air conditioning units to the facade or balconies of the building.

(39) SWINGING DOORS OVER PUBLIC WAY

Any access doors to enclosures housing building services and facilities, such as hydrant and sprinkler booster assemblies or the like, must not open over the footway/roadway.

(40) SIGNAGE STRATEGY

Prior to the issue of a Construction Certificate for above ground works, a signage strategy for the building must be submitted to and approved by Council's Area Planning Manager. The signage strategy must be prepared in accordance with Section 3.16 of Sydney Development Control Plan 2012 and is to include information and scale drawings of the location, type, construction, materials and total number of signs appropriate for the building.

(41) SIGNS - SEPARATE DA REQUIRED

A separate development application for any proposed signs additional to those approved as part of this consent (other than exempt or complying signs) must be submitted to and approved by Council prior to the erection or display of any such signs.

(42) ALL TREES MUST BE RETAINED

Approval is not granted for the removal of any trees.

SCHEDULE 1B

PRIOR TO CONSTRUCTION CERTIFICATE/COMMENCEMENT OF WORK/HEALTH AND BUILDING

(43) ACCESS AND FACILITIES FOR PERSONS WITH DISABILITIES

The building must be designed and constructed to provide access and facilities for people with a disability in accordance with the *Building Code of Australia*.

If, in complying with this condition, amendments to the development are required, the design changes must be submitted to and approved by Council prior to a Construction Certificate being issued.

(44) ASBESTOS REMOVAL WORKS

- (a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence shall be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.
- (c) All work must be carried out in accordance with the *Work Health and Safety Regulation 2017* and the NSW Government and SafeWork NSW document entitled *How to manage and control asbestos in the work place: Code of Practice (Safework NSW) December 2011* and the *City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines*.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.
- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 -

1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.

- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).
- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.
- (i) A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

(45) EXTERNAL WALLS AND CLADDING FLAMMABILITY

The external walls of the building including attachments must comply with the relevant requirements of the Building Code of Australia (BCA). Prior to the issue of a Construction Certificate and Occupation Certificate the Accredited Certifier and the Principal Certifier must:

- (a) Be satisfied that suitable evidence is provided to demonstrate that the products and systems proposed for use or used in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the relevant requirements of the BCA; and
- (b) Ensure that the documentation relied upon in the approval processes include an appropriate level of detail to demonstrate compliance with the BCA as proposed and as built.

(46) FLASHINGS TO BOUNDARY WALLS

A flashing must be provided to prevent water entering between the proposed and existing external boundary walls of the adjoining properties.

Note: Attachments or connections to party walls may require the consent of the adjoining property owner/s.

(47) OPERATING HOISTING DEVICES INCLUDING BUILDING MAINTENANCE UNITS OVER A PUBLIC ROAD

If it is proposed to install a building maintenance unit or operate a hoisting device above a road (footpath) including swinging, hoisting material/equipment

and slewing any part of the device, a separate application under Section 68 of the *Local Government Act 1993* and Section 138 of the *Roads Act 1993* must be made to Council to obtain approval.

Note: Building maintenance unit means a power operated suspended platform and associated equipment on a building specifically designed to provide permanent access to the faces of the building for maintenance (*Work Health and Safety Regulation 2017*).

(48) PRODUCTS BANNED UNDER THE BUILDING PRODUCTS (SAFETY) ACT 2017

- (a) No building products that are banned, or products that are subject to a ban if used in a particular way, under the Building Products (Safety) Act 2017 are to be used in the construction of the development approved in this development consent.
- (b) Prior to the issue of any Occupation Certificate, the principal certifier is to confirm that none of the building products used on the building are subject to a building product use ban under the Building Products (Safety) Act 2017 or, if a product is only subject to a ban if used in a particular way that it is not used in any way contrary to the Building Products (Safety) Act 2017.

(49) STRUCTURAL CERTIFICATION FOR DESIGN – BCA (ALL BUILDING CLASSES)

Prior to the issue of a Construction Certificate, structural details and a Structural Certificate for Design by a qualified practising structural engineer and in accordance with Clause A5.2(1)(e) of the Building Code of Australia must be submitted to the satisfaction of Council (where Council is the Accredited Certifier).

(50) CONSTRUCTION TRAFFIC MANAGEMENT PLAN

A Construction Traffic Management Plan must be submitted to and approved by Council prior to a Construction Certificate being issued.

(51) DEMOLITION, EXCAVATION AND CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

A site specific noise management plan shall be submitted to the Council for comment and approval prior to issue of any Construction Certificate. The Plan must be prepared by a suitably qualified person who possesses the qualifications to render them eligible for membership of the Australian Acoustic Society, Institution of Engineers Australia or the Australian Association of Acoustic Consultants. The plan must include but not be limited to the following:-

- (a) Identification of noise sensitive receivers near to the site.
- (b) A prediction as to the level of noise impact likely to affect the nearest noise sensitive receivers from the use and proposed number of high noise intrusive appliances intended to be operated onsite. A statement should also be submitted outlining whether or not predicted noise levels

will comply with the noise criteria stated within the *City of Sydney Construction Hours /Noise Code of Practice 1992* for the typical construction hours of 07.00am to 7.00pm. Where resultant site noise levels are likely to be in exceedance of this noise criteria then a suitable proposal must be given as to the duration and frequency of respite periods that will be afforded to the occupiers of neighbouring property.

- (c) A representative background noise measurement ($L_{A90, 15 \text{ minute}}$) should be submitted, assessed in the vicinity of any potentially affected receiver locations and measured in accordance with AS 1055:1.2.1997.
- (d) Confirmation of the level of community consultation that has/is and will be undertaken with Building Managers/ occupiers of the main adjoining noise sensitive properties likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.
- (e) Confirmation of noise monitoring methodology that is to be undertaken during the main stages of work at neighbouring noise sensitive properties in order to keep complaints to a minimum and to ensure that noise from site works complies with the noise criteria contained within City's Construction Noise Code.
- (f) What course of action will be undertaken following receipt of a complaint concerning offensive noise?
- (g) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupiers of neighbouring noise sensitive property to a minimum.
- (h) What plant and equipment is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on the occupiers of neighbouring property and other less intrusive technologies available.

(52) COMPLIANCE WITH DEMOLITION, EXCAVATION & CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

- (a) All works conducted on site which form part of this development must be carried out in accordance with the submitted and written approved Demolition, Excavation and Construction Management Plan.
- (b) Where all such control measures have been implemented and the resultant noise and/ or vibration levels at any sensitive receiver still exceed the council's applicable criteria stated in the Construction Hours/Noise Code 1992 and are giving rise to sustained complaints then the contractor must provide regular, appropriate and sustained periods of respite in consultation with Council's Health and Building unit. Approval to vary the authorised noise and vibration levels must be received in writing by the proponent from Council prior to activities being undertaken that exceed sanctioned emission levels.

Such periods must be set and agreed to by Council's Health and Building Unit.

(53) COMPLIANCE WITH THE ACOUSTIC REPORT PRIOR TO CONSTRUCTION AND OR OCCUPATION CERTIFICATES

- (a) All relevant performance parameters (including but not limited to requirements, engineering assumptions and recommendations) in the DA Acoustic Report prepared by Acouras Consultancy, '589-591 Elizabeth Street, Redfern' document reference SYD2018-1032-R0011, 03/07/2018, Trim 2018/367566 must be implemented in the development prior to the commencement of its use.
- (b) Prior to the issue of any relevant Construction Certificate, the final construction drawings and final construction methodology must be assessed and reported to be in accordance with the requirements of the DA Acoustic Report in (a) above, with reference to relevant documentation including specifications of the vehicle lift. This must be done by a Suitably Qualified Acoustic Consultant* (see definition below). This work will be to the satisfaction of the certifier.
- (c) Prior to the issue of an Occupation Certificate, a Suitably Qualified Acoustic Consultant* is to provide a written Acoustic Verification Report to the satisfaction of the Principal Certifier/Principal certifying Authority that the development complies with the requirements set out in the Report and in (a) and (b) above.

Note: *Suitably Qualified Acoustic Consultant* means a consultant who possesses the qualifications to render them eligible for membership of the Australian Acoustics Society, Institution of Engineers Australia or the Association of Australian Acoustic Consultants at the grade of member.

- (d) All physical aspects of the building's structure installed in order to meet performance parameters in accordance with this condition must be maintained at all times.

(54) DEMOLITION, EXCAVATION AND CONSTRUCTION MANAGEMENT

- (a) Prior to the commencement of demolition and/or excavation work the following details must be submitted to and be approved by the Principal Certifier:
 - (i) Plans and elevations showing distances of the subject building from the location of adjoining and common/party walls, and (where applicable) the proposed method of facade retention.
 - (ii) A Demolition Work Method Statement prepared by a licensed demolisher who is registered with the Work Cover Authority. (The demolition by induced collapse, the use of explosives or on-site burning is not permitted.)
 - (iii) An Excavation Work Method Statement prepared by an appropriately qualified person.

- (iv) A Waste Management Plan for the demolition and or excavation of the proposed development.
- (v) Plans and elevations showing the location, construction and installation of temporary site fencing and any temporary structures used in connection with the construction of the development.

Note: Temporary structures, including hoardings and scaffolding, proposed for erection on City-owned and controlled land (footways and roadways), must comply with the City's *Guidelines for Hoardings and Scaffolding* and be approved by Council under the provisions of the Local Government Act 1993 and the Roads Act 1993 prior to installation.

- (b) Such statements must, where applicable, be in compliance with AS2601-2001 Demolition of Structures, the *Work, Health and Safety Act 2011* and Regulation; Council's *Policy for Waste Minimisation in New Developments 2005*, the *Waste Avoidance and Resource Recovery Act 2001*, and all other relevant acts and regulations and must include provisions for:
 - (i) A Materials Handling Statement for the removal of refuse from the site in accordance with the *Waste Avoidance and Resource Recovery Act 2001*.
 - (ii) The name and address of the company/contractor undertaking demolition/excavation works.
 - (iii) The name and address of the company/contractor undertaking off site remediation/disposal of excavated materials.
 - (iv) The name and address of the transport contractor.
 - (v) The type and quantity of material to be removed from site.
 - (vi) Location and method of waste disposal and recycling.
 - (vii) Proposed truck routes, in accordance with this development consent.
 - (viii) Procedures to be adopted for the prevention of loose or contaminated material, spoil, dust and litter from being deposited onto the public way from trucks and associated equipment and the proposed method of cleaning surrounding roadways from such deposits. (Note: With regard to demolition of buildings, dust emission must be minimised for the full height of the building. A minimum requirement is that perimeter scaffolding, combined with chain wire and shade cloth must be used, together with continuous water spray during the demolition process. Compressed air must not be used to blow dust from the building site).
 - (ix) Measures to control noise emissions from the site.
 - (x) Measures to suppress odours.
 - (xi) Enclosing and making the site safe.

- (xii) Induction training for on-site personnel.
 - (xiii) Written confirmation that an appropriately qualified Occupational Hygiene Consultant has inspected the building/site for asbestos, contamination and other hazardous materials, in accordance with the procedures acceptable to SafeWork NSW.
 - (xiv) An Asbestos and Hazardous Materials Clearance Certificate by a person approved by the SafeWork NSW.
 - (xv) Disconnection of utilities.
 - (xvi) Fire Fighting. (Fire fighting services on site are to be maintained at all times during demolition work. Access to fire services in the street must not be obstructed).
 - (xvii) Access and egress. (Demolition and excavation activity must not cause damage to or adversely affect the safe access and egress of the subject building or any adjacent buildings).
 - (xviii) Waterproofing of any exposed surfaces of adjoining buildings.
 - (xix) Control of water pollution and leachate and cleaning of vehicles tyres (proposals must be in accordance with the *Protection of the Environmental Operations Act 1997*).
 - (xx) Working hours, in accordance with this development consent.
 - (xxi) Any SafeWork NSW requirements.
- (c) The approved work method statements and a waste management plan as required by this condition must be implemented in full during the period of construction.

(55) DILAPIDATION REPORT – MAJOR EXCAVATION/DEMOLITION

- (a) Subject to the receipt of permission of the affected landowners, dilapidation reports (including a photographic survey) for No. 587 Elizabeth Street, No. 593-601 Elizabeth Street and Nos. 27 – 39 Great Buckingham Street, Redfern, are to be prepared by an appropriately qualified structural engineer prior to commencement of demolition/excavation works. A copy of the dilapidation report/s together with the accompanying photographs must be given to the above property owners, and a copy lodged with the Accredited Certifier and the Council prior to the issue of a Construction Certificate.

UPON COMPLETION OF EXCAVATION/DEMOLITION

- (b) A second Dilapidation Report/s, including a photographic survey must then be submitted at least one month after the completion of demolition/excavation works. A copy of the second dilapidation report/s, together with the accompanying photographs must be given to the above property owners, and a copy lodged with the Principal Certifier and the Council prior to the issue of any Occupation Certificate.

Any damage to buildings, structures, lawns, trees, sheds, gardens and the like must be fully rectified by the applicant or owner, at no cost to the affected property owner.

Note: Prior to the commencement of the building surveys, the applicant/owner must advise (in writing) all property owners of buildings to be surveyed of what the survey will entail and of the process for making a claim regarding property damage. A copy of this information must be submitted to Council.

(56) EROSION AND SEDIMENT CONTROL - BETWEEN 250 AND 2,500SQM

Prior to the commencement of demolition/excavation/construction work, an Erosion and Sediment Control Plan (ESCP) must be submitted to and be approved by the Principal Certifier. The ESCP must:

- (a) Conform to the specifications and standards contained in *Managing Urban Stormwater: Soils and Construction* (Landcom, 2004); the *Guidelines for Erosion and Sediment Control on Building Sites* (City of Sydney, 2004); and the *NSW Protection of the Environment Operations Act 1997*.
- (b) Include a drawing(s) that clearly shows:
 - (i) location of site boundaries and adjoining roads
 - (ii) approximate grades and indications of direction(s) of fall
 - (iii) approximate location of trees and other vegetation, showing items for removal or retention
 - (iv) location of site access, proposed roads and other impervious areas
 - (v) existing and proposed drainage patterns with stormwater discharge points
 - (vi) north point and scale
- (c) Specify how soil conservation measures will be conducted on site including:
 - (i) timing of works
 - (ii) locations of lands where a protective ground cover will, as far as is practicable, be maintained
 - (iii) access protection measures
 - (iv) nature and extent of earthworks, including the amount of any cut and fill
 - (v) where applicable, the diversion of runoff from upslope lands around the disturbed areas
 - (vi) location of all soil and other material stockpiles including topsoil storage, protection and reuse methodology

- (vii) procedures by which stormwater is to be collected and treated prior to discharge including details of any proposed pollution control device(s)
- (viii) frequency and nature of any maintenance program
- (ix) other site-specific soil or water conservation structures.

(57) ROAD OPENING PERMIT

A separate Road Opening Permit under Section 138 of the *Roads Act 1993* must be obtained from Council prior to the commencement of any:

- (a) Excavation in or disturbance of a public way, or
- (b) Excavation on land that, if shoring were not provided, may disturb the surface of a public road (including footpath).

(58) MECHANICAL PARKING FACILITIES (CAR LIFT)

The following details being submitted to an approved by the Accredited Certifier prior to the issue of the issue of a Construction Certificate:

- (a) A review of the proposed installation by the manufacturer and its suitability for implementation in accordance with the manufacturer's specifications including but not limited to compliance with AS/NZS 2890.1 2004 and its references to AS/NZS 28590.6.

(59) TEMPORARY GROUND ANCHORS, TEMPORARY SHORING AND PERMANENT BASEMENT/RETAINING WALLS AFFECTING THE ROAD RESERVE

For temporary shoring including ground anchors affecting the road reserve, a separate application under Section 138 of the *Roads Act 1993* must be lodged with Council.

(60) LANDSCAPING OF THE SITE

- (a) A detailed landscape plan, drawn to scale, by a qualified landscape architect or landscape designer, must be submitted to and approved by Council's Area Coordinator Planning Assessments or Area Planning Manager prior to the issue of a Construction Certificate for above ground building works. The plan must include:
 - (i) Location of existing and proposed structures on the site including, but not limited to, existing and proposed trees, paved areas, planted areas on slab, planted areas in natural ground, lighting and other features;
 - (ii) Details of earthworks and soil depths including mounding and retaining walls and planter boxes (if applicable). The minimum soil depths for planting on slab must be 1000mm for trees, 450mm for shrubs and 200mm for groundcovers;

- (iii) Location, numbers, type and supply of plant species, with reference to NATSPEC (if applicable);
 - (iv) Details of planting procedure and maintenance;
 - (v) Details of drainage, waterproofing and watering systems.
 - (vi) Provision of a substantial tree within the courtyard tree pit.
- (b) Prior to the issue of a Construction Certificate, a maintenance plan is to be submitted to and approved by the Accredited Certifier. The maintenance plan is to be complied with during occupation of the property.
- (c) All landscaping in the approved plan is to be completed prior to any Occupation Certificate being issued.

(61) LANDSCAPED (GREEN) ROOFS

- (a) A detailed plan of the green roofs, drawn to scale, by a qualified landscape architect or landscape designer, must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the issue of a Construction Certificate. The plan must include:
- (i) Location of existing and proposed structures, services and hard landscaping on the rooftop, roof fixings and other structural elements that may interrupt waterproofing, including cross-sectional details of all components.
 - (ii) Details of earthworks including mounding and retaining walls and planter boxes (if applicable).
 - (iii) Details of the location, sizes and numbers of plants used with reference to NATSPEC (if applicable), with preference for drought resistant species.
 - (iv) Details of the soil media/substrate type and depth.
 - (v) Details of installation methodology e.g. safety considerations for working at height, location of maintenance hooks (if applicable) transport materials etc.
 - (vii) Details of drainage and irrigation systems, including overflow provisions and water retention cells in the drainage layer (if applicable).
- (b) Prior to the issue of a Construction Certificate, the following details are to be submitted to and approved by the Accredited Certifier:
- (i) Evidence the green roof has been assessed as part of the structural certification provided for the development; and
 - (ii) Evidence the green roof has been assessed as part of the waterproofing certification provided for the development.

- (c) All landscaping in the approved plan is to be completed prior to the issue of any Occupation Certificate.
- (d) Prior to the issue of any Occupation Certificate, a maintenance plan is to be submitted and approved by the Principal Certifier. A copy of the maintenance plan is to be kept on site at all times during construction and shall be produced to Council on request following completion. The Maintenance Manual shall include as a minimum:
 - (i) Frequency and methodology of different maintenance requirements including the removal of green waste.
 - (ii) Details of safety procedures.
 - (iii) Laminated copies of 'As Built' drawings.
 - (iv) Manufacturer's contact details and copies of manufacturers' typical details and specification;
 - (v) Copies of warranties and guarantees relating to all materials and plant used in construction; and
 - (vi) Decommissioning procedures.
- (e) The green roofs are required to remain inaccessible, except for the purposes of maintenance only.

(62) CAR PARK VENTILATION

The car park must be ventilated in accordance with the *Building Code of Australia* and, where necessary, Australian Standard AS1668, Parts 1 and 2. Ventilation must be controlled by carbon monoxide monitoring sensors to ensure compliance with occupant health requirements.

(63) AIR HANDLING

In the event of any process in any room being of such a nature that heat, excessive moisture, dangerous or noxious gases, fumes or other aerosols are given-off, an air handling system must be installed providing positive capture and removal of the effluents. The effluent must be discharged to atmosphere at a point that will not create a nuisance and located in a position complying with *AS1668.2 - The Use of Ventilation and Air-Conditioning in Buildings - Mechanical Ventilation in Buildings*.

(64) DEWATERING

- (a) If any dewatering of the site is to be undertaken, a bore licence may be required from the NSW Office of Water under the provisions of Part V of the Water Act 1912. The NSW Office of Water licences dewatering to allow excavation for construction for a temporary period, usually 12 months.

NOTE: The Department's instructions to Council are that they will not endorse the extraction of groundwater in perpetuity i.e. permanent dewatering around a development site, because it considers such

development to be unsuitable. For this reason any proposed basement or other area that requires dewatering on an on-going basis may need to be fully tanked.

- (b) Prior approval must also be sought from the City's Public Domain Unit to discharge any groundwater into the City's stormwater drainage system. Other options for the disposal of groundwater include disposal to sewer with prior approval from Sydney Water, or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

(65) INSTALLATION OF DUAL-FLUSH TOILETS

All toilets installed within the development must be of water efficient dual-flush or other water-saving capacity with at least a 4-star rating under the Water Efficiency and Labelling Scheme (WELS). The details must be submitted for the approval of the Accredited Certifier, prior to a Construction Certificate being issued.

(66) INSTALLATION OF WATER EFFICIENT TAPS

All taps and shower heads installed must be water efficient with at least a 4-star rating under the Water Efficiency and Labelling Scheme (WELS). The details are to be submitted for the approval of the Principal Certifier, prior to any Occupation Certificate being issued.

(67) COMPLIANCE WITH ARBORIST'S REPORT

All recommendations contained in the Arborist's Report (Revision F) prepared by Urban Arbor, dated 9 October 2019 and supplementary Statement prepared by Urban Arbor (Ref:18/11/07/589ESR) must be implemented during construction and use of the development.

(68) SERVICES

- (a) Any trenching works for services / hydraulics / drainage etc must not be undertaken within a Tree Protection Zone (TPZ), and be referred to the Site Arborist with regard to tree protection, prior to commencement of any works.
- (b) Alternative installation methods for services, such as directional boring/drilling, or redirection of services shall be employed where large woody roots greater than 40mm diameter are encountered during the installation of any services adjacent to the specified TPZ.

(69) SITE SUPERVISION AND REPORTING

- (a) An Arborist with minimum qualifications in Arboriculture of Level 5 (under the Australian Qualification Framework) must oversee various stages of work within the Tree Protection Zone in accordance with Australian Standard AS4970 Protection of Trees on Development Sites. The Arborist must certify compliance with each key milestone detailed below to the Area Planning Manager:

- (i) The installation of tree protection measures prior to the issuing of a Construction Certificate;
 - (ii) During any excavation and trenching within the Tree Protection Zone.
 - (iii) During demolition of all buildings/structures (including slabs),
 - (iv) During excavation and construction of the basement; and
 - (v) During the construction of the new building within close proximity to TPZs.
- (b) A fortnightly compliance report shall be submitted to the Area Planning Manager which provides details on the health and structure of tree to be retained and protected and must include:
- (i) Certification of compliance with each key milestone;
 - (ii) Details of any other works undertaken on any tree to be retained or within TPZ/s;
 - (iii) Documentary evidence of compliance with tree protection and measures (including photographs and site notes);
 - (iv) Ensure that the soil moisture is appropriate and the irrigation system is functioning in accordance with the Arborist's specifications.

(70) SOIL MOISTURE

- (a) An irrigation system shall be installed beneath the suspended concrete slab and within the Tree Protection Zone (TPZ), to ensure soil moisture is maintained following completion of all construction and development works.
- (b) This shall be undertaken in accordance with all specifications to be provided by the Site Arborist prior to the installation of the suspended concrete slab.

(71) STREET TREE PROTECTION

Street trees must be protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites. All street trees must be protected during the construction works as follows:

- (a) Tree trunk and major limb protection must be undertaken prior to or during the installation of any hoarding or scaffoldings. The protection must be installed by a qualified Arborist (AFQ 2 or 3) and must include:
 - (i) An adequate clearance, minimum 250mm, must be provided between the structure and tree branches, limbs and truck at all times;

- (ii) Tree trunk/s and/or major branches, located within 500mm of any hoarding or scaffolding structure, must be protected by wrapped hessian or similar material to limit damage, and
 - (iii) Timber planks (50mm x 100mm or similar) must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals, and must be fixed against the trunk with tie wire, or strapping. The hessian and timber planks must not be fixed to the tree in any instance, or in any fashion,
 - (iv) Tree trunk and major branch protection is to remain in place for the duration of construction and development works, and must be removed at the completion of the project.
- (b) All hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree setts. Supporting columns must not be placed on any tree roots that are exposed.
 - (c) Materials or goods, including site sheds, must not be stored or placed:
 - (i) around or under the tree canopy; or
 - (ii) within two (2) metres of tree trunks or branches of any street trees.
 - (d) Protective fencing (1.8 metre chain wire mesh fencing) must be erected on top of the hoarding immediately surrounding the subject trees to be retained to protect branches during the construction works.
 - (e) Any damage sustained to street tree/s as a result of the erection of hoardings, scaffolding, or due to the loading/unloading of vehicles adjacent the site, must be immediately reported to the Council's Street Tree Contract Coordinator on 9265 9333, in order to determine the appropriate action for maintaining the health and structural integrity of any damaged street tree.

(72) STREET TREE PRUNING

- (a) The consent from Council must be obtained prior to the undertaking of any street tree pruning works including tree roots greater than 40mm diameter. Only minor pruning works will be approved by Council.
- (b) Any pruning that is required to accommodate hoardings, scaffolding, or to accommodate the loading/unloading of vehicles, and has been approved by Council, must be carried out by a qualified Arborist (AQF3), and must be in accordance with AS4373 Australian Standards 'Pruning of Amenity Trees'.

(73) TREE PROTECTION DURING CONSTRUCTION

Stockpiling, storage or mixing of materials, washing of equipment, vehicle parking, disposal of liquids, machinery repairs and refuelling, disposal of building materials such as cement slurry, siting of offices or sheds and the lighting of fires, must not occur within 5m of the trunk of any tree to be retained.

(74) TREE PROTECTION ZONE

- (a) Before the commencement of works, a/the Tree Protection Zone/s (TPZ) must be established around all tree/s to be retained not less than the distance indicated in the TPZ schedule below (and as specified in the Arborist Report prepared by Urban Arbor, dated 9.10.19). Tree protection must be installed and maintained in accordance with the Australian Standard 4970 Protection of Trees on Development Sites.

TPZ Schedule

Tree No	Species Name	Location	Radius (m) From Trunk
1	<i>Grevilleas robusta</i> (Silky Oak)	Street tree – eastern side of Elizabeth Lane	4.9
2	<i>Macadamia spp</i> (Macadamia)	Street tree – eastern side of Elizabeth Lane	2.8
3	<i>Corymbia torelliana</i> (Cadaghi)	Street tree – eastern side of Elizabeth Lane	7.6
4	<i>Corymbia maculata</i> (Spotted Gum)	Located on No. 593-601 Elizabeth Street - Adjacent to the subject site's southern boundary	5.2
5	<i>Corymbia citriodora</i> (Lemon Scented Gum)	Street tree – western side of Elizabeth Lane	5.5
6	<i>Melaleuca quinquenervia</i> (Broad Leaved Paperbark)	Street tree – Elizabeth Street in front of No. 593-601 Elizabeth Street	7.4
7	<i>Melaleuca quinquenervia</i> (Broad Leaved Paperbark)	Street tree – Elizabeth Street in front of the subject site	8.9

Tree No	Species Name	Location	Radius (m) From Trunk
8	<i>Melaleuca quinquenervia</i> (Broad Leaved Paperbark)	Street tree – Elizabeth Street in front of No. 587 Elizabeth Street	8.6

(b) Each TPZ must be:

- (i) Enclosed with a 1.8m high fully supported chainmesh protective fencing. The fencing must be secure and fastened to prevent movement. The fencing must have a lockable opening for access. Woody roots must not be damaged or destroyed during the establishment or maintenance of the fencing;
- (ii) Kept free of weed and grass for the duration of works [delete if not relevant];
- (iii) Mulch maintained to a depth of 75mm for the duration of works;
- (iv) Have two signs identifying the name and contact details of the site Arborist attached facing outwards in a visible position. All signs must remain in place throughout all work on site.

(c) The ground surface protection within the TPZ must be:

- (i) Protected with boarding (ie scaffolding board or plywood sheeting or similar material), placed over a layer of mulch to a depth of at least 75mm and geotextile fabric;
- (ii) The protective boarding must be left in place for the duration of the construction and development.

(d) The following works must be excluded from within any TPZs:

- (i) Soil cut or fill including excavation and trenching;
- (ii) Soil cultivation, disturbance or compaction;
- (iii) Stockpiling, storage or mixing of materials;
- (iv) The parking, storing, washing and repairing of tools, equipment and machinery;
- (v) The disposal of liquids and refuelling;
- (vi) The disposal of building materials;
- (vii) The siting of offices or sheds;
- (viii) Any action leading to the impact on tree health or structure.

- (e) All work undertaken within or above the TPZ must be:
 - (iii) Carried out in accordance with the work methodology statement prepared by the Consultant Arborist and approved by Council's Tree Management Officer before its implementation (including, without limitation, handling and pedestrian/ machinery access).
- (f) Any root/s over 50mm in diameter must be pruned by a qualified Arborist with a minimum of AQF Level 3 and all root pruning undertaken must be detailed in report form to Council within 1 month of the excavation being undertaken.

(75) TREE PRUNING SPECIFICATIONS

All pruning must be carried out by a qualified Arborist (AQF Level 3 Arboriculture) and must be in accordance with AS4373-2007 Australian Standard 'Pruning of Amenity Trees'.

(76) TREE ROOT PROTECTION

- (a) Excavations for the footings must be undertaken using non-destructive methods (such as an Airspade) to ensure no tree roots greater than 40mm diameter are damaged, pruned or removed.
- (b) Footings shall be relocated / realigned if any tree root greater than 40mm in diameter is encounter during excavations. A minimum of 150mm clearance shall be provided between the tree root and footing.
- (c) Excavations for any pier and beam footings located within the Tree Protection Zone (TPZ), must be supervised by a qualified Consultant Arborist, who holds the Diploma in Horticulture (Arboriculture), Level 5 under the Australian Qualification Framework.
- (d) The consent from Council must be obtained prior to the undertaking of any root pruning greater than 40mm in diameter.
- (e) All root pruning must be undertaken by a qualified Arborist with a minimum AQF level 3.

(77) TREE ROOT PROTECTION (Structural Root Zone)

Structural Root Zone (SRZ) Schedule:

Tree No	Botanical/Common Name	Tree Location	SRZ radius (m) from Trunk
1	<i>Grevilleas robusta</i> (Silky Oak)	Street tree – eastern side of Elizabeth Lane	2.5

2	<i>Macadamia spp</i> (Macadamia)	Street tree – eastern side of Elizabeth Lane	2.2
3	<i>Corymbia torelliana</i> (Cadaghi)	Street tree – eastern side of Elizabeth Lane	2.9
4	<i>Corymbia maculata</i> (Spotted Gum)	Located on No. 593-601 Elizabeth Street - Adjacent to the subject site's southern boundary	2.5
5	<i>Corymbia citriodora</i> (Lemon Scented Gum)	Street tree – western side of Elizabeth Lane	2.6
6	<i>Melaleuca quinquenervia</i> (Broad Leaved Paperbark)	Street tree – Elizabeth Street in front of No. 593-601 Elizabeth Street	2.9
7	<i>Melaleuca quinquenervia</i> (Broad Leaved Paperbark)	Street tree – Elizabeth Street in front of the subject site	3.8

- (a) Any excavation is proposed within the SRZ must be carried out in accordance with the approved Arborist Report and Australian Standards.
- (b) Any excavations within the SRZ in accordance with (a) above must be undertaken using non-destructive methods (such as by hand or with an Airspade) to ensure no tree roots greater than 40mm diameter are damaged, pruned or removed.
- (c) Footings shall be relocated / realigned if any tree root greater than 40mm in diameter is encountered during excavations. A minimum of 150mm clearance shall be provided between the tree root and footing.
- (d) All excavations located within the TPZ must be supervised by a qualified Consultant Arborist, who holds the Diploma in Horticulture (Arboriculture), Level 5 under the Australian Qualification Framework.
- (e) All root pruning must be undertaken by a qualified Arborist with a minimum AQF level 3.

(78) TREE TRUNK PROTECTION

The tree/s must be protected in accordance with the Australian Standard AS4970 Protection of Trees on Development Sites. All trees must be protected during the construction works as follows:

- (a) Tree trunk and major limb protection shall be undertaken prior to the issuing of the Construction Certificate. The protection shall be installed by a qualified Arborist with a minimum AQF level 2 and must include:
 - (i) Tree trunk/s and/or major branches must be protected by wrapped hessian or similar material to limit damage;
 - (ii) Timber planks (50mm x 100mm or similar) shall be placed around tree trunk/s. The timber planks shall be spaced at 100mm intervals, and must be fixed against the trunk with tie wire, or strapping. The hessian and timber planks must not be fixed to the tree in any instance, or in any fashion;
 - (iii) Tree trunk and major branch protection is to remain in place for the duration of construction and development works, and shall be removed at the completion of the project.

(79) SYDNEY WATER CERTIFICATE (TAP-IN)

- (a) The approved plans must be submitted to Sydney Water's "Tap-in" online service to determine whether the development will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. Sydney Water's "Tap-in" online service is available at www.sydneywater.com.au, (see Plumbing, Building & Development and then Sydney Water "Tap-in").
- (b) The Consent Authority or a Principal Certifier must ensure that Sydney Water has appropriately stamped the plans before the commencement of work.

(80) UTILITY SERVICES

To ensure that utility authorities are advised of the development:

- (a) Prior to the issue of a Construction Certificate a survey is to be carried out of all utility services within and adjacent to the site including relevant information from utility authorities and excavation if necessary, to determine the position and level of services.
- (b) Prior to the commencement of work the applicant is to obtain written approval from the utility authorities (e.g. Energy Australia, Sydney Water, and Telecommunications Carriers) in connection with the relocation and/or adjustment of the services affected by the construction of the underground structure. Any costs in the relocation, adjustment or support of services are to be the responsibility of the developer.

(81) WASTE AND RECYCLING MANAGEMENT - COMMERCIAL

- (a) The Waste and Recycling Management Plan accompanying this Development Application has not been approved by this consent.
- (b) A Waste and Recycling Management Plan is to be approved by the Principal Certifier prior to a Construction Certificate being issued. The plan must comply with the Council's *Guidelines for Waste Management in New Developments 2018*. All requirements of the approved Building Waste and Recycling Management Plan must be implemented during construction of the development.

UPON COMPLETION OF THE DEVELOPMENT

- (c) Prior to any Occupation Certificate being issued or the use commencing, whichever is earlier, the Principal Certifier must ensure that waste handling works have been completed in accordance with: the Waste and Recycling Management Plan; other relevant development consent conditions; and Council's *Guidelines for Waste Management in New Developments 2018*.

(82) STOCKPILES

- (a) No stockpiles of soil or other materials shall be placed on footpaths or nature strips unless prior approval has been obtained from the City's Construction Regulation Unit.
- (b) All stockpiles of soil or other materials shall be placed away from drainage lines, gutters or stormwater pits or inlets.
- (c) All stockpiles of soil or other materials likely to generate dust or odours shall be covered.
- (d) All stockpiles of contaminated soil shall be stored in a secure area and be covered if remaining more than 24 hours

(83) IMPORTED FILL MATERIALS

All fill imported onto the site shall be validated to ensure the imported fill is suitable for the proposed land use from a contamination perspective. Fill imported on to the site shall also be compatible with the existing soil characteristic for site drainage purposes.

The City may require details of appropriate validation of imported fill material to be submitted with any application for future development of the site. Hence all fill imported onto the site should be validated by either one or both of the following methods during remediation works:

- (a) Imported fill should be accompanied by documentation from the supplier which certifies that the material is not contaminated based upon analyses of the material for the known past history of the site where the material is obtained; and/or
- (b) Sampling and analysis of the fill material shall be conducted in accordance with NSW EPA (1995) Sampling Design Guidelines.

(84) CLASSIFICATION OF WASTE

Prior to the exportation of waste (including fill or soil) from the site, the waste materials must be classified in accordance with the provisions of the Protection of the *Environment Operations Act 1997* and the *NSW DECC Waste Classification Guidelines, Part1: Classifying Waste (July 2009)*. The classification of the material is essential to determine where the waste may be legally taken. The *Protection of the Environment Operations Act 1997* provides for the commission of an offence for both the waste owner and the transporters if the waste is taken to a place that cannot lawfully be used as a waste facility for the particular class of waste. For the transport and disposal of industrial, hazardous or Group A liquid waste advice should be sought from the EPA.

(85) FUTURE FOOD USE - MECHANICAL VENTILATION PROVISION

Prior to the issue of a Construction Certificate, the mechanical exhaust systems and/or shafts must be designed to allow for the discharge of effluent air above roof level and must be designed with capacity to accommodate exhaust ducts and mechanical ventilation systems for the cafe. Systems must be designed in accordance with *AS1668.2 – The Use of Ventilation and Air-conditioning in Buildings – Mechanical Ventilation in Buildings*, and *AS1668.1 – The Use of Mechanical Ventilation and Air-Conditioning in Buildings – Fire and Smoke Control in Multi-compartment Buildings*.

(86) FOOD PREMISES – DETAILED PLANS

- (a) Detailed and scaled plans of all kitchen, bar, food preparation, waste and storage areas, food handler toilets and all areas associated with the food business must be prepared in accordance with the *Australia New Zealand Food Standards Code – 3.2.3– Food Premises and Equipment* under the *Food Act 2003* and *AS 4674 - Design, Construction and Fit-out of Food Premises*.
- (b) Prior to the Issue of a Construction Certificate the plans required by (a) of this condition must be submitted to and approved in writing by the Accredited Certifier.

(87) CAR PARK VENTILATION

The car park must be ventilated in accordance with the *Building Code of Australia* and, where necessary, Australian Standard AS1668, Parts 1 and 2. Ventilation must be controlled by carbon monoxide monitoring sensors to ensure compliance with occupant health requirements.

(88) MECHANICAL VENTILATION

- (a) The premises must be ventilated in accordance with the *Building Code of Australia* and *AS1668.1 and 2 - 2012. The Use of Ventilation and Air-Conditioning in Buildings - Mechanical Ventilation in Buildings*.
- (b) Details of any mechanical ventilation and/or air conditioning system complying with *AS1668.1 and 2 – 2012 The Use of Ventilation and Air-Conditioning in Buildings - Mechanical Ventilation in Buildings*, the *Building Code of Australia* and relevant Australian Standards must be prepared by a suitably qualified person and certified in accordance with

Clause A2.2 (a) (iii) of the *Building Code of Australia*, to the satisfaction of the Principal Certifier prior to the issue of a Construction Certificate.

- (c) Prior to issue of an Occupation Certificate and following the completion, installation, and testing of all the mechanical ventilation systems, a Mechanical Ventilation Certificate of Completion and Performance in accordance with Clause A2.2 (a) (iii) of the *Building Code of Australia*, must be submitted to the Principal Certifier.

(89) MICROBIAL CONTROL IN WATER SYSTEMS

The installation, operation and maintenance of water-cooling or warm water systems installed on the premises must comply with AS/NZS 3666:3:2011 - Air-handling and water systems of buildings-Microbial Control Part 3: Performance based maintenance of cooling water systems.

Note: The occupier of premises at which a water-cooling system is installed, must notify the council in writing on the prescribed form, of the installation of all water-cooling tower systems within the premises - Public Health Act 2010.

Notification forms are available on Council's website www.cityofsydney.nsw.gov.au

(90) ALIGNMENT LEVELS – MAJOR DEVELOPMENT

- (a) Proposed building floor levels, basement levels, basement car park entry levels and ground levels shown on the approved Development Application plans are indicative only and have not been approved by this consent.
- (b) Prior to a Construction Certificate being issued for any excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work, alignment levels for the building and site frontages must be submitted to and approved by Council. The submission must be prepared by a Registered Surveyor and designed by a suitably qualified engineer, must be in accordance with the City of Sydney's *Public Domain Manual* and must be submitted with a completed and Levels and Gradients Approval Application form (available on the City's website).
- (c) These alignment levels, as approved by Council, are to be incorporated into the plans submitted with the application for a Construction Certificate for any civil, drainage and public domain work as applicable under this consent. If the proposed detailed design of the public domain requires changes to any previously approved Alignment Levels, then an amended Alignment Levels submission must be submitted to and approved by Council to reflect these changes prior to a Construction Certificate being issued for public domain work.

(91) PHOTOGRAPHIC RECORD / DILAPIDATION REPORT - PUBLIC DOMAIN

Prior to an approval for demolition being granted or a Construction Certificate being issued, whichever is earlier, a photographic recording of the public domain site frontages is to be prepared and submitted to Council's satisfaction.

The recording must include clear images of the building facade adjoining the footpath, the footpath, nature strip, kerb and gutter, driveway crossovers and laybacks, kerb ramps, road carriageway, street trees and plantings, parking restriction and traffic signs, and all other existing infrastructure along the street.

The form of the recording is to be as follows:-

- (a) A PDF format report containing all images at a scale that clearly demonstrates the existing site conditions;
- (b) Each image is to be labelled to identify the elements depicted, the direction that the image is viewed towards, and include the name of the relevant street frontage;
- (c) Each image is to be numbered and cross referenced to a site location plan;
- (d) A summary report, prepared by a suitable qualified professional, must be submitted in conjunction with the images detailing the project description, identifying any apparent existing defects, detailing the date and authorship of the photographic record, the method of documentation and limitations of the photographic record;
- (e) Include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

Any damage to the public way including trees, footpaths, kerbs, gutters, road carriageway and the like must immediately be made safe and functional by the applicant. Damage must be fully rectified by the applicant in accordance with the City's standards prior to a Certificate of Completion being issued for Public Domain Works or before an Occupation Certificate is issued for the development, whichever is earlier.

(92) PRESERVATION OF SURVEY MARKS

All works in City streets must ensure the preservation of existing permanent survey marks (a brass bolt, or a lead plug holding a brass tack, covered by a cast iron box). At least forty-eight hours prior to the commencement of any works in the public way within 1 metre of a permanent survey mark contact must be made with the City's Project Manager Survey / Design Services to arrange for the recovery of the mark.

Prior to the issue of a Construction Certificate, a survey plan, clearly showing the location of all permanent survey marks fronting the site and within 5 metres on each side of the frontages must be submitted to Council.

At least forty-eight hours prior to the commencement of any works in the public way within 1 metre of a permanent survey mark contact must be made with the City's Senior Surveyor to arrange for the recovery of the mark.

A fee must be paid to the Council for the replacement of any permanent survey mark removed or damaged in accordance with the City's Schedule of Fees and Charges (Reinstatement of Survey Box).

(93) PROTECTION OF SURVEY INFRASTRUCTURE

Prior to the commencement of any work on site, a statement prepared by a Surveyor registered under the *Surveying Act 2002* must be submitted to Council verifying that a survey has been carried out in accordance with the Surveyor General's Direction No. 11 – Reservation of Survey Infrastructure. Any Permanent Marks proposed to be or have been destroyed must be replaced, and a "Plan of Survey Information" must be lodged at the Land and Property Management Authority.

Reason: To ensure that the survey control infrastructure and cadastral framework are preserved for the public benefit and in accordance with the *Surveying Act 2002*.

(94) PUBLIC DOMAIN PLAN

- (a) A detailed Public Domain Plan must be prepared by a suitably qualified architect, urban designer, landscape architect or engineer and must be lodged with Council's Public Domain Section and be approved by Council prior to a Construction Certificate being issued for public domain work or above ground building work, whichever is later.
- (b) The Public Domain Plan must document all works required to ensure that the public domain complies with the City of Sydney's *Public Domain Manual*, *Sydney Streets Code* and *Sydney Streets Technical Specification*, including requirements for road pavement, traffic measures, footway pavement, kerb and gutter, drainage, vehicle crossovers, pedestrian ramps, lighting, street trees and landscaping, signage and other public domain elements. If an Alignment Levels condition applies to the development, the Public Domain Plan submission must incorporate the approved Alignment Levels. If the proposed detailed design of the public domain requires changes to any previously approved Alignment Levels, then an amended Alignment Levels submission must be submitted to and approved by Council to reflect these changes prior to a Construction Certificate being issued for public domain work.
- (c) The works to the public domain are to be completed in accordance with the approved Public Domain Plan and Alignment Levels plans and the *Public Domain Manual* before any Occupation Certificate is issued in respect of the development or before the use commences, whichever is earlier.

(95) PUBLIC DOMAIN WORKS BOND

Public Domain Works Deposit will be required as security for the public domain works and for repairing damage that may be caused to the public domain in the vicinity of the site, in accordance with the City of Sydney's adopted fees and charges and the Public Domain Manual. The Public Domain Works Deposit must be submitted as an unconditional bank guarantee or insurance

bond as per the Council's Performance Bond Policy in favour of Council as security for completion of the obligations under this consent (Guarantee).

Council's Public Domain section must be contacted to determine the guarantee amount prior to lodgement of the guarantee. The guarantee must be lodged with Council prior to approval being issued for the public domain plan.

The Guarantee will be retained in full until all Public Domain works, including rectification of damage to the public domain, are completed to City of Sydney standards and approval and the required certifications, warranties and works-as-executed documentation are submitted and approved by Council in writing. On satisfying the above requirements, 90% of the security will be released. The remaining 10% will be retained for the duration of the specified Defects Liability Period.

(96) PUBLIC DOMAIN WORKS - HOLD POINTS AND HANDOVER

- (a) Prior to a Construction Certificate being issued for public domain work, including civil, drainage and subsurface works, , a set of hold points for approved public domain, civil and drainage work is to be determined with and approved by the City's Public Domain section in accordance with the City of Sydney's *Public Domain Manual* and *Sydney Streets Technical Specification*.
- (b) Prior to a Certificate of Completion being issued for public domain works and before the issue of any Occupation Certificate for the development or before the use commences, whichever is earlier, electronic works-as-executed (as-built) plans and documentation, certified by a suitably qualified, independent professional must be submitted to and accepted by Council for all public domain works. Completion and handover of the constructed public domain works must be undertaken in accordance with the City of Sydney's *Public Domain Manual* and *Sydney Streets Technical Specification*, including requirements for as-built documentation, certification, warranties and the defects liability period.

(97) STORMWATER AND DRAINAGE - MAJOR DEVELOPMENT

- (c) Prior to an approval or Construction Certificate being issued for excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work a detailed drainage engineering design, calculations and design for the stormwater overland flow path for the development must be:
 - (i) prepared by a suitably qualified hydraulic or civil engineer to show the proposed method of collection and disposal of stormwater; and
 - (ii) prepared in accordance with the City of Sydney's *Stormwater Drainage Manual*, technical specifications, standards and policies, as amended from time to time; and
 - (iii) submitted to and be approved by the City of Sydney and a copy of the City's letter of approval must be provided to the Principal Certifying Authority.

- (d) For approval of a connection into the City of Sydney's drainage system an "Application for Approval of Stormwater Drainage Connections" must be submitted to the City, together with an application fee in accordance with the City of Sydney's adopted Schedule of Fees and Charges.
 - (i) The application must be approved by the City of Sydney prior to an approval or Construction Certificate being issued for excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work.
 - (ii) All proposed connections to the City's underground drainage system require the owner to enter into a Deed of Agreement with the City of Sydney and obtain registration on Title of a Positive Covenant prior to an Occupation Certificate being issued, including an Interim Occupation Certificate.

On-site Detention

- (c) The requirements of Sydney Water with regard to the on-site detention of stormwater must be ascertained and complied with.
 - (i) Evidence of the approval by Sydney Water of the detailed design of the on-site detention must be submitted to and be accepted by the City of Sydney and a copy of the City's letter of acceptance must be provided to the Principal Certifying Authority prior to a Construction Certificate being issued, excluding for any approved preparatory, demolition or excavation works.
 - (ii) Prior to the issue of an Occupation Certificate, including an Interim Occupation Certificate, a Positive Covenant must be registered on the property title for all drainage systems involving On-Site Detention (OSD) to ensure maintenance of the approved OSD system regardless of the method of connection.

Stormwater Quality Assessment

- (d) Prior to a Construction Certificate being issued for any excavation, civil construction, drainage or building work (whichever is earlier), but excluding approved preparatory or demolition work, a stormwater quality assessment must be undertaken and must be approved by City of Sydney and a copy of the City's letter of approval must be provided to the Principal Certifying Authority.

A stormwater quality assessment must be undertaken by a suitably qualified drainage engineer to demonstrate how the development will be designed to ensure that the flow of post-development pollutants from the site due to stormwater will be reduced. The water quality assessment must be submitted to and be approved by the City of Sydney and a copy of the City's letter of approval must be provided to the Principal Certifying Authority prior to a Construction Certificate being issued for any excavation, civil construction, drainage or building work (whichever is earlier), excluding approved preparatory or demolition work.

Prior to the issue of an Occupation Certificate, maintenance schedules of the proposed water sensitive urban design and drainage measures

must be submitted to and be approved by the Principal Certifying Authority and a copy provided to the City of Sydney.

Completion / Works-as-Executed Documentation

- (e) Prior to a Certificate of Completion being issued by the City of Sydney for stormwater drainage works:
 - (i) All works for the disposal of stormwater and drainage are to be implemented in accordance with the approved plans, City of Sydney technical specifications. Standards and policies, approval letters and the requirements of this consent.
 - (ii) a Works-As-Executed survey, prepared, signed and dated by a Registered Surveyor, must be submitted to and be accepted by the City of Sydney. The plan must be overlaid on a copy of the approved stormwater drainage plans issued with the Construction Certificate, with variations to locations, dimensions, levels and storage volumes clearly marked.
 - (iii) Electronic works-as-executed (as-built) details, certifications, warranties, inspection reports (including Closed Circuit Television reports) and associated documentation for the completed work must be prepared and certified by a suitably qualified hydraulic engineer, in accordance with the requirements of the City of Sydney's technical specifications, the *Public Domain Manual*, the *Stormwater Drainage Manual*, the conditions of this consent and all letters of approval issued by the City of Sydney for works in the public domain, and must be submitted to and be accepted by the City of Sydney.

- (f) Prior to the issue of the first Occupation Certificate, including an Interim Occupation Certificate, or before the use commences (whichever is earlier):
 - (i) A copy of the City's Certificate of Completion for all stormwater and drainage work undertaken in the public domain must be provided to the Principal Certifying Authority;
 - (ii) a Works-As-Executed survey, must be prepared, signed, dated and certified by a Registered Surveyor and must be submitted to and be accepted by the Principal Certifying Authority. The Works-as-Executed plan must be overlaid on a copy of the approved stormwater drainage plans issued with the Construction Certificate, with variations to locations, dimensions, levels and storage volumes clearly marked;
 - (iii) a Hydraulic Compliance Certificate and Calculation Sheet must be prepared by a suitably qualified hydraulic engineer (minimum NER), showing approved versus installed hydraulic calculations, and must be submitted to and be accepted by the Principal Certifying Authority;
 - (iv) evidence of Sydney Water's acceptance of the Works-As-Executed documentation, certification and Hydraulic Compliance

Certificate and Calculation Sheet must be provided to the Principal Certifying Authority;

- (v) The Principal Certifying Authority must submit a copy of the Works-As-Executed plans, certifications, Hydraulic Compliance Certificate and Calculation Sheet to the City of Sydney.

(98) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS

All works to the City's public domain, including rectification of identified defects, are subject to a 6 month defects liability period from the date of final completion. The date of final completion will be nominated by Council on the Certificate of Completion for public domain works.

(99) DRAINAGE AND SERVICE PIT LIDS

Drainage and service pit lids throughout the public domain shall be heelguard and bicycle safe, finish flush with the adjacent pavement to avoid trip hazards and be clear of obstructions for easy opening and cleaning. Pit lids shall be in accordance with the *City of Sydney's Sydney Streets Design Code* and *Sydney Streets Technical Specification*. Details of drainage and service pit lids shall be submitted and approved by Council prior to a Construction Certificate being issued for the relevant stage of work.

(100) PROTECTION OF STONE KERBS

- (a) The existing stone kerbs on the Elizabeth Lane frontage of the site are to be retained and properly protected during excavation and construction works.
- (b) To avoid damage to stone kerbs during excavation and construction works for the development, temporary removal and storage of the stone kerbs may be approved by Council. Removed, serviceable stone kerbs (i.e. those that are in good condition as agreed by Council officers) must be re-installed in accordance with the City of Sydney's standard details and specifications after the construction works have been completed. Note: A temporary concrete kerb will need to be constructed to retain the footpath until the stone kerbs can be reinstalled. The removed stone kerbs are to be reinstalled prior to the issue of an Occupation Certificate. Note: all costs associated with the works are to be at no cost to the Council.
- (c) Damaged kerbs are to be replaced to match existing to Council's satisfaction or as otherwise advised by Council officers.
- (d) Where new crossings or temporary crossings are to be constructed to access the property, the affected kerb stones should be salvaged and reused wherever possible.
- (e) All new driveway laybacks and kerbs are to be constructed with stone kerbs to match existing stones or as specified by City officers. All unused stone kerbs are to be salvaged and returned to the City's store.
- (f) Council approval is required before kerbs are removed.

- (g) Council approval is required prior to the cutting of existing stone kerbs for stormwater kerb outlets.

(101) PUBLIC DOMAIN DAMAGE DEPOSIT

- (a) A Public Domain Damage Deposit calculated on the basis of 70 square metres of asphalt site frontage must be lodged with Council in accordance with the City of Sydney's adopted Schedule of Fees and Charges. The Public Domain Damage Deposit must be submitted as an unconditional bank guarantee or insurance bond as per the Council's Performance Bond Policy in favour of Council as security for repairing any damage to the public domain in the vicinity of the site (Guarantee).
- (b) The Guarantee must be lodged with Council prior to an approval for demolition being granted or a Construction Certificate being issued, whichever is earlier.
- (c) The Guarantee in this condition will be retained in full until the Public Domain Works Deposit Guarantee if required by this consent is lodged with Council. Upon lodgement of the Public Domain Works Deposit Guarantee, the Guarantee in this condition will be released.
- (d) If no public domain works are required the Guarantee in this condition will be retained in full until the final Occupation Certificate has been issued and any rectification works to the footway and Public Domain are completed to Council's satisfaction. The Guarantee will be released in full unless rectification works are required where upon 90% of the total securities will be released, with the remaining 10% to be retained for the duration of a 6 months Defect Liability Period.

(102) PUBLIC DOMAIN LIGHTING

- (a) Prior to a Construction Certificate for public domain works or above ground building works being issued, whichever is later, a detailed Public Domain Lighting Plan for pedestrian and street lighting in the public domain must be prepared by a suitably qualified, practicing lighting engineer or lighting designer and must be submitted to and approved by Council. The Lighting Plan must be prepared in accordance with the City of Sydney's Sydney Lights Design Code, Sydney Streets Code, *Sydney Streets Technical Specification* and *Public Domain Manual* and must include the following:
 - (i) Vertical and horizontal illuminance plots for the public domain lighting design to demonstrate compliance with all relevant Australian Standards and to meet the lighting categories and requirements specified by the City;
 - (ii) The location, type and category of existing and proposed lights, including details of luminaire specifications, required to ensure compliance with City policies and Australian Standards;
 - (iii) Footing locations and structural details;
 - (iv) Location and details of underground electrical reticulation, connections and conduits;

- (v) Certification by a suitably qualified, practicing lighting engineer or lighting designer to certify that the design complies with City policies and all relevant Australian Standards including AS 1158, AS 3000 and AS4282;
 - (vi) Structural certification for footing designs by a suitably qualified, practicing engineer to certify that the design complies with City of Sydney policies and Australian Standards.
- (b) The public domain lighting works are to be completed in accordance with the approved plans and the City of Sydney's *Public Domain Manual* before any Occupation Certificate is issued in respect of the development or before the use commences, whichever is earlier.

(103) SYDNEY WATER CERTIFICATE

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Coordinator. Please refer to the Building Developing and Plumbing section on the web site www.sydneywater.com.au then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following the submission of the application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Coordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

The Section 73 Certificate must be submitted to Council or the Principal Certifier prior to an Occupation Certificate or subdivision/strata certificate being issued.

SCHEDULE 1C

DURING CONSTRUCTION/PRIOR TO OCCUPATION/COMPLETION

(104) WASTE AND RECYCLING COLLECTION CONTRACT

Prior to any Occupation Certificate being issued and/or commencement of the use, whichever is earlier, the building owner must ensure that there is a contract with a licensed contractor for the removal of **all waste**. No garbage is to be placed on the public way, e.g. footpaths, roadways, plazas, reserves, at any time.

(105) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a permit being issued by Council under Section 68 of the Local Government Act 1993 and/or Section 138 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Unit, prior to works proceeding

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

(106) NOTIFICATION OF EXCAVATION WORKS OR USE OF HIGH NOISE EMISSION APPLIANCES/PLANT

The immediately adjoining neighbours must be given a minimum of 48 hours notice that excavation, shoring or underpinning works or use of high noise emission appliances / plant are about to commence.

(107) USE OF HIGH NOISE EMISSION APPLIANCES / PLANT

- (a) The operation of high noise emission appliances, plant and/or machinery such as pile – drivers, rock breakers and hydraulic hammers and those which are not listed in Groups B, C, D, E or F of Schedule 1 of the *City of Sydney Code of Practice for Construction Hours/Noise 1992* and Australian Standard 2436-2010 *Guide to Noise Control on Construction, Maintenance and Demolition Sites* is restricted to the hours of:

9:00am -12:00pm and 1:00 pm– 4:30pm Mondays to Friday

9:00am – 1:00pm on Saturdays

No work is permitted on Sundays or Public Holidays

- (b) All reasonable and feasible steps must be undertaken to ensure that the work, including demolition, excavation and building complies with the *City of Sydney Code of Practice for Construction Hours/Noise 1992* and Australian Standard 2436- 2010 *Guide to Noise Control on Construction, Maintenance and Demolition Sites*.

(108) COVERING OF LOADS

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

(109) HAZARDOUS AND INDUSTRIAL WASTE

Hazardous and/or industrial waste arising from the demolition/operational activities must be removed and/or transported in accordance with the requirements of the NSW Work Cover Authority pursuant to the provisions of the following:

- (a) *Protection of the Environment Operations Act 1997*
- (b) *Protection of the Environment Operations (Waste) Regulation 2005*
- (c) *Waste Avoidance and Resource Recovery Act 2001*
- (d) *Work Health and Safety Act 2011*
- (e) *Work Health and Safety Regulation 2011.*

(110) VEHICLE CLEANSING

Prior to the commencement of work, suitable measures are to be implemented to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site. It is an offence to allow, permit or cause materials to pollute or be placed in a position from which they may pollute waters.

(111) ARCHAEOLOGICAL DISCOVERY DURING EXCAVATION

- (a) Should any relics be unexpectedly discovered on the site during excavation, all excavation or disturbance to the area is to stop

immediately and the Heritage Council of NSW should be informed in accordance with section 146 of the Heritage Act 1977.

- (b) Should any Aboriginal objects be unexpectedly discovered then all excavation or disturbance of the area is to stop immediately and NSW Government Office of Environment and Heritage is to be informed in accordance with Section 89A of the *National Parks and Wildlife Act 1974*
- (c) Should any archaeological remains or Aboriginal objects be discovered, a copy of recording of the finds and the final archaeological summary report is to be submitted to Council prior to the issue of any Occupational Certificate;
- (d) if the discovery is on Council's land, Council must be informed.

(112) SITE NOTICE OF PROJECTS DETAILS AND APPROVALS

A site notice is to be prominently displayed at the boundary to each frontage of the site for the purposes of informing the public of appropriate project details and relevant approvals. The notice(s) is to satisfy all of the following requirements:

- (a) Minimum dimensions of the notice are to measure 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size;
- (b) The notice is to be durable and weatherproof and is to be displayed throughout the construction period;
- (c) A copy of the first page of the development approval, building approval (including any modifications to those approvals) and any civic works approvals is to be posted alongside the notice in weatherproof casing;
- (d) The approved hours of work, the Principal Certifier including contact address and certification details, the name of the site manager, the responsible managing company, its address and 24 hour contact phone number for any enquiries, including construction/noise complaint, and the estimated date of completion of the project are to be displayed on the site notice;
- (e) The notice(s) is to be mounted at eye level on the perimeter hoardings and is also to state that unauthorised entry to the site is not permitted.
- (f) All notices and signs must be displayed in locations as specified in the City's Guidelines for Hoardings and Scaffolding.

(113) ENCROACHMENTS – NEIGHBOURING PROPERTIES

No portion of the proposed structure shall encroach onto the adjoining properties.

(114) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

(115) SURVEY

All footings, walls and floor slabs adjacent to a boundary must be set out by a registered surveyor. On commencement of brickwork or wall construction a survey and report, prepared by a Registered Surveyor, must be submitted to the Principal Certifier indicating the position of external walls in relation to the boundaries of the allotment. Any encroachments by the subject building over adjoining boundaries or roads must be removed prior to continuation of building construction work.

(116) SURVEY CERTIFICATE AT COMPLETION

A Survey Certificate prepared by a Registered Surveyor must be submitted to the Principal Certifier at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

(117) CONNECTION TO SEWERS OF SYDNEY WATER CORPORATION

Waste water arising from the use must be directed to the sewers of the Sydney Water Corporation (SWC) under a Trade Waste License Agreement. The pre-treatment of wastewater may be a requirement of the Corporation prior to discharge to the sewer. Details of the Corporation's requirements should be obtained prior to the commencement of construction work.

(118) STREET NUMBERING – MAJOR DEVELOPMENT

Prior to any Occupation Certificate being issued, street numbers and the building name must be clearly displayed at either end of the ground level frontage in accordance with the *Policy on Numbering of Premises within the City of Sydney*. If new street numbers or a change to street numbers is required, a separate application must be made to Council.

(119) SYDNEY WATER CERTIFICATE

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Coordinator. Please refer to the Building Developing and Plumbing section on the web site www.sydneywater.com.au then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Coordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

The Section 73 Certificate must be submitted to Council or the Principal Certifier prior to any Occupation Certificate or subdivision/strata certificate being issued.

(120) ACCESS DRIVEWAYS TO BE CONSTRUCTED

Approved driveways are to be constructed for all vehicular access to the construction site in accordance with the requirements of Council's "Driveway Specifications" to the satisfaction of Council.

(121) LOADING AND UNLOADING DURING CONSTRUCTION

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site, where possible.
- (b) If, it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.
- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.
- (d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate approval under Section 68 of the Local Government Act 1993 and Section 138 of the Roads Act 1993 must be obtained.

(122) NO OBSTRUCTION OF PUBLIC WAY

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances. Non-compliance with this requirement will result in the issue of a notice by Council to stop all work on site.

(123) USE OF MOBILE CRANES

The following requirements apply:

- (a) Mobile cranes operating from the road must not be used as a method of demolishing or constructing a building.
- (b) For special operations including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes, permits must be obtained from Council for the use of a mobile crane. The permits must be obtained 48 hours beforehand for partial road closures which, in the opinion of Council will create minimal traffic disruptions and 4 weeks beforehand in the case of full road closures and partial road closures which, in the opinion of Council, will create significant traffic disruptions.
- (c) The use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes

outside of approved hours of construction can occur, subject to a permit being issued by Council under Section 68 of the Local Government Act 1993 and/or Section 138 of the Roads Act 1993.

(124) PHYSICAL MODELS

- (a) Prior to the issue of any Occupation Certificate an accurate 1:500 scale model of the development as constructed must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the City Model in Town Hall House.

Note:

- (i) The models must be constructed in accordance with the Model Specifications available online at <http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements> Council's modellers must be consulted prior to construction of the model.
- (ii) The models are to comply with all of the conditions of the Development Consent.
- (iii) The models must be amended to reflect any further modifications to the approval (under Section 4.55 of the *Environmental Planning and Assessment Act*) that affect the external appearance of the building.

(125) SUBMISSION OF ELECTRONIC CAD MODELS PRIOR TO OCCUPATION CERTIFICATE

- (a) Prior to any Occupation Certificate being issued, an accurate 1:1 electronic CAD model of the completed development must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the electronic Visualisation City Model.
- (b) The data required to be submitted within the surveyed location must include and identify:
 - (i) building design above and below ground in accordance with the development consent;
 - (ii) all underground services and utilities, underground structures and basements, known archaeological structures and artefacts;
 - (iii) a current two points on the site boundary clearly marked to show their Northing and Easting MGA (Map Grid of Australia) coordinates, which must be based on Established Marks registered in the Department of Lands and Property Information's SCIMS Database with a Horizontal Position Equal to or better than Class C.

The data is to be submitted as a DGN or DWG file on a Compact Disc. All modelling is to be referenced to the Map Grid of Australia (MGA) spatially located in the Initial Data Extraction file.

- (c) The electronic model must be constructed in accordance with the City's 3D CAD electronic model specification. The specification is available online at <http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements> Council's Modelling staff should be consulted prior to creation of the model. The data is to comply with all of the conditions of the Development Consent.

(126) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

SCHEDULE 2

PRESCRIBED CONDITIONS

The prescribed conditions in accordance with Division 8A of the *Environmental Planning and Assessment Regulation 2000* apply:

Clause 98 Compliance with *Building Code of Australia* and insurance requirements under the *Home Building Act 1989*

Clause 98A Erection of signs

Clause 98B Notification of *Home Building Act 1989* requirements

Clause 98C Conditions relating to entertainment venues

Clause 98D Conditions relating to maximum capacity signage

Clause 98E Conditions relating to shoring and adequacy of adjoining property

Refer to the NSW State legislation for full text of the clauses under Division 8A of the *Environmental Planning and Assessment Regulation 2000*. This can be accessed at: <http://www.legislation.nsw.gov.au>