

Attachment A

Recommended Conditions of Consent
--

CONDITIONS OF CONSENT

SCHEDULE 1A

APPROVED DEVELOPMENT/DESIGN MODIFICATIONS/COVENANTS AND CONTRIBUTIONS/USE AND OPERATION

Note: Some conditions in Schedule 1A are to be satisfied prior to issue of a Construction Certificate and some are to be satisfied prior to issue of Occupation Certificate, where indicated.

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2020/923 dated 1 October 2020, as amended by the conditions of this consent.
- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the plans will prevail.

(2) DEMOLITION, EXCAVATION AND CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

A site specific noise management plan shall be submitted to the Council for comment and approval prior to issue of any Construction Certificate.

The Plan must be prepared by a suitably qualified person who possesses the qualifications to render them eligible for membership of the Australian Acoustic Society, Institution of Engineers Australia or the Australian Association of Acoustic Consultants.

The plan must include but not be limited to the following:

- (a) Identification of noise sensitive receivers near to the site.
- (b) A prediction as to the level of noise impact likely to affect the nearest noise sensitive receivers from the use and proposed number of high noise intrusive appliances intended to be operated onsite. A statement should also be submitted outlining whether or not predicted noise levels will comply with the noise criteria stated within the *City of Sydney Construction Hours /Noise Code of Practice 1992* for the typical construction hours of 07.00am to 7.00pm. Where resultant site noise levels are likely to be in exceedance of this noise criteria then a suitable proposal must be given as to the duration and frequency of respite periods that will be afforded to the occupiers of neighbouring property.
- (c) A representative background noise measurement ($L_{A90, 15 \text{ minute}}$) should be submitted, assessed in the vicinity of any potentially affected receiver locations and measured in accordance with AS 1055:1.2.1997.
- (d) Confirmation of the level of community consultation that has/is and will be undertaken with Building Managers/ occupiers of the main adjoining noise sensitive properties likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.
- (e) Confirmation of noise monitoring methodology that is to be undertaken during the main stages of work at neighbouring noise sensitive properties in order to keep complaints to a minimum and to ensure that noise from site works complies with the noise criteria contained within City's Construction Noise Code.

- (f) What course of action will be undertaken following receipt of a complaint concerning offensive noise.
 - (g) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupiers of neighbouring noise sensitive property to a minimum.
 - (h) What plant and equipment is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on the occupiers of neighbouring property and other less intrusive technologies available.
- COMPLIANCE WITH DEMOLITION, EXCAVATION & CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN**
- (a) All works conducted on site which form part of this development must be carried out in accordance with the submitted Demolition, Excavation and Construction Management Plan approved under condition 2.
 - (b) Where all such control measures have been implemented and the resultant noise and/ or vibration levels at any sensitive receiver still exceed the council's applicable criteria stated in the Construction Hours/Noise Code 1992 and are giving rise to sustained complaints then the contractor must provide regular, appropriate and sustained periods of respite in consultation with Council's Health and Building unit. Approval to vary the authorised noise and vibration levels must be received in writing by the proponent from Council prior to activities being undertaken that exceed sanctioned emission levels. (Use where respite periods not specified under the approved DEC NMP)

(4) CONSTRUCTION TRAFFIC MANAGEMENT PLAN

- (a) A Construction Traffic Management Plan (CTMP) must be submitted to and approved by Council's Area Planning Manager/Area Planning Coordinator prior to the issue of any Construction Certificate. The CTMP must be prepared in accordance with Council's requirements, located at –

<http://www.cityofsydney.nsw.gov.au/business/business-responsibilities/traffic-management/construction-traffic-management-plans>
- (b) The development must be undertaken in accordance with the CTMP approved under (b) above.

SCHEDULE 1B

PRIOR TO CONSTRUCTION CERTIFICATE/COMMENCEMENT OF WORK/HEALTH AND BUILDING

(5) ASBESTOS REMOVAL WORKS

- (a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence shall be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.
- (c) All work must be carried out in accordance with the *Work Health and Safety Regulation 2017* and the NSW Government and SafeWork NSW document entitled *How to manage and control asbestos in the work place: Code of Practice (Safework NSW)* December 2011 and the *City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines*.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.
- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 -1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.
- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).
- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.
- (i) A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

(6) HAZARDOUS MATERIALS SURVEY REQUIRED

A Hazardous Materials Survey Report must be prepared by a certified Occupational Hygienist (*Australia Institute of Occupational Hygienists*) and submitted to the satisfaction of Council's Area Coordinator Planning Assessments / Area Planning Manager prior to any demolition / refurbishment work commencing at the site. The report must identify and record the type, location and extent of any hazardous materials on the site and make recommendations as to their safe management and/or removal to ensure the site is made safe for demolition, construction and future use/occupation.

(7) COMPLIANCE WITH HAZARDOUS MATERIALS SURVEY REPORT

All of the recommendations for management and/or removal of hazardous materials on the site, as outlined in the Hazardous Materials Survey Report as approved must be complied with.

Prior to the issue of any Occupation Certificate, certification must be submitted to the Principal Certifier from a certified Occupational Hygienist (*Australia Institute of Occupational Hygienists*) confirming that all hazardous materials identified have been contained, managed or removed in accordance with the recommendations given in the approved Hazardous Materials Survey Report and that the site is safe for future occupation in accordance with the approved use.

(8) LAND REMEDIATION

- (a) The Remedial Action Plan prepared by JBS&B dated 3 September 2020 reference number 53719/129939 Rev 1 (2020/432840) is to be amended, submitted to and approved by Council's Area Planning Manager prior to commencement of works to require excavation and clean fill to a depth and marker layer of 1.5 metres below finished natural ground level. The Letter of Interim Advice prepared by NSW Environment Protection Authority accredited Site Auditor Rowena Salmon dated 9 September 2020 entitled "Review of Remedial Action Plan, Proposed Green Square School, 3 Joynton Avenue, Zetland, NSW", (2020/432841) is to be updated and submitted with the revised Remediation Action Plan accordingly.
- (b) The site is to be remediated and validated in accordance with the revised Remedial Action Plan and Letter of Interim Advice approved under (a) above.
- (c) All remediation work carried out shall be conducted in accordance with the guidelines in force from time to time under the *Contaminated Land Management Act 1997*.
- (d) Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination must be immediately notified to the Council's Area Planning Manager, the Site Auditor and the Principal Certifier.

- (e) Any variations to the approved Remediation Action Plan shall be approved in writing by the Site Auditor and Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the commencement of such work.

(9) SITE AUDIT STATEMENT

Prior to the issue of an Occupation Certificate, a Section A Site Audit Statement must be obtained from a NSW Environment Protection Authority accredited Site Auditor and submitted to the Council's Area Planning Manager at email address:

hbapplications@cityofsydney.nsw.gov.au

The Site Audit Statement must confirm that the site has been remediated in accordance with the approved Remedial Action Plan and clearly state that site is suitable for the intended Green Square Integrated Communities Facilities and School use.

- (a) In circumstances where the Site Audit Statement is subject to conditions that require ongoing review by the Auditor or Council, these must be reviewed and must be approved by the Council's Health and Building Unit in writing through the Area Planning Manager before the Site Audit Statement is issued.
- (b) In circumstances where the Site Audit Statement conditions (if applicable) are not consistent with the consent, the development must not proceed until the inconsistency has been resolved to the satisfaction of Council (such as via a S4.55 modification of the consent pursuant to the provisions of the *Environmental Planning & Assessment Act 1979*).
- (c) **No Occupation Certificate is to be issued** by the Principal Certifier unless a Site Audit Statement has been submitted to and approved by Council in accordance with this condition.

(10) SITE AUDIT STATEMENT – PASSIVE ENVIRONMENTAL MANAGEMENT PLAN

Where the ongoing land use suitability and release of the Final (Section A) Site Audit Statement is dependent upon the implementation of an Environmental Management Plan (EMP) in relation to any residual contamination remaining onsite, the EMP must be approved by the Site Auditor and Council's Area Planning Manager prior to the issue of the final Site Audit Statement.

The owner of the land is required to comply with the ongoing obligations of any EMP which form part of the final Site Audit Statement for the site.

A covenant shall be registered on the title of the land binding the owners and future owners to be responsible for ongoing maintenance and any future rehabilitation works required in terms of the encapsulated/remaining contaminated materials, including the discharge or prevention of discharge from any contaminants or for any works subsequently required by the NSW Environment Protection Authority

A copy of the revised certificate of land title recording the covenant must be submitted to Council's Area Planning Manager and the Principal Certifier prior to the issue of any Occupation Certificate.

(11) IMPORTED FILL MATERIALS

All fill imported onto the site shall be validated to ensure the imported fill is suitable for the proposed land use from a contamination perspective. Fill imported on to the site shall also be compatible with the existing soil characteristic for site drainage purposes.

The City may require details of appropriate validation of imported fill material to be submitted with any application for future development of the site. Hence all fill imported onto the site should be validated by either one or both of the following methods during remediation works:

- (a) imported fill must be accompanied by documentation from the supplier which certifies that the material is not contaminated based upon analyses of the material for the known past history of the site where the material is obtained; and/or
- (b) sampling and analysis of the fill material shall be conducted in accordance with NSW EPA (1995) Sampling Design Guidelines.

(12) CLASSIFICATION OF WASTE

Prior to the exportation of waste (including fill or soil) from the site, the waste materials must be classified in accordance with the provisions of the *Protection of the Environment Operations Act 1997* and the *NSW DECC Waste Classification Guidelines, Part1: Classifying Waste (July 2009)*. The classification of the material is essential to determine where the waste may be legally taken. The *Protection of the Environment Operations Act 1997* provides for the commission of an offence for both the waste owner and the transporters if the waste is taken to a place that cannot lawfully be used as a waste facility for the particular class of waste. For the transport and disposal of industrial, hazardous or Group A liquid waste advice should be sought from the EPA.

(13) DISCHARGE OF CONTAMINATED GROUNDWATER

Contaminated groundwater shall not be discharged into the City's stormwater drainage system.

Options for the disposal of groundwater include disposal to sewer with prior approval from Sydney Water or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

(14) ENVIRONMENTAL MANAGEMENT PLAN

Prior to the commencement of any demolition and remedial works an Environmental Management Plan (EMP) must be prepared for the site and submitted to Council's Area Planning Manager for written approval prior to the commencement of work. The EMP must consider all potential environmental impacts from the approved works including but not limited to sedimentation control, contamination containment, stockpiles, noise and vibration, odours and dust emissions.

All works must be undertaken onsite in accordance with the approved Environmental Management Plan.

(15) STOCKPILES

- (a) No stockpiles of soil or other materials shall be placed on footpaths or nature strips unless prior approval has been obtained from the City's Construction Regulation Team.
- (b) All stockpiles of soil or other materials shall be placed away from drainage lines, gutters or stormwater pits or inlets.
- (c) All stockpiles of soil or other materials likely to generate dust or odours shall be covered.
- (d) All stockpiles of contaminated soil shall be stored in a secure area and be covered if remaining more than 24 hours

(16) DECOMMISSIONING OF UNDERGROUND PETROLEUM STORAGE TANKS

The removal of underground petroleum storage tanks must be undertaken in accordance with Safework NSW requirements which includes writing to the Chief Inspector of Dangerous Goods and complying with any conditions imposed and all relevant NSW Environmental Protection Authority/Office of the Environment and Heritage Guidelines and Australian Standards including following;

NSW EPA Technical Note: *Decommissioning, Abandonment and Removal of UPSS* (January 2010),

NSW EPA Technical Note: *Investigation of Service Station Sites* (April 2014),

AS 1940 – 2004: Storage and handling of flammable and combustible liquids,

AS 4976 – 2008: The removal and disposal of underground petroleum storage tanks.

A site contamination assessment must be conducted in accordance with the *Guidelines for Consultants Reporting on Contaminated Sites* (NSW Office of the Environment and Heritage 2011) and the *Sampling Design Guidelines* (NSW Environmental Protection Authority September 1995) to determine whether petroleum has contaminated soil and groundwater in the vicinity of the storage system and whether remediation is required to ensure the land remains suitable for the continued approved land use.

Subsequent remediation of the site must be undertaken in accordance with the *Managing Land Contamination – Planning Guidelines, State Environmental Planning Policy 55 – Remediation of land* (Department of Urban Affairs and Planning 1998) including notification to Council's Area Planning Manager at the start and completion of land remediation.

The removal or in-situ decommissioning of the underground petroleum storage system and any subsequent contamination assessment, preparation of a remediation strategy and final decommissioning reporting must be carried out by a duly qualified person, who has competencies and experience in relation to this area of work that are recognised as appropriate by the relevant industry and the NSW Environmental Protection Authority.

(17) UNDERGROUND PETROLEUM STORAGE SYSTEM – DECOMMISSIONING REPORT

The underground petroleum storage system must be investigated for contamination and a site investigation report obtained from a suitably qualified Environmental Consultant in accordance with NSW Environmental Protection Authority guidelines, must be submitted to Council's Area Planning Manager within 60 days of completion of either validation that no site remediation is necessary or completion of any necessary remediation works. The report must provide confirmation that the site is suitable for continued approved land use or prior approved remediation criteria.

The report must be undertaken in accordance with clause 13 and 15 of the *Protection of the Environment (Underground Petroleum Storage Systems) Regulation 2014* and the NSW Department of the Environment, Climate Change and Water *Underground Petroleum Storage System Technical Note: Site Validation Reporting – January 2010* and *Guidelines for Consultants Reporting on Contaminated Sites (NSW Office of the Environment and Heritage 2011)*.

The decommissioning report must contain:

- (a) a description of the scale and nature of any contamination originally present;
- (b) a description of the remedial methods used, including objectives, where applicable;
- (c) a statement about the site's ongoing or future use;
- (d) a description of the extent of any remaining contamination and how this was assessed; and
- (e) a site plan delineating the area being validated and any contamination remaining after site works.

(18) PHOTOGRAPHIC RECORD / DILAPIDATION REPORT - PUBLIC DOMAIN

Prior to an approval for demolition being granted or a Construction Certificate being issued, whichever is earlier, a photographic recording of the public domain site frontages is to be prepared and submitted to Council's satisfaction.

The recording must include clear images of the building facade adjoining the footpath, the footpath, nature strip, kerb and gutter, driveway crossovers and laybacks, kerb ramps, road carriageway, street trees and plantings, parking restriction and traffic signs, and all other existing infrastructure along the street.

The form of the recording is to be as follows:-

- (a) A PDF format report containing all images at a scale that clearly demonstrates the existing site conditions;
- (b) Each image is to be labelled to identify the elements depicted, the direction that the image is viewed towards, and include the name of the relevant street frontage;
- (c) Each image is to be numbered and cross referenced to a site location plan;
- (d) A summary report, prepared by a suitable qualified professional, must be submitted in conjunction with the images detailing the project description, identifying any apparent existing defects, detailing the date and authorship of

the photographic record, the method of documentation and limitations of the photographic record;

- (e) Include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

(19) PUBLIC DOMAIN DAMAGE BOND

- (a) A Public Domain Damage Bond calculated on the basis of 560 square metres of paved site frontage must be lodged with Council in accordance with the City of Sydney's adopted Schedule of Fees and Charges. The Public Domain Damage Bond must be submitted as an unconditional bank guarantee or insurance bond as per the Council's Performance Bond Policy in favour of Council as security for repairing any damage to the public domain in the vicinity of the site (Guarantee).
- (b) The Guarantee must be lodged with Council prior to an approval for demolition being granted or any Construction Certificate being issued, whichever is earlier.
- (c) The Guarantee in this condition will be retained in full until the final Site Audit Report has been issued, or the public domain works bond has been lodged and any rectification works to the footway and Public Domain are completed to Council's satisfaction. The Guarantee will be released in full unless rectification works are required where upon 90% of the total securities will be released, with the remaining 10% to be retained for the duration of a 6 months Defect Liability Period.

SCHEDULE 1C

DURING CONSTRUCTION/PRIOR TO OCCUPATION/COMPLETION

(20) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

(21) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a permit being issued by Council under Section 68 of the Local Government Act 1993 and/or Section 138 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Team, prior to works proceeding

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

(22) SITE NOTICE OF PROJECTS DETAILS AND APPROVALS

A site notice is to be prominently displayed at the boundary to each frontage of the site for the purposes of informing the public of appropriate project details and relevant approvals. The notice(s) is to satisfy all of the following requirements:

- (a) Minimum dimensions of the notice are to measure 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.
- (b) The notice is to be durable and weatherproof and is to be displayed throughout the construction period.

- (c) A copy of the first page of the development approval, building approval (including any modifications to those approvals) and any civic works approvals is to be posted alongside the notice in weatherproof casing.
- (d) The approved hours of work, the Principal Certifier including contact address and certification details, the name of the site manager, the responsible managing company, its address and 24 hour contact phone number for any enquiries, including construction/noise complaint, and the estimated date of completion of the project are to be displayed on the site notice.
- (e) The notice(s) is to be mounted at eye level on the perimeter hoardings and is also to state that unauthorised entry to the site is not permitted.
- (f) All notices and signs must be displayed in locations as specified in the City's Guidelines for Hoardings and Scaffolding.

(23) USE OF HIGH NOISE EMISSION APPLIANCES / PLANT

- (a) The operation of high noise emission appliances, plant and/or machinery such as pile – drivers, rock breakers and hydraulic hammers and those which are not listed in Groups B, C, D, E or F of Schedule 1 of the *City of Sydney Code of Practice for Construction Hours/Noise 1992* and Australian Standard 2436-2010 *Guide to Noise Control on Construction, Maintenance and Demolition Sites* is restricted to the hours of 9.30am to 1pm and 2pm to 4.30pm Mondays to Fridays and 9.30am to 1.30pm Saturdays.
- (b) All reasonable and feasible steps must be undertaken to ensure that the work, including demolition, excavation and building complies with the *City of Sydney Code of Practice for Construction Hours/Noise 1992* and Australian Standard 2436- 2010 *Guide to Noise Control on Construction, Maintenance and Demolition Sites*.

(24) LIGHTING OF SITE OUTSIDE OF STANDARD CONSTRUCTION HOURS

Lighting of the site while any work is undertaken outside of Council's standard hours of construction must ensure that at no time must the intensity, hours of illumination or location of the lighting cause objectionable glare or injury to the amenity of the neighbourhood or Obtrusive Light in accordance with the definition in Australian Standard AS4282-1997 *Control of the obtrusive effects of outdoor lighting*. If in the opinion of Council, injury is likely to be caused, the intensity, hours of illumination and location of the lighting must be varied so that it does not cause injury to nearby residents.

(25) NOTIFICATION OF EXCAVATION WORKS OR USE OF HIGH NOISE EMISSION APPLIANCES/PLANT

The immediately adjoining neighbours must be given a minimum of 48 hours notice that excavation, shoring or underpinning works or use of high noise emission appliances / plant are about to commence.

(26) ARCHAEOLOGICAL DISCOVERY DURING EXCAVATION

- (a) Should any relics be unexpectedly discovered on the site during excavation, all excavation or disturbance to the area is to stop immediately and the Heritage Council of NSW should be informed in accordance with section 146 of the Heritage Act 1977.

- (b) Should any Aboriginal objects be unexpectedly discovered then all excavation or disturbance of the area is to stop immediately and NSW Government Office of Environment and Heritage is to be informed in accordance with Section 89A of the *National Parks and Wildlife Act 1974*.
- (c) Should any archaeological remains or Aboriginal objects be discovered, a copy of recording of the finds and the final archaeological summary report is to be submitted to Council prior to the issue of any Occupational Certificate.
- (d) if the discovery is on Council's land, Council must be informed.

(27) ARCHAEOLOGICAL ASSESSMENT

An archaeological assessment undertaken by a suitably qualified archaeologist must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the issue of a Construction Certificate. The report must assess whether the proposed works have the potential to disturb any archaeological remains and the need for any archaeological investigation prior to commencement of any works on site. The report should also recommend measures and documentation to be undertaken during the process of demolition and excavation work.

Recommendations by the archaeological assessment are to be implemented during the process of demolition and excavation work.

Should the assessment report suggest the site may contain relics and the proposed work may disturb them, council may request the applicant to amend the proposal so that the relics are properly protected or interpreted.

(28) ARCHAEOLOGICAL INVESTIGATION

- (a) The applicant must apply to the Heritage Division of the Department of Environment and Heritage for an excavation permit under Section 140 of the *Heritage Act 1977*.
- (b) Should any potential archaeological deposit likely to contain Aboriginal objects be identified by any person during the planning or historical assessment stage, application must be made by a suitably qualified archaeologist to the NSW Government Office of Environment and Heritage for an excavation permit for Aboriginal objects.
- (c) The applicant must comply with the conditions and requirements of any excavation permit required, and are to ensure that allowance is made for compliance with these conditions and requirements into the development program.
- (d) General bulk excavation of the site is not to commence prior to compliance with the conditions and requirements of any excavation permit required.
- (e) Should any relics be unexpectedly discovered in any areas of the site not subject to an excavation permit, then all excavation or disturbance to the area is to stop immediately and the Heritage Council of NSW should be informed in accordance with section 146 of the *Heritage Act 1977*.
- (f) Should any Aboriginal objects be unexpectedly discovered then all excavation or disturbance of the area is to stop immediately and NSW Government Office

of Environment and Heritage is to be informed in accordance with Section 89A of the *National Parks and Wildlife Act 1974*;

- (g) Should any archaeological remains or Aboriginal objects be discovered, a copy of recording of the finds and the final archaeological summary report is to be submitted to Council's Area Coordinator Planning Assessments / Area Planning Manager prior to issue of any Occupation Certificate.