


Attachment A9



Site Survey – 2 Chifley Square, Sydney



2 Chifley Square

Drawing:
 Drawing no:
 Issue:
 Scale @ A3:
 Date:

Site Survey Plan
PP-00-04
1 : 600
13/07/21



Architectus Sydney
 Level 18 MLC Centre
 19 Martin Place
 Sydney NSW 2000
 sydney@architectus.com.au



Date: 26th November 2018

Our Ref: 69554

Instructed By: Charter Hall

Re: 2 Chifley Square, Sydney, NSW

Further to your instructions and for your private use we have surveyed, for Identification purposes only, the land comprised in Computer Folio Certificate Title Reference:

- 10/777545 being Lot 10 in Deposited Plan 777545.

The Folio Certificate Search as obtained from NSW Land Registry Services is certified to 22/11/2018.

Lease Folios created as noted on the Computer Folio Certificate. Refer to Lease Premises Index Search for LF355.

Location of Subject Land

Locality: Sydney

Local Government Area: Sydney

Parish: St James

County: Cumberland

The subject land is known as No. 2 Chifley Square, and has frontages to Bent Street, Phillip Street Chifley Square and Hunter Street.

Improvements on the Subject Land

Erected on the subject land is a multi-level concrete, metal, tiled & glass office building complex with car parking under. The surveyed building location relative to the subject property boundaries is as shown on the accompanying plan.

The area of the subject land is 6438m² (vide DP 777545).

Fencing

The land is substantially walled as shown on the accompanying plan.

Encroachments

In our opinion:

- A metal awning (AWL) attached to the building erected on the subject property overhangs Bent Street to the north-east by up to about 0.3 metres as shown on the accompanying plan.
- A metal awning (AWL) attached to the building erected on the subject land overhangs Hunter Street to the south by up to about 1.4 metres as shown.
- A metal awning (AWU) overhangs Hunter Street to the south by up to about 0.04 metres as shown.

- Metal awnings (AWL & AWU) overhang Chifley Square to the south-west by up to about 1.6 metres as shown.
- Metal architectural features (AF) overhang Hunter Street to the south by up to about 0.13 metres as shown.
- Metal architectural features (AF), overhang Phillip Street to the west by up to about 0.16 metres as shown.
- Concrete coping (CP) overhangs Hunter Street to the south by up to about 0.07 metres as shown.
- Concrete coping (CP) overhangs Phillip Street to the west by up to about 0.1 metres as shown.
- Concrete coping (CP) overhangs Bent Street to the north-east by up to about 0.09 metres as shown.
- An adjoining cladded wall (AJW) erected on Lot 2 DP217711 stands upon the subject property to the east by 0.02 metres as shown.
- An adjoining brick pier (BKP) erected on Lot 2 DP217711 stands upon the subject property to the east by up to 0.26 metres as shown.
- A masonry cladded column (C) erected on the corner of Phillip Street & Chifley Square stands upon the road reserve by up to 1.65 metres as shown.
- A masonry cladded column (C) erected on the corner of Hunter Street & Chifley Square stands upon the road reserve by up to 2.2 metres as shown.
- A metal awning (AWL) attached to the building erected on the corner of Phillip Street & Chifley Square overhangs the road reserve by up to 2.67 metres as shown.
- A metal awning (AWL) attached to the building erected on the corner of Hunter Street & Chifley Square overhangs the road reserve by up to 3.21 metres as shown.

Apart from the abovementioned & where accessible, there appear to be no further visible encroachments by or upon the subject property.

Registered Encumbrances, Easements and Interests

Lot 10 DP 777545

1. Reservations and Conditions in the Crown Grant(s).
2. Easement for support benefitting the land (vide Dealing No. J504777).
3. Lease (vide Dealing No. X641679) which includes, Lease to Energy Australia of Cable Jointing and Substation Premises No.'s 6865, 6866 & 6867 together with Right of Way & Easement for Electricity Purposes burdening the land (vide Dealing No. 5740055).

Note:

1. The certificate of title for this folio of the register does not include security features included on computerised certificates of title issued from 4th January, 2004. It is recommended that stringent processes are adopted in verifying the identity of the person(s) claiming a right to deal with the land comprised in this folio.
2. Refer all dealings to SD2.

Boundary Reinstatement

The boundaries have been compiled from title dimensions and survey measurements to marks & monuments recorded on existing registered survey plans of the subject and adjoining lands.

This report and accompanying plan have been prepared for Identification purposes only and as such is not a new survey of the title dimensions and should not be used for any other purpose other than to identify the subject land.

This survey & report is not registered at Land Registry Services NSW. Subsequent registered or other surveys in the area may affect boundary definition as shown in this report. Any differences so caused to the boundary definition in this report are beyond the control of the signing Registered Surveyor who can accept no responsibility for such differences.

This report is to be read in conjunction with the accompanying Plan of Identification Survey.



.....
David McCulloch (Registered Surveyor)


Attachments

- *Plan of Identification Survey*

LEASE TO ENERGY AUSTRALIA (VIDE DEALING No. 5740055)
 (S) SUBSTATION PREMISES 6865 & 6866 (PL1 & LGL)
 (U) CABLE JOINTING PREMISES (LGL & UGL)
 (Y) EASEMENT FOR ELECTRICITY PURPOSES (PL1)
 (V) RIGHT OF WAY (LOWER GROUND TO LEVEL 43)
 (W) RIGHT OF WAY
 (X) RIGHT OF WAY ELEVATOR (LEVEL 1 TO LEVEL 42)

NOTE : REFER TO DEALING No. 5740055
 FOR UPPER LEVEL LEASE DETAILS &
 SUBSTATION PREMISES 6867.

PL1 - PARKING LEVEL 1 (DL 5740055)
 LGL - LOWER GROUND LEVEL (DL 5740055)
 UGL - UPPER GROUND LEVEL (DL 5740055)



394

HUNTER STREET
 HUNTER STREET
 HUNTER STREET

PHILLIP STREET

STREET

BENT STREET

CHIFLEY SQUARE

10 DP 777545

"CHIFLEY" No. 2
 MULTI-LEVEL CONCRETE,
 METAL, TILED & GLASS OFFICE BUILDING COMPLEX
 WITH CAR PARKING UNDER

"MACQUARIE HOUSE"
 No. 165-169 MACQUARIE STREET
 MULTI STOREY CONCRETE
 COMMERCIAL BUILDING

SCHEDULE OF ABBREVIATIONS

- A - ARC
- AF - ARCHITECTURAL FEATURE (METAL STRIP) - APPROXIMATE OVERHANG
- AJW - ADJOINING WALL
- AWL - AWNING LOWER - OVERHANG
- AWU - AWNING UPPER - OVERHANG
- BKP - ADJOINING BRICK PIER
- BLG - BUILDING LINE GROUND
- C - COLUMN (GROUND)
- CP - CONCRETE COPING - OVERHANG UPPER FLOORS
- DL - DEALING No.
- GS - GLASS STRUCTURE
- KB - KERB
- NF - NOT FENCED
- R - RADIUS
- RW - ADJOINING RENDERED WALL
- STR - STAIRS
- ISB - INSIDE SUBJECT PROPERTY BOUNDARY
- OSB - OUTSIDE SUBJECT PROPERTY BOUNDARY

This is the plan referred to in my report dated 26-11-2018

David McCulloch
 Registered surveyor - Surveyor ID No: 125

Plan Prepared for:
CHARTER HALL
 Disclaimer: This plan has been prepared for Identification purposes only and as such is not a new survey of the title dimensions. This plan should not be used for any other purpose other than to identify the parcel of land.

PLAN OF IDENTIFICATION SURVEY
 LOT 10 DP 777545
 2 CHIFLEY SQUARE, SYDNEY
 LGA : SYDNEY

Date: 26-11-2018
 Ref: 69554
 Rev: -
 Scale: n/a

Australia | New Zealand
REALSERVE
 Start confident.

Building Measurement Specialist
 Consulting Land Surveyors
 3D Laser Scanning
 ph. 02 9629 9377
 www.realserve.com.au