

Attachment A

Recommended Conditions of Consent
--

CONDITIONS OF CONSENT

SCHEDULE 1A

APPROVED DEVELOPMENT/DESIGN MODIFICATIONS/COVENANTS AND CONTRIBUTIONS/USE AND OPERATION

Note: Some conditions in Schedule 1A are to be satisfied prior to issue of a Construction Certificate and some are to be satisfied prior to issue of Occupation Certificate, where indicated.

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2021/759 dated 7 July 2021 and the following drawings prepared by SJB:

Drawing Number	Drawing Name	Date
DA-1001 Rev 7	Ground floor plan	7.10.2021
DA-1002 Rev 7	Level 1 floor plan	7.10.2021
DA-1003 Rev 7	Level 2 floor plan	7.10.2021
DA-1004 Rev 7	Level 3 floor plan	7.10.2021
DA-1005 Rev 7	Roof plan	7.10.2021
DA-1401 Rev 7	Elevations – north south	7.10.2021
DA-1402 Rev 7	Elevations – east west	7.10.2021
DA-1501 Rev 7	Section A	7.10.2021
DA-1502 Rev 7	Section B	7.10.2021

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the drawings will prevail.

(2) DESIGN MODIFICATIONS

The design of the building must be modified as follows:

- (a) The Level 3 planter bed is to be raised in height to the balustrade height across the length of the north elevation terrace.

The modifications are to be submitted to and approved by Council's Area Planning Manager prior to the issue of a Construction Certificate.

(3) MATERIALS AND SAMPLES SCHEDULE – MINOR DEVELOPMENT

A detailed materials, colours and finishes schedule (including visible rainwater goods and services) keyed to each building elevation must be submitted to and approved by Council's Area Planning Manager prior to a Construction Certificate being issued. The materials and samples schedule/board must not include generic material or colour descriptions, or use terminology such as 'or similar'. Detailed plans of the privacy louvres to the northern elevation are to be included.

(4) NO AIR CONDITIONING UNITS TO FACADE OR BALCONIES OF BUILDING

Approval is not granted for the installation of individual air conditioning units to the facade or balconies of the building.

(5) NOISE – MECHANICAL PLANT

- (a) Noise from any mechanical plant must not exceed a project amenity/intrusiveness noise level or maximum noise level in accordance with relevant requirements of the NSW EPA [Noise Policy for Industry 2017 \(NPfI\)](#) unless agreed to by the City's Area Planning Manager. Further:
 - (i) Background noise monitoring must be carried out in accordance with the long-term methodology in [Fact Sheet B](#) of the NPfI unless otherwise agreed by the City's Area Planning Manager.
 - (ii) Commercial plant is limited to heating, ventilation, air conditioning, refrigeration and energy generation equipment.
- (b) An $L_{Aeq,15 \text{ minute}}$ (noise level) emitted from the development must not exceed the $L_{A90, 15 \text{ minute}}$ (background noise level) by more than 3dB when assessed inside any habitable room of any affected residence or noise sensitive commercial premises at any time. Further:
 - (i) The noise level and the background noise level must both be measured with all external doors and windows of the affected residence closed.
 - (ii) Background noise measurements must not include noise from the development but may include noise from necessary ventilation at the affected premise.
- (c) Corrections in [Fact Sheet C](#) of the NPfI are applicable to relevant noise from the development measured in accordance with this condition, however duration corrections are excluded from commercial noise.

SCHEDULE 1B

PRIOR TO CONSTRUCTION CERTIFICATE/COMMENCEMENT OF WORK/HEALTH AND BUILDING

(6) BASIX CERTIFICATE – DETAILS TO BE LODGED WITH A CC

A copy of the required completed BASIX certificate accepted as part of this Development Consent with respect to the proposed residential building works, must be lodged with an application for a construction certificate and the items nominated as part of the subject BASIX certificate must be specified on the plans submitted with the construction certificate application. – See Note.

IMPORTANT NOTE:

Any requirement detailed in the accompanying BASIX Certificate, MUST be included as a specific notation or inclusion on any future Construction Certificate plans and specification in accordance with Part 3 of Schedule 1 of the EP&A Regulation, 2000.

(7) STRUCTURAL CERTIFICATION FOR EXISTING BUILDING – ALTERATIONS AND ADDITIONS

A qualified practising registered structural engineer must provide structural certification to Council (where Council is the Accredited Certifier) verifying that the existing structure can adequately support the proposed new loads and the structural design complies with the Structural Provisions of Part B1 (Vol 1) and Part 2.1 (Vol 2) of the *Building Code of Australia* prior to a Construction Certificate being issued. The proposed additional loads and/or alterations must not cause a decrease in the existing structural performance of the building including its performance under earthquake actions (AS1170.4).

(8) EROSION AND SEDIMENT CONTROL - LESS THAN 250SQM

Where less than 250 square metres are being disturbed, no formal plan is required however, the site is to be provided with sediment control measures and these must be implemented so that sediment, including soil, excavated material, building material or other materials cannot fall, descend, percolate, be pumped, drained, washed or allowed to flow to the street, stormwater system or waterways.

(9) DILAPIDATION REPORT – MINOR

Subject to the receipt of permission of the affected landowner, dilapidation report/s of adjoining buildings are to be prepared by an appropriately qualified practising structural engineer and submitted for the approval of the Accredited Certifier:

- (a) prior to the commencement of demolition/excavation works; and
- (b) on completion of construction demolition/excavation works.

(10) FLASHINGS TO BOUNDARY WALLS

A flashing must be provided to prevent water entering between the proposed and existing external boundary walls of the adjoining properties.

Note: Attachments or connections to party walls may require the consent of the adjoining property owner/s.

(11) LANDSCAPING OF THE SITE

- (a) A detailed landscape plan, drawn to scale, by a qualified landscape architect or landscape designer, must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the issue of a Construction Certificate for above ground building works. The plan must include:
 - (i) Location of existing and proposed structures on the site including, but not limited to, existing and proposed trees, paved areas, planted areas on slab, planted areas in natural ground, lighting and other features;
 - (ii) The proposed tree planting must consist of a species that will provide the minimum 15% canopy cover for the site, or include other plantings within additional deep soil to demonstrate the development will provide the minimum 15% canopy required.
 - (iii) Details of earthworks and soil depths including mounding and retaining walls and planter boxes (if applicable). The minimum soil depths for planting on slab must be 1000mm for trees, 450mm for shrubs and 200mm for groundcovers;
 - (iv) Location, numbers, type and supply of plant species, with reference to NATSPEC (if applicable);
 - (v) Details of planting procedure and maintenance;
 - (vi) Details of drainage, waterproofing and watering systems.
- (b) Prior to the issue of a Construction Certificate, a maintenance plan is to be submitted to and approved by the Accredited Certifier. The maintenance plan is to be complied with during occupation of the property.
- (c) All landscaping in the approved plan is to be completed prior to any Occupation Certificate being issued.

(12) CONSTRUCTION PEDESTRIAN TRAFFIC MANAGEMENT PLAN

- (a) A Construction Pedestrian Traffic Management Plan must be submitted to and approved by Council prior to a Construction Certificate being issued.
- (b) The approved plan must be complied with during any demolition and/or construction work.

Construction Traffic and Pedestrian Management Plans are to be prepared in accordance with Standard Requirements for Construction Traffic Management Plan on the City's website <http://www.cityofsydney.nsw.gov.au/business/business-responsibilities/traffic-management/construction-traffic-management-plans>

(13) DEMOLITION, EXCAVATION AND CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

A site specific noise management plan must be submitted to the Council for comment and approval prior to issue of any Construction Certificate.

The Plan must be prepared by a suitably qualified person who possesses the qualifications to render them eligible for membership of the Australian Acoustic Society, Institution of Engineers Australia or the Australian Association of Acoustic Consultants.

The plan must include but not be limited to the following:-

- (a) identification of noise sensitive receivers near to the site.
- (b) A prediction as to the level of noise impact likely to affect the nearest noise sensitive receivers from the use and proposed number of high noise intrusive appliances intended to be operated onsite. A statement should also be submitted outlining whether or not predicted noise levels will comply with the noise criteria stated within the *City of Sydney Construction Hours /Noise Code of Practice 1992* for the typical construction hours of 07.00am to 7.00pm. Where resultant site noise levels are likely to be in exceedance of this noise criteria then a suitable proposal must be given as to the duration and frequency of respite periods that will be afforded to the occupiers of neighbouring property.
- (c) A representative background noise measurement ($L_{A90, 15 \text{ minute}}$) should be submitted, assessed in the vicinity of any potentially affected receiver locations and measured in accordance with AS 1055:1.2.1997.
- (d) Confirmation of the level of community consultation that has/is and will be undertaken with Building Managers/ occupiers of the main adjoining noise sensitive properties likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.
- (e) Confirmation of noise monitoring methodology that is to be undertaken during the main stages of work at neighbouring noise sensitive properties in order to keep complaints to a minimum and to ensure that noise from site works complies with the noise criteria contained within City's Construction Noise Code.
- (f) What course of action will be undertaken following receipt of a complaint concerning offensive noise.
- (g) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupiers of neighbouring noise sensitive property to a minimum.
- (h) What plant and equipment is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on the occupiers of neighbouring property and other less intrusive technologies available.

(14) COMPLIANCE WITH DEMOLITION, EXCAVATION & CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

- (a) All works conducted on site which form part of this development must be carried out in accordance with the submitted Demolition, Excavation and Construction Management Plan prepared approved by Council.
- (b) Where all such control measures have been implemented and the resultant noise and/ or vibration levels at any sensitive receiver still exceed the council's applicable criteria stated in the Construction Hours/Noise Code 1992 and are giving rise to sustained complaints then the contractor must provide regular, appropriate and sustained periods of respite in consultation with Council's Health and Building unit. Approval to vary the authorised noise and vibration levels must be received in writing by the proponent from Council prior to activities being undertaken that exceed sanctioned emission levels. (Use where respite periods not specified under the approved DEC NMP)

Such periods must be set and agreed to by Council's Health and Building Unit.

(15) STORMWATER AND DRAINAGE - MINOR DEVELOPMENT

The drainage system is to be constructed in accordance with the City's standard requirements as detailed in the City of Sydney's Stormwater Drainage Manual. The development is to be designed so that the flow of pollutants from the site due to stormwater is reduced.

(16) SYDNEY WATER CERTIFICATE (TAP-IN)

- (a) The approved plans must be submitted to Sydney Water's "Tap-in" online service to determine whether the development will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. Sydney Water's "Tap-in" online service is available at www.sydneywater.com.au, (see Plumbing, Building & Development and then Sydney Water "Tap-in").
- (b) The Consent Authority or a Principal Certifier must ensure that Sydney Water has appropriately stamped the plans before the commencement of work.

(17) WASTE AND RECYCLING MANAGEMENT - GENERAL

The proposal must comply with the relevant provisions of Council's *Guidelines for Waste Management in New Developments 2018* which requires facilities to promote the efficient storage, separation, collection and handling of waste to maximise resources recovery.

(18) ASBESTOS REMOVAL WORKS

- (a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence must be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.
- (c) All work must be carried out in accordance with the *Work Health and Safety Regulation 2017* and the NSW Government and SafeWork NSW document entitled *How to manage and control asbestos in the work place: Code of Practice (Safework NSW)* December 2011 and the *City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines*.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.
- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 -1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.
- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).
- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.
- (i) A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

(19) NOTIFICATION – NEW CONTAMINATION EVIDENCE

Council's Area Planning Manager and the Principal Certifier must be notified of any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination.

(20) CLASSIFICATION OF WASTE

Prior to the exportation of waste (including fill or soil) from the site, the waste materials must be classified in accordance with the provisions of the Protection of the *Environment Operations Act 1997* and the *NSW EPA Waste Classification Guidelines, Part1: Classifying Waste (November 2014)*. The classification of the material is essential to determine where the waste may be legally taken. The *Protection of the Environment Operations Act 1997* provides for the commission of an offence for both the waste owner and the transporters if the waste is taken to a place that cannot lawfully be used as a waste facility for the particular class of waste. For the transport and disposal of industrial, hazardous or Group A liquid waste advice should be sought from the EPA.

- (b) Sampling and analysis of the fill material shall be conducted in accordance with NSW EPA (1995) Sampling Design Guidelines.

(21) IMPORTED FILL MATERIALS

All fill imported onto the site must be validated to ensure the imported fill is suitable for the proposed land use from a contamination perspective. Fill imported on to the site shall also be compatible with the existing soil characteristic for site drainage purposes.

The City may require details of appropriate validation of imported fill material to be submitted with any application for future development of the site. Hence all fill imported onto the site should be validated by either one or both of the following methods during remediation works:

- (a) Imported fill must be accompanied by documentation from the supplier which certifies that the material is not contaminated based upon analyses of the material for the known past history of the site where the material is obtained.

(22) TREES THAT MUST BE PROTECTED

- (a) The existing trees detailed in Table 1 below must be protected in accordance with the conditions of consent throughout the construction and development.

Table 1 – Trees to be protected:

Tree No	Botanical/Common Name	Location
1	Melaleuca quinquenervia (Paperbark)	Street tree

(23) TREE PROTECTION PLANS

- (a) All detailed architectural, building, engineering (structural, stormwater and drainage services) and landscape documentation submitted for the

Construction Certificate shall clearly show on all drawings the retention of trees as required by these conditions of consent, the position of their trunks, full diameter of their canopies, Structural Root Zones (SRZs) and Tree Protection Zones (TPZs).

(24) TREE PROTECTION DURING CONSTRUCTION

All trees within and adjoining the property must be protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites and as follows:

- (a) Stockpiling, storage or mixing of materials, washing of equipment, vehicle parking, disposal of liquids, machinery repairs and refuelling, disposal of building materials such as cement slurry, siting of offices or sheds and the lighting of fires, must not occur within 4 metres of the trunk of any tree (including trees in adjoining properties).
- (b) Excavation (except for localised siting of pier) must not occur within 4 metres of any tree (including trees in adjoining properties). If excavation is proposed within this zone, the Council's Tree Management Officer must be contacted immediately and the excavation must be carried out in accordance with Council's direction.
- (c) Excavations for the footings where they are within 4 metres of any tree (including trees in adjoining properties) must be undertaken using non-destructive methods (such as by hand) to ensure no tree roots greater than 40mm diameter are damaged, pruned or removed.
- (d) Footings shall be relocated / realigned if any tree root greater than 40mm in diameter is encountered during excavations. A minimum of 150mm clearance shall be provided between the tree root and footing.
- (e) The consent from Council's Tree Management Officer must be obtained prior to the undertaking of any tree pruning works, including tree roots greater than 40mm in diameter. Only minor pruning works will be approved by Council.

(25) TREE PRUNING

- (a) A separate permit to prune any trees within or adjacent to the property and/or any pruning of tree roots must be obtained from Council prior to any works being undertaken.

(26) STREET TREE PROTECTION

All street trees directly outside the site must be retained and protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites. All street trees must be protected during the construction works as follows:

- (a) Tree trunk and major limb protection must be undertaken prior to the commencement of any works. The protection must be installed and certified by a qualified Arborist (AQF level 3) and must include:

- (i) An adequate clearance, minimum 250mm, must be provided between the structure and tree branches, limbs and trunks at all times;
 - (ii) Tree trunk/s and/or major branches, must be protected by wrapped hessian or similar material to limit damage, and
 - (iii) Timber planks (50mm x 100mm or similar) must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals, and must be fixed against the trunk with tie wire, or strapping. The hessian and timber planks must not be fixed to the tree in any instance, or in any fashion,
 - (iv) Tree trunk and major branch protection is to remain in place for the duration of construction and development works, and must be removed at the completion of the project.
- (b) All hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree setts. Supporting columns must not be placed on any tree roots that are exposed.
- (c) Young street trees shall be protection by installing three (3) wooden takes around the edge of the tree pit. Hessian shall be wrapped around the stakes. If existing stakes are already in place, these shall suffice as tree protection.
- (d) Temporary signs, or any other items, shall not be fixed or attached to any street tree.
- (e) Materials or goods, including site sheds, must not be stored or placed:
 - (i) around or under the tree canopy; or
 - (ii) within two (2) metres of tree trunks or branches of any street trees.
- (f) Any excavation within in any area known to, or suspected of having street tree roots greater than 40mm diameter must be undertaken by hand.
- (g) Any trenching works for services / hydraulics / drainage etc must not be undertaken within 4 metres of any street tree. Alternative installation methods for services, such as directional boring/drilling, or redirection of services shall be employed where large woody roots greater than 40mm diameter are encountered during the installation of any services.
- (h) Existing sections of kerbs adjacent to any street tree must not be removed without approval from the Council's Tree Management Officer.
- (i) Any damage sustained to street tree/s as a result of construction activities (including demolition) must be immediately reported to the Council's Tree Management Officer on 9265 9333. Any damage to street trees as a result of construction activities may result in a prosecution under the Local Government Act 1993 and the Environmental Planning and Assessment Act 1979.

(27) STREET TREE PRUNING

- (a) The consent from Council's Tree Management Officer must be obtained prior to the undertaking of any street tree pruning works including tree roots greater than 40mm diameter. Only minor pruning works will be approved by Council.
- (b) Any pruning that has been approved by Council, must be carried out by a qualified Arborist (AQF3), and must be in accordance with AS4373 Australian Standards 'Pruning of Amenity Trees'.

(28) ADVANCED TREE PLANTING

Tree planting within the property must be undertaken in accordance with the following conditions, and to Council's satisfaction, prior to the issuing of the Occupation Certificate;

- (a) One tree is to be planted in the rear courtyard at the completion of all construction works
- (b) The tree species, when mature, must attain a minimum height of no less than 7 metres. Palms, fruit trees and species recognised to have a short life span are not considered a suitable replacement.
- (c) The tree must be grown to Australian Standard 2303:2015 'Tree stock for landscape use'
- (d) At the time of planting, the container size is to be a minimum of 75 litres and a minimum height of 2 metres.
- (e) New trees must be planted in natural ground with adequate soil volumes to allow maturity to be achieved. Planter boxes will not be accepted for tree planting;
- (f) New trees must be appropriately located away from existing buildings and structures to allow maturity to be achieved without restriction;
- (g) The tree must be planted by a qualified Horticulturalist or Arborist of Level 2 under the Australian Qualifications Framework (AQF).
- (h) The replacement planting/s must be planted in such a manner as to promote good health during the establishment period, and must be maintained, as far as practicable to ensure tree growth into maturity.
- (i) Written confirmation is to be obtained from Council's Area Planning Manager that all tree planting/s have been completed to Council's satisfaction (excluding tree maintenance) prior to the issue of an Occupation Certificate.
- (j) Any newly planted tree that fails to establish within 2 years of the initial planting date must be replaced with a tree of comparable qualities.

(29) APPLICATION FOR HOARDINGS AND SCAFFOLDING INSTALLED ON OR ABOVE A PUBLIC ROAD AND OPERATING HOISTING DEVICES INCLUDING BUILDING MAINTENANCE UNITS OVER A PUBLIC ROAD

- (a) Where a hoarding and/or scaffolding (temporary structures) are proposed to be installed on or above a road reservation (footway and/or roadway), a separate application under Section 68 of the *Local Government Act 1993* and Sections 138/139 of the *Roads Act 1993* must be submitted to and approved by Council for such structures.
- (b) Where an approval (Permit) is granted allowing the placement of temporary structures on or above a public road the structures must comply fully with Council's *Hoarding and Scaffolding Policy; Guidelines for Hoardings and Scaffolding*; and the conditions of approval (Permit) granted including:
 - (i) maintaining a current and valid approval for the full duration that the temporary structure/s is in place;
 - (ii) maintaining temporary structure/s in a structurally sound and stable condition for the full duration of installation (Clause 2.11.1);
 - (iii) bill posters and graffiti being removed within 24 hours of their placement (Clause 2.11.2);
 - (iv) maintaining temporary structures and the public place adjoining the work site in a clean and tidy condition including repainting and/or repair of graphics (Clauses 2.11.1, 2.11.4, 2.14.1 and 3.9.3);
 - (v) maintaining a watertight deck (Type B hoardings) to prevent liquids including rainwater, falling onto the footway/roadway surfaces (Clauses 3.9.1 and 3.9.4);
 - (vi) approved site sheds on the decks of a Type B hoarding being fully screened from the public place (Clause 3.9.5);
 - (vii) material and equipment not being placed or stored on the deck of Type B hoardings, unless specifically approved by Council (Clause 3.9.4);
 - (viii) providing and maintaining operational artificial lighting systems under Type B hoardings including at high-bay truck entry points (Clause 3.9.9); and
 - (ix) ensuring all required signage, artwork or historic images are provided and fully maintained to the City's requirements (Clauses 3.4, 3.9.3, 3.9.6, 3.9.8, 3.10.1 and 4.2).

If it is proposed to operate a hoisting device including a building maintenance unit above a public road which swings, hoists material/equipment and/or slews/wind vanes any part of the device over the public road, a separate application under Section 68 of the *Local Government Act 1993* and Sections 138/139 of the *Roads Act 1993* must be made to Council to obtain approval.

Note: 'Building maintenance unit' means a power-operated suspended platform and associated equipment on a building specifically designed to provide

permanent access to the faces of the building for maintenance (*Work Health and Safety Regulation 2017*).

SCHEDULE 1C

DURING CONSTRUCTION/PRIOR TO OCCUPATION/COMPLETION

(30) USE OF INTRUSIVE APPLIANCES – NOT APPROVED

This development consent does not extend to the use of appliances which emit noise of a highly intrusive nature (such as pile - drivers and hydraulic hammers) or are not listed in Groups B, C, D, E or F of Schedule 1 of the City of Sydney Code of Practice for Construction Hours/Noise 1992".

A separate Section 4.55 application must be submitted to the Council for the use of any equipment of a highly intrusive nature (such as pile - drivers and hydraulic hammers) or are not listed in Groups B, C, D, E or F of Schedule 1 of the *City of Sydney Code of Practice for Construction Hours/Noise 1992*.

(31) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on-site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Team, prior to works proceeding

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

(32) BASIX

All commitments listed in each relevant BASIX Certificate for the development must be fulfilled prior to any Occupation Certificate being issued.

(33) ENCROACHMENTS – NEIGHBOURING PROPERTIES

No portion of the proposed structure shall encroach onto the adjoining properties.

(34) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

(35) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

(36) LOADING AND UNLOADING DURING CONSTRUCTION

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site, where possible.
- (b) If, it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.
- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.
- (d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate application under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993 must be submitted to and approved by Council.

(37) NO OBSTRUCTION OF PUBLIC WAY

Unless otherwise approved by Council, the public way must not be obstructed by any materials, vehicles, waste receptacles, skip-bins or the like. Non-compliance with this requirement may result in the issue of a notice by Council to stop all work on the site.

(38) USE OF MOBILE CRANES

The following requirements apply:

- (a) Mobile cranes operating from the road must not be used as a method of demolishing or constructing a building.
- (b) For special operations including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes, permits must be obtained from Council for the use of a mobile crane. The permits must be obtained 48 hours beforehand for partial road closures which, in the opinion of Council will create minimal traffic disruptions and 4 weeks beforehand in the case of full road closures and partial road closures which, in the opinion of Council, will create significant traffic disruptions.
- (c) The use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of approved hours of construction can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

SCHEDULE 2

PRESCRIBED CONDITIONS

The prescribed conditions in accordance with Division 8A of the *Environmental Planning and Assessment Regulation 2000* apply:

- Clause 98 Compliance with *Building Code of Australia* and insurance requirements under the *Home Building Act 1989*
- Clause 98A Erection of signs
- Clause 98B Notification of *Home Building Act 1989* requirements
- Clause 98C Conditions relating to entertainment venues
- Clause 98D Conditions relating to maximum capacity signage
- Clause 98E Conditions relating to shoring and adequacy of adjoining property

Refer to the NSW State legislation for full text of the clauses under Division 8A of the *Environmental Planning and Assessment Regulation 2000*. This can be accessed at: <http://www.legislation.nsw.gov.au>