

Attachment A

Recommended Conditions of Consent
--

SCHEDULE 1 – DEFERRED COMMENCEMENT CONDITIONS (CONDITIONS TO BE SATISFIED PRIOR TO CONSENT OPERATING)

The following deferred commencement conditions must be satisfied prior to the consent becoming operative:

(A) PART A - DEFERRED COMMENCEMENT CONDITIONS

(CONDITIONS TO BE SATISFIED PRIOR TO CONSENT OPERATING)

The consent is not to operate until the following condition is satisfied, within **24 months** of the date of this determination:

(1) DESIGN MODIFICATIONS – TREES

The design of the building must be modified as follows:

- (a) The design of the entire Dwelling 2 and the Dwelling 1 addition, boundary wall and any retaining walls must be constructed without the use of a continuous strip footing. The construction method shall include flexibly located pier and beam footings, and the terraces and concrete slabs must be installed at or above grade. The design and construction must ensure tree roots greater than 40mm in diameter are not damaged, pruned or removed during construction.
- (b) The design of the rear vehicle turning area must be amended to ensure no level changes occur within the Tree Protection Zone (TPZ) of protected trees. The concrete turning circle slab must be constructed using an elevated pier and beam or cantilever slab to ensure a 0.5m gap is maintained between ground level and slab.
- (c) A section drawing detailing the southern side and northern side of the site is to be provided to reflect the above design amendments.
- (d) Stormwater drainage including excavation for pits must be located outside the Structural Root Zone (SRZ) of all trees. Where it is within the TPZ of tree(s) it must be installed using non-destructive trenching techniques (such as by hand / airspade) to ensure no tree roots >30mm diameter are damaged, pruned or removed.

The amended plans and details must be submitted and approved by the Area Planning Manager.

(2) DESIGN MODIFICATIONS – FLOODING

The design of the driveway must be modified as follows:

- (a) The architectural plans must be updated to show the driveway crest at a minimum height of 15.25m AHD, as per the civil engineering drawings submitted with the application.

The modifications are to be submitted to and approved by Council's Area Planning Manager.

Evidence that will sufficiently enable Council to be satisfied as to those matters identified in deferred commencement conditions, as indicated above, must be submitted to Council within 24 months of the date of determination of this deferred commencement consent failing which, this deferred development consent will lapse pursuant to section 4.53(6) of the Environmental Planning and Assessment Act 1979.

The consent will not operate until such time that the Council notifies the Applicant in writing that deferred commencement consent conditions, as indicated above, have been satisfied.

Upon Council giving written notification to the Applicant that the deferred commencement conditions have been satisfied, the consent will become operative from the date of that written notification, subject to the conditions of consent, as detailed in Part B Conditions of Consent (Once the Consent is Operation).

(B) PART B – CONDITIONS OF CONSENT

SCHEDULE 1A

APPROVED DEVELOPMENT/DESIGN MODIFICATIONS/COVENANTS AND CONTRIBUTIONS/USE AND OPERATION

Note: Some conditions in Schedule 1A are to be satisfied prior to issue of a Construction Certificate and some are to be satisfied prior to issue of Occupation Certificate, where indicated.

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2021/865 dated 30 July 2021 and the following drawings prepared by Weir Phillips:

Drawing Number	Rev.	Drawing Name	Date
DA01	F	Site plan Roof plan	25.03.2022
DA10	G	Ground floor plan	01.04.2022
DA11	F	First floor plan	25.03.2022
DA12	F	Lower ground floor plan	25.03.2022
DA20	F	Overall western site elevation + park elevation	25.03.2022
DA21	F	Overall eastern site elevation	25.03.2022
DA22	F	Primary dwelling southern elevation + street front elevation	25.03.2022
DA23	F	Primary dwelling northern elevation	25.03.2022
DA24	F	Primary dwelling western elevation + eastern elevation	25.03.2022
DA25	F	Secondary dwelling southern elevation	25.03.2022
DA26	F	Secondary dwelling northern elevation	25.03.2022
DA27	F	Secondary dwelling western elevation + eastern elevation	25.03.2022
DA30	F	Section A-A	25.03.2022
DA31	F	Section B-B	25.03.2022

Drawing Number	Rev.	Drawing Name	Date
DA32	F	Section C-C	25.03.2022

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the drawings will prevail.

(2) SECTION 7.11 CONTRIBUTIONS PAYABLE - CONTRIBUTION TOWARDS PUBLIC AMENITIES – CITY OF SYDNEY DEVELOPMENT CONTRIBUTIONS PLAN 2015 – WEST PRECINCT

Council has identified the development will increase demand for public amenities and facilities. Pursuant to Section 7.11 of the Environmental Planning and Assessment Act, 1979 (as amended), and the City of Sydney Development Contributions Plan 2015 the following monetary contributions are required towards the cost of public amenities.

<u>Contribution Category</u>	<u>Amount</u>
Open Space	\$29,981.53
Community Facilities	\$9,753.33
Traffic and Transport	\$77.40
Stormwater Drainage	\$0.00
Total	\$39,812.27

The City of Sydney will index the above contribution for inflation at the time of payment using the following formula.

$$C_{\text{payment}} = C_{\text{consent}} \times (CPI_{\text{payment}} \div CPI_{\text{consent}})$$

Where:

C_{payment} = Is the contribution at time of payment;

C_{consent} = Is the contribution at the time of consent, as shown above;

CPI_{payment} = Is the Consumer Price Index (All Groups Index) for Sydney published by the Australian Bureau of Statistics that applies at the time of payment; and

CPI_{consent} = Is the Consumer Price Index (All Groups Index) for Sydney at the date the contribution amount above was calculated being – 121.6 for the December 2021 quarter.

The contribution must be paid prior to the issue of any Construction Certificate in relation to this development.

Please contact Council's Planning Administration staff at planningsystemsadmin@cityofsydney.nsw.gov.au to request a letter confirming the indexed contribution amount payable.

Once the letter confirming the indexed contribution is obtained, payment may be made at any of the City's Neighbourhood Service Centres or the One Stop Shop at Town Hall House. Acceptable payment methods are EFTPOS (debit card only), cash (up to 10K only), Credit Card (up to 50K only) or a bank cheque made payable to the City of Sydney. Personal or company cheques will not be accepted.

(3) AFFORDABLE HOUSING CONTRIBUTION – RESIDUAL LAND OR CENTRAL SYDNEY – PAYMENT IN LIEU OF FLOOR SPACE CONTRIBUTION – PRIOR TO CONSTRUCTION CERTIFICATE

- (a) In accordance with the City of Sydney Affordable Housing Program and prior to the issue of a Construction Certificate, the applicant must provide evidence that a monetary contribution towards the provision of affordable housing has been paid to the City of Sydney Council.
- (b) The contribution is \$126,669.19 (indexed at 1 April 2022). This is calculated by establishing the sum of the equivalent monetary contribution \$11,599.74 multiplied by 1.5% of the total floor area for residential development (404sqm).
- (c) If the contribution is paid after the indexation period in which the consent is granted, being 1 March 2022 to 28 February 2023, the above contribution will be adjusted according to the Sydney LGA median strata dwelling price ('MDP') using the following formula.
- (d) Contribution payable at Time of Payment = $C \times \text{MDP2} / \text{MDP1}$, where:
 - (i) C is the original total contribution amount payable to the City of Sydney as shown above;
 - (ii) MDP2 is the Median Strata Dwelling Price in Sydney LGA taken from the most recent NSW Government Rent and Sales Report at the time of indexation of the equivalent monetary contribution rate; and
 - (iii) MDP1 is the Median Strata Dwelling Price in Sydney LGA taken from the NSW Government Rent and Sales Report used to establish the current equivalent monetary contribution rate, being 1 March 2022 to 28 February 2023.

Contact Council's Planning Assessment Unit at planningsystemsadmin@cityofsydney.nsw.gov.au for written confirmation of the amount payable, with indexation as necessary, prior to payment.

(4) DESIGN MODIFICATIONS

The design of the building must be modified as follows:

- (a) The flue from the fireplace is to taper within the roof space so that the chimney which projects above the roof is reduced in width. The chimney is

to be similar to the typical width of nearby historic chimneys (i.e. 500mm-600mm).

- (b) The base and posts of the new palisade front fence are to be sandstone.

The modifications are to be submitted to and approved by Council's Area Planning Manager prior to the issue of a Construction Certificate.

(5) ADDITIONAL DETAILS

Additional information and/or drawings addressing the following are required:

- (a) The colour and detailing of the sandstone cladding to the new building. The sandstone is not to be heavily banded with substantial colour variation.
- (b) Details of the new balustrade to the rear of the existing dwelling.
- (c) The existing encaustic tile path, encaustic tiles, and marble edging to the front verandah of the existing dwelling are to be retained and conserved. Where the front encaustic tiled path widens and where it joins the verandah, there are two masonry plinths at the edge which detract from the character of the property. Details of how this is to be rectified/treated are to be shown on drawings which are to be prepared with input with the applicant's heritage consultant.

The modifications are to be submitted to and approved by Council's Area Planning Manager prior to the issue of a Construction Certificate.

(6) MATERIALS AND SAMPLES SCHEDULE – MINOR DEVELOPMENT

A detailed materials, colours and finishes schedule (including visible rainwater goods and services) keyed to each building elevation must be submitted to and approved by Council's Area Planning Manager prior to a Construction Certificate being issued. The materials and samples schedule/board must not include generic material or colour descriptions, or use terminology such as 'or similar'. Metal roofing is to be no darker than 'Basalt' in colour, with a lighter colour preferred to limit heat absorbance.

(7) BUILDING WORKS TO COMPLY WITH BCA – HERITAGE BUILDINGS OR BUILDINGS WITHIN CONSERVATION AREA

Any building works required to ensure compliance with the BCA or new building standards not specified in the submitted/approved plan must not damage existing fabric and building features. If such upgrading works have impact or potentially have impact on existing fabric and features, details of the works must be submitted and approved by Council's Area Planning Manager prior to issue of any Construction Certificate.

(8) DRIVEWAY REQUIREMENTS

The maximum height of the new brick columns on each side of the new fence and gate at the driveway shall be designed in accordance with AS2890.1, Figure 3.2 Sight Distance Requirements at Access Driveways.

(9) ASSOCIATED ROADWAY COSTS

All costs associated with the construction of any new road works including kerb and gutter, road pavement, drainage system and footway shall be borne by the developer. The new road works must be designed and constructed in accordance with the City's "Sydney Streets Technical Specification" including amendments and "Sydney Streets Design Code".

(10) COST OF SIGNPOSTING

All costs associated with signposting for any kerbside parking restrictions and traffic management measures associated with the development shall be borne by the developer.

(11) LAND SUBDIVISION

Any proposal to subdivide the site will require a separate application to Council to obtain development consent for the proposal and subsequent issue of the Subdivision Certificate under Section 6.15 of the *Environmental Planning and Assessment Act 1979*.

SCHEDULE 1B

PRIOR TO CONSTRUCTION CERTIFICATE/COMMENCEMENT OF WORK/HEALTH AND BUILDING

(12) GENERAL HERITAGE

- (a) The fabric and features to be retained by the proposal must be properly protected during the process of demolition and construction.
- (b) Appropriately qualified tradespersons (as appropriate) are to be commissioned who are skilled in traditional building and engineering trades to carry out work to the existing house, front fence and entry path.
- (c) The face brickwork, stone, and tiles must not be rendered, painted or coated.

(13) ARCHAEOLOGICAL DISCOVERY DURING EXCAVATION

- (a) Should any relics be unexpectedly discovered on the site during excavation, all excavation or disturbance to the area is to stop immediately and the Heritage Council of NSW should be informed in accordance with section 146 of the Heritage Act 1977.
- (b) Should any Aboriginal objects be unexpectedly discovered then all excavation or disturbance of the area is to stop immediately and NSW Government Office of Environment and Heritage is to be informed in accordance with Section 89A of the *National Parks and Wildlife Act 1974*.
- (c) Should any archaeological remains or Aboriginal objects be discovered, a copy of recording of the finds and the final archaeological summary report is to be submitted to Council prior to the issue of any Occupational Certificate.
- (d) If the discovery is on Council's land, Council must be informed.

(14) CONSTRUCTION TRAFFIC AND PEDESTRIAN MANAGEMENT PLAN

- (a) A Construction Traffic and Pedestrian Management Plan must be submitted to and approved by Council prior to a Construction Certificate being issued.
- (b) The approved plan must be complied with during any demolition and/or construction work.

Construction Traffic and Pedestrian Management Plans are to be prepared in accordance with Standard Requirements for Construction Traffic Management Plan on the City's website <http://www.cityofsydney.nsw.gov.au/business/business-responsibilities/traffic-management/construction-traffic-management-plans>

(15) ASBESTOS REMOVAL WORKS

- (a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence must be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.
- (c) All work must be carried out in accordance with the *Work Health and Safety Regulation 2017* and the NSW Government and SafeWork NSW document entitled *How to manage and control asbestos in the work place: Code of Practice (Safework NSW) December 2011* and the *City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines*.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.
- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 -1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.
- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).
- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.
- (i) A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

(16) CLASSIFICATION OF WASTE

Prior to the exportation of waste (including fill or soil) from the site, the waste materials must be classified in accordance with the provisions of the Protection of the *Environment Operations Act 1997* and the *NSW DECC Waste Classification Guidelines, Part1: Classifying Waste (July 2009)*. The classification of the material is essential to determine where the waste may be legally taken. The *Protection of the Environment Operations Act 1997* provides for the commission of an offence for both the waste owner and the transporters if the waste is taken to a place that cannot lawfully be used as a waste facility for the particular class of waste. For the transport and disposal of industrial, hazardous or Group A liquid waste advice should be sought from the EPA.

(17) ACID SULFATE SOILS MANAGEMENT PLAN

An Acid Sulphate Soil Management Plan must be prepared by a suitably qualified person in accordance with the *Acid Sulphate Soil Assessment Guidelines (Acid Sulfate Soils Management Advisory Committee August 1998)*.

The Management Plan must be submitted to and approved in writing by the City's Area Planning Manager prior to the issue of a Construction Certificate

(18) NOTIFICATION – NEW CONTAMINATION EVIDENCE

Council's Area Planning Manager and the Principal Certifier must be notified of any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination.

(19) BASIX CERTIFICATE – DETAILS TO BE LODGED WITH A CC

A copy of the required completed BASIX certificate accepted as part of this Development Consent with respect to the proposed residential building works, must be lodged with an application for a construction certificate and the items nominated as part of the subject BASIX certificate must be specified on the plans submitted with the construction certificate application. – See Note.

IMPORTANT NOTE:

Any requirement detailed in the accompanying BASIX Certificate, MUST be included as a specific notation or inclusion on any future Construction Certificate plans and specification in accordance with Part 3 of Schedule 1 of the EP&A Regulation, 2000.

(20) STRUCTURAL CERTIFICATION FOR EXISTING BUILDING – ALTERATIONS AND ADDITIONS

A qualified practising registered structural engineer must provide structural certification to Council (where Council is the Accredited Certifier) verifying that the existing structure can adequately support the proposed new loads and the structural design complies with the Structural Provisions of Part B1 (Vol 1) and Part 2.1 (Vol 2) of the *Building Code of Australia* prior to a Construction Certificate being issued. The proposed additional loads and/or alterations must not cause a decrease in the existing structural performance of the building including its performance under earthquake actions (AS1170.4).

(21) EROSION AND SEDIMENT CONTROL - BETWEEN 250 AND 2,500SQM

Prior to the commencement of demolition/excavation/construction work, an Erosion and Sediment Control Plan (ESCP) must be submitted to and be approved by the Principal Certifier. The ESCP must:

- (a) Conform to the specifications and standards contained in *Managing Urban Stormwater: Soils and Construction* (Landcom, 2004); the *Guidelines for Erosion and Sediment Control on Building Sites* (City of Sydney, 2004); and the *NSW Protection of the Environment Operations Act 1997*.
- (b) Include a drawing(s) that clearly shows:
 - (i) location of site boundaries and adjoining roads
 - (ii) approximate grades and indications of direction(s) of fall
 - (iii) approximate location of trees and other vegetation, showing items for removal or retention
 - (iv) location of site access, proposed roads and other impervious areas
 - (v) existing and proposed drainage patterns with stormwater discharge points
 - (vi) north point and scale
- (c) Specify how soil conservation measures will be conducted on site including:
 - (i) timing of works
 - (ii) locations of lands where a protective ground cover will, as far as is practicable, be maintained
 - (iii) access protection measures
 - (iv) nature and extent of earthworks, including the amount of any cut and fill
 - (v) where applicable, the diversion of runoff from upslope lands around the disturbed areas
 - (vi) location of all soil and other material stockpiles including topsoil storage, protection and reuse methodology
 - (vii) procedures by which stormwater is to be collected and treated prior to discharge including details of any proposed pollution control device(s)
 - (viii) frequency and nature of any maintenance program
 - (ix) other site-specific soil or water conservation structures.

(22) DILAPIDATION REPORT – MINOR

Subject to the receipt of permission of the affected landowner, dilapidation report/s of adjoining buildings are to be prepared by an appropriately qualified practising structural engineer and submitted for the approval of the Accredited Certifier:

- (a) prior to the commencement of demolition/excavation works; and
- (b) on completion of construction demolition/excavation works.

(23) DILAPIDATION REPORT - PUBLIC DOMAIN

Prior to an approval for demolition and preparatory works being granted or the issue of any Construction Certificate, whichever is earlier, a photographic recording of the public domain site frontages is to be prepared as described in the Public Domain Manual and submitted for approval by Council's Public Domain Unit. The City's *Public Domain Manual* is available for download from the City's website at <https://www.cityofsydney.nsw.gov.au/>

The submission is to include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

(24) SURVEY INFRASTRUCTURE – IDENTIFICATION AND RECOVERY

Under Section 24 of the Surveying and Spatial Information Act 2002, it is an offence to remove, damage, destroy, displace, obliterate or deface any survey mark unless authorised to do so by the Surveyor-General. Accordingly, the applicant must, where possible, ensure the preservation of existing survey infrastructure undisturbed and in its original state or else provide evidence of the Surveyor-General's authorisation to remove or replace marks.

Prior to the issue of any Construction Certificate, documentary evidence must be prepared by a Registered Surveyor and submitted to and approved by Council's Area Planning Manager / Coordinator. This evidence must include either:

- (a) A copy of any Surveyor-General's Approval for Survey Mark Removal granted by NSW Spatial Services for the subject site, including all documentation submitted as part of that application (for example the survey mark audit schedule, strategy plan and strategy report); or
- (b) A letter, signed by a current NSW Registered Land Surveyor and including his or her Board of Surveying and Spatial Information (BOSSI) identification number, stating that all investigations required under Surveyor-General's Direction No.11 have been made for the subject site and that no survey infrastructure will be affected by the proposal.

Council's Principal Surveyor may request further information and/or add conditions to any Surveyor-General's Approval at their discretion.

(25) STORMWATER AND DRAINAGE - MINOR DEVELOPMENT

The drainage system is to be constructed in accordance with the City's standard requirements as detailed in the City of Sydney's Stormwater Drainage Manual. The development is to be designed so that the flow of pollutants from the site due to stormwater is reduced.

The requirements of Sydney Water regarding the on-site detention (OSD) of stormwater must be ascertained and complied with. Evidence of the on-site detention (OSD) approval must be submitted to City's Public Domain Unit prior to issue of any Construction Certificate other than demolition.

(26) FLOOD PLANNING LEVELS

The development must be constructed to comply with the recommended flood planning levels indicated in submitted document - Site Specific Flood Information prepared by "WMAwater" dated 25 October 2021.

Details must be submitted to the Principal Certifier prior to the issue of any Construction Certificate demonstrating that the development will comply with the recommended flood planning levels.

(27) TEMPORARY DEWATERING DURING CONSTRUCTION

Prior to discharging any water collected during excavation and construction into the City's stormwater drainage system, approval must be sought from the City's Public Domain Unit. A dewatering management plan must be submitted with an *Application for Temporary Dewatering* available to download on the City's website.

Other options for dewatering include disposal to sewer with prior approval from Sydney Water, or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

(28) PUBLIC DOMAIN PLAN DETAILED DOCUMENTATION FOR CONSTRUCTION

A detailed public domain plan and all relevant documentation must be submitted to and approved by City's Public Domain Unit prior to the construction of any public domain works. This Plan must document all works required to ensure that the public domain complies with the City of Sydney's *Public Domain Manual*, *Sydney Streets Code*, *Sydney Street Tree Masterplan*, *Sydney Lights Design Code* and *Sydney Streets Technical Specification*. The documentation must be *checked, accurate, and comply with specified requirements*. Plans must be based on an accurate survey, to scale and fully coordinated across all disciplines and submissions. The supplied documentation must be for Construction issue and will be approved under Section 138 of the Roads Act.

The Public Domain Manual and all other relevant documents are available for download from Council's website at <https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

The Public Domain Plan documentation must be submitted with an *Application for Public Domain Plan Assessment*. The proposed detailed design of the public domain shall include the latest approved architectural layout along the boundary.

(29) HOLD POINTS

Prior to an approval being issued for the construction of public domain and / or planning agreement works, including civil, drainage and subsurface works, a set of hold points will be provided by the City's Public Domain Unit in accordance with the City's Public Domain Manual and Sydney Streets Technical Specification. The list of hold point inspections will be included in the Public Domain works approval letter.

These hold point inspections must be adhered to during construction works. Prior to the issue of any Occupation Certificate, confirmation from the City's Public Domain Unit, that hold point inspections have been completed and works have been accepted by the City must be provided to the Principal Certifier.

(30) PUBLIC DOMAIN WORK – CONSTRUCTION APPROVAL UNDER SECTION 138 ROADS ACT 1993

Prior to the construction of any public domain works, approval under Section 138 / 139 of the *Roads Act 1993* must be issued by the City's Public Domain Unit.

(31) PUBLIC DOMAIN WORKS SECURITY BOND

A Public Domain Works Security Bond will be required for the public domain works and for repairing damage that may be caused to the public domain in the vicinity of the site, in accordance with the City of Sydney's adopted fees and charges and the Public Domain Manual.

The City's Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The bond must be lodged with the City prior to an approval being issued for the approval of the Public Domain Plan.

The bond will be retained in full until all public domain works, including any rectification of damage to the public domain, are completed to City's standards, and the required work as executed documentation is approved. On satisfying the above requirements and the issue of the Public Domain Works Letter of Completion Operational Acceptance by the City, 90% of the bond will be released. The remaining 10% balance will be held for the duration of the specified defects liability period.

(32) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS

All works to the City's public domain, including rectification of identified defects, are subject to a 6 month defects liability period from the date of Completion. The date of Completion will be nominated by Council on the Public Domain Works – Letter of Completion Operational Acceptance.

(33) NO OBSTRUCTIONS

All public footways and paths of travel must be free from obstructions. If services are required to be relocated to clear paths of travel then this must be undertaken at the developer's expense. All obstructions are to be removed prior to the issue of any Occupation Certificate.

(34) PUBLIC DOMAIN WORKS COMPLETION

The Public Domain works are to be constructed in accordance with the Public Domain Works Approval letter, stamped plans for Public Domain Levels and Gradients, Stormwater, Public Domain Lighting, the City's *Public Domain Manual*, *Stormwater Drainage Manual*, *Sydney Lights Design Code* and *Sydney Streets Technical Specification*.

The public domain work must be inspected and a Public Domain Works Letter of Completion Operational Acceptance must be issued by Council's Public Domain Officer prior to the issue of any Occupation Certificate or before the commencement of use, whichever is earlier.

(35) PUBLIC DOMAIN WORKS COMPLETION – WORK AS EXECUTED DOCUMENTATION

Prior to a Public Domain Works Letter of Completion Operational Acceptance being issued for public domain works, Works-As-Executed (As-Built) plans and documentation, must be submitted to and accepted by the City of Sydney for all public domain works, including where required Stormwater, Public Domain Lighting and Road construction. Details of the plans and documentation required for approval will be advised by the City's Public Domain Unit.

(36) SURVEY INFRASTRUCTURE – RESTORATION

- (a) Prior to any Occupation Certificate being issued for the development, documentary evidence of restoration must be prepared by a Registered Surveyor and submitted to and approved by Council's Area Planning Manager / Coordinator. This evidence must include:
 - (i) Certification that all requirements requested under the Surveyor-General's Approval for Survey Mark Removal or by the City's Principal Surveyor under condition "Survey Infrastructure – Identification and Recovery" have been complied with;
 - (ii) Certification that all requirements requested under any Surveyor-General's Approval for Deferment of Survey Marks from condition "Survey Infrastructure – Pre Subdivision Certificate works" have been complied with and;
 - (iii) Time-stamped photographic records of all new survey infrastructure relating to the site clearly showing the mark itself and sufficient context to aid in identifying the mark on site.

(37) CONSTRUCTED FLOOR LEVELS

A certification report prepared by a suitably qualified practitioner engineer (NER), must be submitted to the Principal Certifier prior to the issue of any Occupation Certificate stating that the development has been constructed and the required flood planning levels achieved in accordance with the recommendations of the report titled Site Specific Flood Information prepared by "WMAwater" dated 25 October 2021.

(38) PUBLIC DOMAIN DAMAGE BOND

- (a) A Public Domain Damage Security Bond calculated on the basis of 44.00 square metres of bitumen site frontage must be lodged with the City in accordance with the City of Sydney's adopted fees and charges. The bond must be provided as security for repairing any damage to the public domain in the vicinity of the site.
- (b) The City's Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The Bond must be lodged with the City prior to an approval for demolition being granted or any Construction Certificate being issued, whichever is earlier.
- (c) The bond in this condition will be released in full when the Final Occupation Certificate has been issued and, any rectification works to the footway and Public Domain, are completed to City's satisfaction. If rectification works are required the City will release 90% of the total Bond, with the remaining 10% balance to be held for the duration of a 6 months Defect Liability Period.

(39) PROTECTION OF STONE KERBS

The design of the building must be modified as follows:

- (a) The existing stone kerbs on the Victoria Road frontage of the site are to be retained and properly protected during demolition, excavation and construction works.
- (b) To avoid damage to stone kerbs during excavation and construction works for the development, temporary removal and storage of the stone kerbs may be approved by Council. Removed, serviceable stone kerbs (i.e. those that are in good condition as agreed by Council officers) must be re-installed in accordance with the City of Sydney's standard details and specifications after the construction works have been completed. A temporary concrete kerb will need to be constructed to retain the footpath until the stone kerbs can be reinstalled.
- (c) Note the following:
 - (i) All costs associated with the works are to be borne by the developer.
 - (ii) Damaged kerbs are to be replaced to match existing to Council's satisfaction or as otherwise advised by Council officers.
 - (iii) Where new vehicle crossings or temporary crossings are to be constructed to access the property, the affected kerb stones should be salvaged and reused wherever possible.
 - (iv) All new driveway laybacks and kerbs are to be constructed with stone kerbs to match existing stones or as specified by City officers.
 - (v) Council approval is required before kerbs are removed.
 - (vi) Council approval is required prior to the cutting of existing stone kerbs for stormwater kerb outlets.

- (vii) A bond may be required for stone kerbs and gutters in accordance with the City of Sydney's adopted Schedule of Fees and Charges. If so, this will be included with the Public Domain Damage Bond.

(40) DRAINAGE AND SERVICE PIT LIDS

All existing or proposed drainage and service pit lids throughout the public domain must be to City of Sydney specifications and heel/bicycle safe, slip resistant, infill with material to match surrounding surface, finished flush with the adjacent pavement to avoid trip hazards and be clear of obstructions for easy opening and cleaning. Infill pit lids are to be detailed where specified by Council's Public Domain Officer. Private pits are not permitted within the public domain. All details of pit lids must be shown on the public domain plan and must be approved by the City's Public Domain Unit prior to the issue of an approval for public domain works.

(41) SYDNEY WATER CERTIFICATE (TAP-IN)

- (a) The approved plans must be submitted to Sydney Water's "Tap-in" online service to determine whether the development will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. Sydney Water's "Tap-in" online service is available at www.sydneywater.com.au, (see Plumbing, Building & Development and then Sydney Water "Tap-in").
- (b) The Consent Authority or a Principal Certifier must ensure that Sydney Water has appropriately stamped the plans before the commencement of work.

(42) UTILITY SERVICES

To ensure that utility authorities are advised of the development:

- (a) Prior to the issue of a Construction Certificate a survey is to be carried out of all utility services within and adjacent to the site including relevant information from utility authorities and excavation if necessary, to determine the position and level of services.
- (b) Prior to the commencement of work the applicant is to obtain written approval from the utility authorities (e.g. Energy Australia, Sydney Water, and Telecommunications Carriers) in connection with the relocation and/or adjustment of the services affected by the construction of the underground structure. Any costs in the relocation, adjustment or support of services are to be the responsibility of the developer.

(43) WASTE AND RECYCLING MANAGEMENT - GENERAL

The proposal must comply with the relevant provisions of Council's *Guidelines for Waste Management in New Developments 2018* which requires facilities to promote the efficient storage, separation, collection and handling of waste to maximise resources recovery.

(44) COMPLIANCE WITH ARBORIST'S REPORT

Prior to approval of the Construction Certificate an updated Arboricultural Impact Assessment based on the most up-to-date plans must be submitted and approved by Council's Tree Management.

(45) TREE PROTECTION ZONE

- (a) Before the commencement of works, Tree Protection Zone/s (TPZ) must be established around all trees to be retained not less than the distance indicated in the TPZ schedule below.
- (b) Tree protection must be installed and maintained in accordance with the Australian Standard 4970 Protection of Trees on Development Sites and with the following schedule:

TPZ Schedule

Tree No.	Species Name	Location	Radius (m) From Trunk
1	<i>Lophostemon confertus</i>	Street tree	2
2	<i>Celtis australis</i>		2.5
8	<i>Archontophoenix alexandrae</i>	1 Alexandra Lane	2.5
10	<i>Gingko biloba</i>		3
11	<i>Camellia sasanqua</i>		2
12	<i>Unknown species</i>		2
14	<i>Archontophoenix alexandrae</i>	3 Victoria Road	2
15	<i>Lophostemon confertus</i>	Jubilee Park	7
16	<i>Jacaranda mimosifolia</i>		7
17	<i>Cinnamoumum camphora</i>		15
18	<i>Ficus rubiginosa</i>		11
19	<i>Ficus rubiginosa</i>		15
20	<i>Lophostemon confertus</i>		9
21	<i>Ficus rubiginosa</i>		14
22	<i>Lophostemon confertus</i>		6
23	<i>Cinnamoumum camphora</i>		15

Note: Only applies to the TPZ within the subject development site.

- (c) Tree Protection Fencing must be installed and maintained prior to the commencement of any works and in accordance with the following:
 - (i) A 1.8 metre high fully supported chainmesh protective fencing, secured and fastened to prevent movement shall be installed around the TPZ distance surrounding trees. Woody roots must not be damaged or destroyed during the establishment or maintenance of the fencing;
 - (ii) The area within the fencing shall be mulched to a depth of 75mm and kept free of weeds and grass for the duration of works

- (iii) Tree Protection Signage shall be attached facing outwards in a visible position identifying the name and contact details of the site Arborist. All signs must remain in place throughout all work on site.
 - (iv) Tree Protection Fencing must not be relocated unless written approval is obtained from the Site Arborist and a copy is provided to Council which outlines alternate protection measures required to ensure all trees remain viable and confirmation that the relocation of the fencing will not impact the tree/s.
- (d) The ground surface protection must be installed if construction access is required through any TPZ and part (g)(i) of this condition has been approved:
- (i) Protected with boarding (ie scaffolding board or plywood sheeting or similar material), placed over a layer of mulch to a depth of at least 75mm and geotextile fabric;
 - (ii) The protective boarding must be left in place for the duration of the construction and development.
- (e) The following works must be excluded from within any TPZs:
- (i) Excavation (except for localised siting of piers / demolition of the concrete slab);
 - (ii) Soil cut or fill including trenching;
 - (iii) Soil cultivation, disturbance or compaction;
 - (iv) Stockpiling, storage or mixing of materials;
 - (v) The parking, storing, washing and repairing of tools, equipment and machinery;
 - (vi) The disposal of liquids and refuelling;
 - (vii) The disposal of building materials;
 - (viii) The siting of offices or sheds;
 - (ix) Any action leading to the impact on tree health or structure.
- (f) Any trenching works for services / hydraulics / drainage etc must not be undertaken within any Tree Protection Zone (TPZ). Alternative installation methods for services, such as directional boring/drilling, or redirection of services shall be employed.
- (g) All work undertaken within or above the TPZ must be:
- (i) Carried out in accordance with a work methodology statement prepared by an Arborist (minimum AQF Level 5) and written approval is obtained from Council's Tree Management Officer before its implementation; and
 - (ii) Supervised by a qualified Consultant Arborist (minimum AQF Level 5).

(46) TREE ROOT PROTECTION

(a) Structural Root Zone (SRZ) Schedule;

Tree No.	Species Name (Common name)	Location	Radius (m) From Trunk
1	<i>Lophostemon confertus</i> (Brush Box)	Street tree	2
2	<i>Celtis australis</i> (Nettle tree)		1.8
8	<i>Archontophoenix alexandrae</i> (Alexander Palm)	1 Alexandra Lane	n/a
10	<i>Gingko biloba</i> (Maidenhair Tree)		1.9
11	<i>Camellia sasanqua</i> (Camellia sasanqua)		1.5
12	<i>Unknown species</i>	5 Victoria Road	1.6
14	<i>Archontophoenix alexandrae</i> (Alexander Palm)	3 Victoria Road	n/a
15	<i>Lophostemon confertus</i> (Brush Box)	Jubilee Park	2.8
16	<i>Jacaranda mimosifolia</i> (Jacaranda)		2.8
17	<i>Cinnamoumum camphora</i> (Camphor Laurel)		4.1
18	<i>Ficus rubiginosa</i> (Port Jackson Fig)		3.4
19	<i>Ficus rubiginosa</i> (Port Jackson Fig)		3.9
20	<i>Lophostemon confertus</i> (Brush Box)		3.2
21	<i>Ficus rubiginosa</i> (Port Jackson Fig)		3.7
22	<i>Lophostemon confertus</i> (Brush Box)		2.6
23	<i>Cinnamoumum camphora</i> (Camphor Laurel)		3.9

- (b) Excavation must not occur within the SRZ. If excavation is proposed within this zone, the Council's Tree Management Officer must be contacted immediately and the excavation must be carried out in accordance with Council's direction.
- (c) Without prejudice to clause (a) above, any excavations within the SRZ must be undertaken using non-destructive methods (such as by hand or with an Airspade) to ensure no tree roots greater than 40mm diameter are damaged, pruned or removed
- (d) Footings shall be relocated / realigned if any tree root greater than 40mm in diameter is encounter during excavations. A minimum of 150mm clearance shall be provided between the tree root and footing.

- (e) All excavations located within the TPZ must be supervised by a qualified Consultant Arborist, who holds the Diploma in Horticulture (Arboriculture), Level 5 under the Australian Qualification Framework.
- (f) All root pruning must be undertaken by a qualified Arborist with a minimum AQF level 3.

(47) SITE SUPERVISION AND REPORTING

- (a) An Arborist with minimum qualifications in Arboriculture of Level 5 (under the Australian Qualification Framework) must oversee various stages of work within the Tree Protection Zone of any tree listed for retention. The Arborist must certify compliance with each key milestone as detailed below:
 - (i) Installation of tree protection measures;
 - (ii) During demolition of any ground surface materials (paving, concrete, grass etc) within the Tree Protection Zone (TPZ) of any tree to be retained;
 - (iii) During any excavation which has been approved by Council within the TPZ of any tree to be retained;
 - (iv) During any Landscape works within the TPZ of any tree to be retained
- (b) An Arboricultural Compliance Report which includes photographic evidence and details of the health and condition of trees, must be submitted to Council's Area Planning Manager at each hold-point listed below
 - (i) Certification tree protection measures have been installed in accordance with the conditions prior to the commencement of works'
 - (ii) (Certification of compliance with each key milestone listed above within 48 hours of completion;
 - (iii) Details of any other works undertaken on any tree to be retained or within TPZ/s;
 - (iv) A final compliance report shall be submitted prior to the issuing of the Occupation Certificate.

(48) TREE PRUNING SPECIFICATIONS

- (a) Prior to approval of the Construction Certificate an updated "Pruning Specification Report" prepared by a qualified Arborist (minimum AQF Level 5) must be submitted and referred to Tree Management for approval. The report must include:
 - (i) Number of branches and orientation, branch diameter, percentage of canopy to be pruned/removed.
 - (ii) Photos with individual branches which are recommended for pruning/removal to be clearly marked. (Please note reports which include photos with a single vertical line as the area recommended for pruning will not be accepted).

- (iii) A maximum of 5% canopy removal and maximum of 100mm diameter branches will be permitted by Council.
 - (iv) Pruning work must be specified in accordance with Australian Standard 4373–2007, Pruning of Amenity Trees.
 - (v) Tree removal must not be recommended in this report.
- (b) All approved tree pruning works must be carried out by a qualified Arborist, with a minimum Level 3 AQF in arboriculture and in accordance with WorkCover's Code of Practice – Amenity Tree Industry.
 - (c) Any pruning works carried out under this consent must not result in the death of the tree, the creation of a hazard or in excessive or inappropriate amounts of pruning, which result in the overall shape of the tree becoming unbalanced and/or unstable.
 - (d) This consent does not authorise the applicant, or the contractor engaged to do the tree works to enter a neighbouring property.
 - (e) The consent from Council's Tree Management Officer must be obtained prior to the undertaking of any additional tree pruning works or pruning of any tree roots greater than 40mm in diameter

(49) STREET TREE PROTECTION

All street trees located directly outside the site must be retained and protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites. All street trees must be protected during the construction works as follows:

- (a) Tree trunk and major limb protection must be undertaken prior to the commencement of any works (including demolition). The protection must be installed and certified by a qualified Arborist (AQR Level 3) and must include:
 - (i) An adequate clearance, minimum 250mm, must be provided between the structure and tree branches, limbs and truck at all times;
 - (ii) Tree trunk/s and/or major branches, must be protected by wrapped hessian or similar material to limit damage, and
 - (iii) Timber planks (50mm x 100mm or similar) must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals and must be fixed against the trunk with tie wire, or strapping. The hessian and timber planks must not be fixed to the tree in any instance, or in any fashion,
 - (iv) Tree trunk and major branch protection is to remain in place for the duration of construction and development works and must be removed at the completion of the project.
- (b) All hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree pits. Supporting columns must not be placed on any tree roots that are exposed.

- (c) Young street trees must be protected by installing three (3) wooden stakes around the edge of the tree pits or a minimum of 1 metre from the base of the trunk. Hessian must be wrapped around the stakes. If existing stakes or a metal tree guard are already in place, these suffice as tree protection.
- (d) Materials or goods, including site sheds, must not be stored or placed:
 - (i) around or under the tree canopy; or
 - (ii) within two (2) metres of tree trunks or branches of any street trees.
- (e) Any excavation within any area known to or suspected of having tree roots greater than 30mm diameter must be undertaken by hand;
- (f) Any trenching works for services, hydraulics, drainage etc. must not be undertaken within two metres of the trunk of any street tree. Alternate installation methods for services such as directional boring/drilling or redirection of services must be employed where large roots greater than 30mm diameter are encountered during installation of any services;
- (g) Existing sections of kerbs adjacent to any street tree must not be removed without approval from the Council's Tree Management Officer;
- (h) Any damage sustained to street tree/s as a result of the erection of any construction activities (including demolition) must be immediately reported to the Council's Tree Management Officer on 9265 9333. Any damage to street trees as a result of any construction activities may result in prosecution under the Local Government Act 1993 and the Environmental Planning and Assessment Act 1979.

(50) STORMWATER AND DRAINAGE – MAJOR DEVELOPMENT

- (a) Any trenching works for services / hydraulics / drainage etc must not be undertaken within a Tree Protection Zone (TPZ) and be referred to the Site Arborist with regard to tree protection, prior to commencement of any works.
- (b) Alternative installation methods for services, such as directional boring/drilling, or redirection of services shall be employed where large woody roots greater than 40mm diameter are encountered during the installation of any services adjacent to the specified TPZ.

(51) ADVANCE TREE PLANTING

Tree planting within the property must be undertaken in accordance with the following conditions, and to Council's satisfaction, prior to the issuing any Occupation Certificate.

- (a) Three (3) trees are to be planted within the site at the completion of all construction works.
- (c) One (1) of the tree species, when mature, must attain a minimum height of no less than 10 metres and minimum canopy spread of six metres. Palms, fruit trees and species recognised to have a short life span are not considered a suitable replacement.

- (d) The tree(s) must be grown in accordance with the Australian Standard 2303 'Trees stock for landscape use'.
- (e) At the time of planting, the container size of the tree intended to grow to 10m in height is to be a minimum of 100 litres and a minimum height of two metres.
- (f) The trees must be planted in natural ground with adequate soil volume to allow healthy tree maturity to be achieved. Planter boxes will not be accepted for tree planting.
- (g) The tree(s) must be appropriately located away from existing buildings and structures to allow healthy tree maturity to be achieved without restrictions.
- (h) The tree(s) must be planted by a qualified Horticulturalist or Arborist of Level 3 under the Australian Qualifications Framework (AQF).
- (i) The replacement planting/s must be planted in such a manner as to promote good health during the establishment period, and must be maintained, as far as practicable to ensure tree growth into maturity.
- (i) Written confirmation is to be obtained from Council's Area Planning Manager that all tree planting/s have been completed to Council's satisfaction (excluding tree maintenance) prior to the issue of an Occupation Certificate.
- (j) Any newly planted tree that fails to establish within 2 years of the initial planting date must be replaced with a tree of comparable qualities.

SCHEDULE 1C

DURING CONSTRUCTION/PRIOR TO OCCUPATION/COMPLETION

(52) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

(53) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a permit being issued by Council under Section 68 of the Local Government Act 1993 and/or Section 138 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Unit, prior to works proceeding

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

(54) BASIX

All commitments listed in each relevant BASIX Certificate for the development must be fulfilled prior to any Occupation Certificate being issued.

(55) ENCROACHMENTS – NEIGHBOURING PROPERTIES

No portion of the proposed structure shall encroach onto the adjoining properties.

(56) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

(57) SURVEY

All footings, walls and floor slabs adjacent to a boundary must be set out by a registered surveyor. On commencement of brickwork or wall construction a survey and report, prepared by a Registered Surveyor, must be submitted to the Principal Certifier indicating the position of external walls in relation to the boundaries of the allotment. Any encroachments by the subject building over adjoining boundaries or roads must be removed prior to continuation of building construction work.

(58) SURVEY CERTIFICATE AT COMPLETION

A Survey Certificate prepared by a Registered Surveyor must be submitted to the Principal Certifier at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

(59) COVERING OF LOADS

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

(60) HAZARDOUS AND INDUSTRIAL WASTE

Hazardous and/or industrial waste arising from the demolition/operational activities must be removed and/or transported in accordance with the requirements of the NSW Work Cover Authority pursuant to the provisions of the following:

- (a) *Protection of the Environment Operations Act 1997*
- (b) *Protection of the Environment Operations (Waste) Regulation 2005*
- (c) *Waste Avoidance and Resource Recovery Act 2001*
- (d) *Work Health and Safety Act 2011*
- (e) *Work Health and Safety Regulation 2017.*

(61) LOADING AND UNLOADING DURING CONSTRUCTION

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site, where possible.
- (b) If, it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.
- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for

a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.

- (d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate application under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993 must be submitted to and approved by Council.

(62) NO OBSTRUCTION OF PUBLIC WAY

Unless otherwise approved by Council, the public way must not be obstructed by any materials, vehicles, waste receptacles, skip-bins or the like. Non-compliance with this requirement may result in the issue of a notice by Council to stop all work on the site.

SCHEDULE 2

PRESCRIBED CONDITIONS

The prescribed conditions in accordance with Division 8A of the *Environmental Planning and Assessment Regulation 2000* apply:

- Clause 98 Compliance with *Building Code of Australia* and insurance requirements under the *Home Building Act 1989*
- Clause 98A Erection of signs
- Clause 98B Notification of *Home Building Act 1989* requirements
- Clause 98C Conditions relating to entertainment venues
- Clause 98D Conditions relating to maximum capacity signage
- Clause 98E Conditions relating to shoring and adequacy of adjoining property

Refer to the NSW State legislation for full text of the clauses under Division 8A of the *Environmental Planning and Assessment Regulation 2000*. This can be accessed at: <http://www.legislation.nsw.gov.au>