

Attachment A

Recommended Conditions of Consent
--

SCHEDULE 1

CONDITIONS OF CONSENT

PART A - GENERAL

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2022/253 dated 23 March 2022 and the draft Plan of First Title Creation labelled 'Plan of Part of Chapman Road for Title Issue & Road Closing Under The Roads Act 1993', prepared by Michael Alexander Brown and dated 21 January 2021 (Ref 79397);

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the plans will prevail.

Reason

To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

(2) WASTE AND RECYCLING MANAGEMENT - GENERAL

The proposal must comply with the relevant provisions of Council's *Guidelines for Waste Management in New Developments 2018* which requires facilities to promote the efficient storage, separation, collection and handling of waste to maximise resources recovery.

Reason

To ensure that waste and recycling is appropriately managed.

(3) TREES APPROVED FOR REMOVAL

- (a) Trees numbered 25, 26, 27, 28 and 29 in the Arboricultural Impact Assessment prepared by Tree iQ dated January 2022 are approved for removal as part of the remediation works.
- (b) All tree removal works must be carried out by a qualified Arborist, with a minimum Level 3 AQF in arboriculture and in accordance with WorkCover's Code of Practice – Amenity Tree Industry.

Reason

To ensure the correct trees are removed safely.

(4) TREES THAT MUST BE RETAINED / PROTECTED

Trees numbered 1 to 24 and 30 in the Arboricultural Impact Assessment prepared by Tree iQ dated January 2022 must be retained and protected in accordance with the conditions of consent throughout the remediation works.

Reason

To ensure surrounding trees are protected.

(5) TREE PROTECTION SPECIFICATION AND TREE PROTECTION PLANS

(a) A Tree Protection Specification and Tree Protection Plan prepared by a qualified Arborist with a minimum Australian Qualification Framework (AQF) of Level 5 in Arboriculture and written in accordance with the Australian Standard 4970-2009 Protection of Trees on Development Sites must be submitted to and approved by Council's Area Planning Manager prior to any works commencing on-site which details the following:

- (i) The Arborist must be appointed through the City's Tree Management Team.
- (ii) The specification shall include a detailed list of all trees listed for retention as detailed in these conditions.
- (iii) A plan showing trees numbers, locations, Tree Protection Zone/s and Structural Root Zone/s in accordance with AS4970-2009.
- (iv) Details of tree sensitive methods required during installation of new paving, installation of new retaining walls and site remediation works located within the TPZ of any tree to be retained.
- (v) Details of the tree protection measures in accordance with AS4970-2009
- (vi) Information on the Project Arborist's involvement during the works including hold points to be outlined in the report.

Reason

To ensure the surrounding trees are protected.

(6) COMPLIANCE WITH ARBORICULTURAL IMPACT ASSESSMENT

All recommendations, Tree Protection, and Methodology Statements contained in the approved Tree Protection Specification and Tree Protection Plan must be implemented during the remediation works.

Reason

To ensure surrounding trees are protected.

(7) TREE PLANTING

Certain tree species placed in close proximity to Sydney Water's underground assets have the potential to inflict damage through invasive root penetration and

soil destabilisation. Sydney Water requires that all proposed or removed trees and vegetation included within the proposal adhere to the specifications and requirements within Section 46 of the Sydney Water Act (1994) and *Diagram 5 – Planting Trees* within our [Technical guidelines – Building over and adjacent to pipe assets](#). Please note these guidelines include more examples of potential activities impacting our assets which may also apply to your development.

If any tree planting proposed breaches our policy, Sydney Water may need to issue an order to remove every tree breaching the act, or directly remove every tree breaching the Act and bill the developer or Council for their removal.

Reason

To ensure Sydney Water assets are protected.

(8) TFNSW - GENERAL

The applicant must comply with all Altrac Light Rail Partnership (Altrac) or any subsequent operator of Sydney Light Rail (Sydney Light Rail Operator) policies, rules and procedures when working in and about the Sydney Light Rail corridor; and

The applicant shall provide safe and unimpeded access for Sydney Light Rail patrons traversing to and from the Sydney Light Rail stops at all times.

Reason

To ensure the protection of TfNSW infrastructure.

(9) AUSGRID

The design submission must comply with relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice for construction works near existing electrical assets. The “as constructed” minimum clearances to Ausgrid’s infrastructure must not be encroached by the building development. It also remains the responsibility of the developer and relevant contractors to verify and maintain these clearances onsite. Ausgrid’s Network Standards can be sourced from Ausgrid’s website, www.ausgrid.com.au

Reason

To ensure the protection of Ausgrid infrastructure.

(10) LAND SUBDIVISION – SUBDIVISION CERTIFICATE

A separate application must be made to Council to obtain the approval of the plan of subdivision and issue of a Subdivision Certificate under Section 6.15 of the *Environmental Planning and Assessment Act 1979*.

Reason

To ensure separate development consent is sought for the plan of subdivision and issue of a Subdivision Certificate.

PART B – BEFORE THE ISSUE OF A CONSTRUCTION CERTIFICATE

(11) CONSTRUCTION TRAFFIC MANAGEMENT PLAN

- (a) A Construction Traffic Management Plan must be submitted to and approved by Council prior to any remediation works commencing.
- (b) The approved plan must be complied with during any demolition and remediation work.

Reason

To ensure that the impacts of construction traffic is appropriately managed.

(12) ENVIRONMENTAL MANAGEMENT PLAN

Prior to any works commencing, an Environmental Management Plan (EMP) must be prepared for the site and submitted to Council's Area Planning Coordinator | Area Planning Manager for written approval.

The EMP must consider all potential environmental impacts from the approved works including but not limited to:

- (a) sedimentation control, contamination containment, stockpiles, noise and vibration, odours and dust emissions, particularly in relation to other properties in close proximity (such as the child care centre);
- (b) Any SafeWork NSW requirements; and
- (c) Procedures to be adopted for the prevention of loose or contaminated material, spoil, dust and litter from being deposited onto the public way from trucks and associated equipment and the proposed method of cleaning surrounding roadways from such deposits.

All works must be undertaken onsite in accordance with the approved Construction Environmental Management Plan.

Reason

To ensure that contamination is appropriately managed.

(13) SITE SUPERVISION AND REPORTING

- (a) An Arborist with minimum qualifications in Arboriculture of Level 5 (under the Australian Qualification Framework) must oversee various stages of work within the Tree Protection Zone of any tree listed for retention. The Arborist must certify compliance with each key milestone as detailed below:
 - (i) Installation of tree protection measures;
 - (ii) During demolition of any ground surface materials (paving, concrete, grass etc) within the Tree Protection Zone (TPZ) of any tree to be retained;

- (iii) During any excavation and trenching which has been approved by Council within the TPZ of any tree to be retained;
 - (iv) During all hold points included in the approved Tree Protection Specification and Tree Protection Plan
 - (v) During any Landscape works within the TPZ of any tree to be retained.
- (b) An Arboricultural Compliance Report which includes photographic evidence and details of the health and condition of trees, must be submitted to Council's Area Planning Manager at each hold-point listed below:
- (i) Certification tree protection measures have been installed in accordance with the conditions prior to the commencement of works.
 - (ii) Certification of compliance with each key milestone listed above within 72 hours of completion.
 - (iii) Monthly reporting for the duration of construction and development within the site.
 - (iv) Details of any other works undertaken on any tree to be retained or within TPZ/s;
 - (v) A final compliance report shall be submitted at the completion of remediation works and prior to the commencement of works relating to the sports field.

Reason

To ensure the protection of trees to be retained in close proximity to the works.

(14) SURVEY INFRASTRUCTURE – IDENTIFICATION AND RECOVERY

Under Section 24 of the Surveying and Spatial Information Act 2002, it is an offence to remove, damage, destroy, displace, obliterate, or deface any survey mark unless authorised to do so by the Surveyor-General. Accordingly, the applicant must, where possible, ensure the preservation of existing survey infrastructure undisturbed and in its original state or else provide evidence of the Surveyor-General's authorisation to remove or replace marks.

Prior to any remediation works being carried out, documentary evidence must be prepared by a Registered Surveyor and submitted to and approved by the City of Sydney's Survey team. This evidence must include either:

- (a) A copy of any Surveyor-General's Approval for Survey Mark Removal granted by NSW Spatial Services for the subject site, including all documentation submitted as part of that application (for example the survey mark audit schedule, strategy plan and strategy report) or,
- (b) A letter, signed by a current NSW Registered Land Surveyor and including his or her Board of Surveying and Spatial Information (BOSSI) identification number, stating that all investigations required under Surveyor-General's Direction No.11 have been made for the subject site and that no survey infrastructure will be affected by the proposal.

The City's Principal Surveyor may request further information and/or add conditions to any Surveyor-General's Approval at their discretion.

Reason

To ensure the preservation of existing survey infrastructure.

(15) BUILDING PLAN APPROVAL

The approved plans must be submitted to the Sydney Water Tap in™ online service to determine whether the development will affect any Sydney Water sewer or water main, stormwater drains and/or easement, and if further requirements need to be met.

The Tap in™ service provides 24/7 access to a range of services, including:

- (a) building plan approvals
- (b) connection and disconnection approvals
- (c) diagrams
- (d) trade waste approvals
- (e) pressure information
- (f) water meter installations
- (g) pressure boosting and pump approvals
- (h) changes to an existing service or asset, e.g. relocating or moving an asset.

Sydney Water's Tap in™ online service is available at: <https://www.sydneywater.com.au/SW/plumbing-building-developing/building/sydney-water-tap-in/index.htm>

Sydney Water recommends developers apply for Building Plan approval early as in some instances the initial assessment will identify that an Out of Scope Building Plan Approval will be required.

Reason

To ensure the protection Sydney Water assets.

(16) OUT OF SCOPE BUILDING PLAN APPROVAL

Sydney Water will need to undertake a detailed review of building plans:

- (a) That affect or are likely to affect any of the following:
 - (i) Wastewater pipes larger than 300mm in size
 - (ii) Pressure wastewater pipes
 - (iii) Drinking water or recycled water pipes

- (iv) Our property boundary
 - (v) An easement in our favour
 - (vi) Stormwater infrastructure within 10m of the property boundary.
- (b) Where the building plan includes:
- (i) Construction of a retaining wall over, or within the zone of influence of our assets
 - (ii) Excavation of a basement or building over, or adjacent to, one of our assets
 - (iii) Dewatering – removing water from solid material or soil.
- (c) The detailed review is to ensure that:
- (i) our assets will not be damaged during, or because of the construction of the development
 - (ii) we can access our assets for operation and maintenance
 - (iii) your building will be protected if we need to work on our assets in the future.

The developer will be required to pay Sydney Water for the costs associated with the detailed review.

Reason

To ensure the protection of Sydney Water assets.

(17) TfNSW PRE-CONSTRUCTION WORK DILAPIDATION REPORT

If required by TfNSW, a pre-construction work Dilapidation Report of the Sydney Light Rail and its assets shall be prepared by a qualified structural engineer. The dilapidation survey shall be undertaken via a joint site inspection by the representatives of the Sydney Light Rail Operator, TfNSW and the applicant. These dilapidation surveys will establish the extent of existing damage and enable any deterioration during construction to be observed.

Reason

To ensure the protection of TfNSW infrastructure.

PART C – BEFORE THE COMMENCEMENT OF WORK

(18) EROSION AND SEDIMENT CONTROL - BETWEEN 250 AND 2,500SQM

Prior to the commencement of any demolition/remediation/excavation work, an Erosion and Sediment Control Plan (ESCP) must be submitted to and be approved by the Principal Certifier. The ESCP must:

- (a) Conform to the specifications and standards contained in *Managing Urban Stormwater: Soils and Construction* (Landcom, 2004); the *Guidelines for Erosion and Sediment Control on Building Sites* (City of Sydney, 2004); and the *NSW Protection of the Environment Operations Act 1997*.
- (b) Include a drawing(s) that clearly shows:
 - (i) location of site boundaries and adjoining roads
 - (ii) approximate grades and indications of direction(s) of fall
 - (iii) approximate location of trees and other vegetation, showing items for removal or retention
 - (iv) location of site access, proposed roads and other impervious areas
 - (v) existing and proposed drainage patterns with stormwater discharge points
 - (vi) north point and scale
- (c) Specify how soil conservation measures will be conducted on site including:
 - (i) timing of works
 - (ii) locations of lands where a protective ground cover will, as far as is practicable, be maintained
 - (iii) access protection measures
 - (iv) nature and extent of earthworks, including the amount of any cut and fill
 - (v) where applicable, the diversion of runoff from upslope lands around the disturbed areas
 - (vi) location of all soil and other material stockpiles including topsoil storage, protection and reuse methodology
 - (vii) procedures by which stormwater is to be collected and treated prior to discharge including details of any proposed pollution control device(s)
 - (viii) frequency and nature of any maintenance program
 - (ix) other site-specific soil or water conservation structures.

Reason

To ensure that appropriate erosion and sediment control measures are put in place during construction to protect the environment.

(19) OTHER APPROVALS

Any activity which is proposed to be undertaken in, on or above a road reserve or the public domain (including a public footway) must have separate approval(s) obtainable through the lodgement of an application under Section 68 of the Local Government Act 1993 and/or Section 138/139 of the Roads Act 1993 prior to the commencement of work/activities within the road reserve/public domain. Such activities include but not limited to:

- (a) installation of construction-related temporary structures including hoardings/scaffolding;
- (b) installation and/or alterations to advertising/business signs;
- (c) installation and/or alterations to street awnings;
- (d) crane operation and other hoisting activities;
- (e) temporary works (e.g. barricading, road openings, mobile hoisting devices);
- (f) works zones (for loading and unloading from the roadway); and
- (g) temporary ground anchoring and shoring to support a roadway when excavating; and
- (h) any other structure or encroachment including facade elements/architectural features.

Reason

To ensure use of a public place is managed appropriately.

PART D – WHILE WORK IS BEING CARRIED OUT

(20) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on-site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Team, prior to works proceeding

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

Reason

To protect the amenity of the surrounding area.

(21) ASBESTOS REMOVAL WORKS

- (a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence must be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of

the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.

- (c) All work must be carried out in accordance with the *Work Health and Safety Regulation 2017* and the NSW Government and SafeWork NSW document entitled *How to manage and control asbestos in the work place: Code of Practice (Safework NSW) December 2011* and the *City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines*.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.
- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 -1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.
- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).
- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.
- (i) A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

Reason

To ensure that the handling and removal of asbestos from the site is appropriately managed.

(22) SITE NOTICE OF PROJECTS DETAILS AND APPROVALS

A site notice is to be prominently displayed at the boundary to each frontage of the site for the purposes of informing the public of appropriate project details and relevant approvals. The notice(s) is to satisfy all of the following requirements:

- (a) Minimum dimensions of the notice are to measure 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size;
- (b) The notice is to be durable and weatherproof and is to be displayed throughout the construction period;
- (c) A copy of the first page of the development approval, building approval (including any modifications to those approvals) and any civic works approvals is to be posted alongside the notice in weatherproof casing;
- (d) The approved hours of work, the Principal Certifier including contact address and certification details, the name of the site manager, the responsible managing company, its address and 24 hour contact phone number for any enquiries, including construction/noise complaint, and the estimated date of completion of the project are to be displayed on the site notice;
- (e) The notice(s) is to be mounted at eye level on the perimeter hoardings and is also to state that unauthorised entry to the site is not permitted.
- (f) All notices and signs must be displayed in locations as specified in the City's Guidelines for Hoardings and Scaffolding.

Reason

(Prescribed condition EP&A Regulation, clauses 98A (2) and (3)).

(23) CLASSIFICATION OF WASTE

Prior to the exportation of waste (including fill or soil) from the site, the waste materials must be classified in accordance with the provisions of the Protection of the *Environment Operations Act 1997* and the *NSW DECC Waste Classification Guidelines, Part1: Classifying Waste (July 2009)*. The classification of the material is essential to determine where the waste may be legally taken. The *Protection of the Environment Operations Act 1997* provides for the commission of an offence for both the waste owner and the transporters if the waste is taken to a place that cannot lawfully be used as a waste facility for the particular class of waste. For the transport and disposal of industrial, hazardous or Group A liquid waste advice should be sought from the EPA.

Reason

To ensure that waste from site is classified and disposed of appropriately.

(24) DISCHARGE OF CONTAMINATED GROUNDWATER

Contaminated groundwater must not be discharged into the City's stormwater drainage system.

Options for the disposal of groundwater include disposal to sewer with prior approval from Sydney Water or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

Reason

To ensure that the discharge of ground water is appropriately managed.

(25) IMPORTED FILL MATERIALS

All fill imported onto the site must be validated to ensure the imported fill is suitable for the proposed land use from a contamination perspective. Fill imported on to the site shall also be compatible with the existing soil characteristic for site drainage purposes.

The City may require details of appropriate validation of imported fill material to be submitted with any application for future development of the site. Hence all fill imported onto the site should be validated by either one or both of the following methods during remediation works:

- (a) Imported fill must be accompanied by documentation from the supplier which certifies that the material is not contaminated based upon analyses of the material for the known past history of the site where the material is obtained; and/or
- (b) Sampling and analysis of the fill material shall be conducted in accordance with NSW EPA (1995) Sampling Design Guidelines.

Reason

To ensure that imported fill is not contaminated.

(26) LAND REMEDIATION (Where Site Auditor engaged)

The site is to be remediated and validated in accordance with the Remedial Action Plan prepared by Geosyntec Consultants dated 15 March 2022, reference number 20252 R03 and the Section B Site Audit Statement prepared by NSW Environment Protection Authority accredited Site Auditor Dr Julie Evans (Envirocene Pty Ltd) dated 22 March 2022 and reference (audit number) JE087-A. All remediation work carried out shall be conducted in accordance with the guidelines in force from time to time under the *Contaminated Land Management Act 1997*.

Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination must be immediately notified to the Council's Area Planning Manager, the Site Auditor and the Principal Certifier.

Any variations to the approved Remediation Action Plan must be approved in writing by the Site Auditor and Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the commencement of such work.

Reason

To ensure that the site is appropriately remediated.

(27) NOTIFICATION – NEW CONTAMINATION EVIDENCE

Council's Area Planning Manager and the Principal Certifier must be notified of any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination.

Reason

To ensure that the site is appropriately remediated.

(28) STOCKPILES

- (a) No stockpiles of soil or other materials must be placed on footpaths or nature strips unless prior approval has been obtained from the City's Construction Regulation Team.
- (b) All stockpiles of soil or other materials must be placed away from drainage lines, gutters or stormwater pits or inlets.
- (c) All stockpiles of soil or other materials likely to generate dust or odours must be covered.
- (d) All stockpiles of contaminated soil must be stored in a secure area and be covered if remaining more than 24 hours.

Reason

To ensure that stockpiles of soil or other materials are appropriately managed.

(29) COVERING OF LOADS

All vehicles involved in the remediation process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

Reason

To ensure loads are managed appropriately and do not impact local amenity.

(30) EROSION AND SEDIMENT CONTROL

The Soil and Water Management Plan (SWMP) or Erosion and Sediment Control Plan (ESCP) which has been approved by the Principal Certifier must be implemented in full during the construction period.

During the construction period:-

- (a) erosion and sediment controls must be regularly inspected, repaired and maintained in working order sufficient for a 10 year Average Recurrence Interval (ARI) rainfall event;
- (b) erosion and sediment control signage available from Council must be completed and attached to the most prominent structure visible at all times when entering the site for the duration of construction; and

- (c) building operations and stockpiles must not be located on the public footway or any other locations which could lead to the discharge of materials into the stormwater system.

Reason

To ensure no substance other than rainwater enters the stormwater system and waterways.

(31) HAZARDOUS AND INDUSTRIAL WASTE

Hazardous and/or industrial waste arising from the demolition/operational activities must be removed and/or transported in accordance with the requirements of the NSW Work Cover Authority pursuant to the provisions of the following:

- (a) *Protection of the Environment Operations Act 1997*
- (b) *Protection of the Environment Operations (Waste) Regulation 2005*
- (c) *Waste Avoidance and Resource Recovery Act 2001*
- (d) *Work Health and Safety Act 2011*
- (e) *Work Health and Safety Regulation 2017.*

Reason

To ensure hazardous/ industrial waste is managed appropriately.

(32) VEHICLE CLEANSING

Prior to the commencement of work, suitable measures are to be implemented to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site. It is an offence to allow, permit or cause materials to pollute or be placed in a position from which they may pollute waters.

Reason

To ensure sediment is not tracked onto the roadway.

(33) NO OBSTRUCTION OF PUBLIC WAY

Unless otherwise approved by Council, the public way must not be obstructed by any materials, vehicles, waste receptacles, skip-bins or the like. Non-compliance with this requirement may result in the issue of a notice by Council to stop all work on the site.

Reason

To protect the amenity of the public domain.

(34) DRAINAGE AND SERVICE PIT LIDS

All existing or proposed drainage and service pit lids throughout the public domain must be to City of Sydney specifications and heel/bicycle safe, slip resistant, infill with material to match surrounding surface, finished flush with the adjacent pavement to avoid trip hazards and be clear of obstructions for easy opening and cleaning.

Reason

To ensure drainage and service pit lids within the public domain are appropriately designed and installed.

(35) HOLD POINTS

Hold Points for all public domain work including civil, drainage and subsurface works will be in accordance with the City of Sydney's Public Domain Manual and Sydney Streets Technical Specification. These Hold Points must be adhered to during construction.

Reason

To ensure hold points are adhered to during construction works.

(36) SECTION 73 COMPLIANCE CERTIFICATE - SUBDIVISION

Prior to the issue of a Subdivision/Strata Certificate, a Section 73 Compliance Certificate under the *Sydney Water Act 1994* must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Coordinator. Please refer to the Building Developing and Plumbing section on the web site www.sydneywater.com.au then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of any water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Coordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

The Section 73 Certificate must be submitted to Council prior to a Subdivision Certificate being issued. It should be noted that a Section 73 certificate is not required for the second stage of the subdivision as it will involve dedication of a road & public reserve only.

Reason

To ensure Sydney Water directions are complied with.

(37) TFNSW - DURING CONSTRUCTION

- (a) No metal ladders, tapes and plant/machinery, or conductive material are to be used within 6 horizontal metres of any live electrical equipment unless a physical barrier such as a hoarding or structure provides separation; and

- (b) During all stages of the development extreme care shall be taken to prevent any form of pollution entering the light rail corridor. Any form of pollution that arises as a consequence of the development activities shall remain the full responsibility of the applicant.

Reason

To ensure the protection of TfNSW infrastructure.

PART E – BEFORE THE ISSUE OF AN OCCUPATION CERTIFICATE

(38) SITE AUDIT STATEMENT

Prior to the commencement of any work associated with the sports field or the issue of a subdivision certificate for Chapman Road, whichever occurs first, a Section A Site Audit Statement must be obtained from a NSW Environment Protection Authority accredited Site Auditor and submitted to and approved by, the Council's Area Planning Manager at email address:-

hbapplications@cityofsydney.nsw.gov.au

The Site Audit Statement must confirm that the site has been remediated in accordance with the approved Remedial Action Plan and clearly state that site is suitable for the proposed use.

- (a) In circumstances where the Site Audit Statement is subject to conditions that require ongoing review by the Auditor or Council, these must be reviewed and must be approved by the Council's Health and Building Unit in writing through the Area Planning Manager before the Site Audit Statement is issued.
- (b) In circumstances where the Site Audit Statement conditions (if applicable) are not consistent with the consent, the development must not proceed until the inconsistency has been resolved to the satisfaction of Council (such as via a S4.55 modification of the consent pursuant to the provisions of the *Environmental Planning & Assessment Act 1979*).
- (c) **No Occupation Certificate is to be issued** by the Principal Certifier for the sports field unless a Site Audit Statement has been submitted to and approved by Council in accordance with this condition.

Reason

To ensure that the site is appropriately remediated.

(39) SITE AUDIT STATEMENT – ENVIRONMENTAL MANAGEMENT PLAN

Where the ongoing land use suitability and release of the Final (Section A) Site Audit Statement is dependent upon the implementation of an Environmental Management Plan (EMP) in relation to any residual contamination remaining onsite, the EMP must be approved by the Site Auditor and Council's Area Planning Manager prior to the issue of the final Site Audit Statement.

The owner of the land is required to comply with the ongoing obligations of any EMP which form part of the final Site Audit Statement for the site.

A covenant must be registered on the title of the land binding the owners and future owners to be responsible for ongoing maintenance and any future rehabilitation works required in terms of the encapsulated/remaining contaminated materials, including the discharge or prevention of discharge from any contaminants or for any works subsequently required by the NSW Environment Protection Authority

A copy of the revised certificate of land title recording the covenant must be submitted to Council's Area Planning Manager and the Principal Certifier prior to the issue of any Occupation Certificate relating to the sports field.

Reason

To ensure that contamination is appropriately managed.

(40) SURVEY INFRASTRUCTURE – PRE-SUBDIVISION CERTIFICATE WORKS

- (a) Pursuant to Section 38 of the Surveying and Spatial Information Act 2002, if it is likely that any new survey mark will be disturbed by associated works (for example, footpath or kerb and gutter construction), a surveyor may defer the placement of those marks.
- (b) Prior to any the issue of any Subdivision Certificate, documentary evidence in accordance with Section B11 – *Survey Infrastructure of the Technical Specification* must be prepared by a Registered Surveyor and submitted to and approved by the City. This evidence must include:
 - (i) A copy of any Surveyor-General's Approval for Deferment of Survey Marks granted by NSW Spatial Services for the subject site, including all documentation submitted as part of that application (for example the draft deposited plan) or
 - (ii) A certificate of Practical Completion obtained from the City's Public Domain team, together with a letter, signed by a current NSW Registered Land Surveyor and including his or her Board of Surveying and Spatial Information (BOSSI) identification number, stating that all survey marks shown on their Deposited Plan remain at the date of practical completion.

Reason

To allow for deferment of survey marks.

(41) TfNSW - POST - CONSTRUCTION DILAPIDATION REPORT

Prior to the issue of the Occupation Certificate, if required by TfNSW, a post-construction dilapidation survey shall be undertaken via a joint inspection with representatives from TfNSW, Altrac, the Sydney Light Rail Operator and the applicant. The dilapidation survey will be undertaken on the rail infrastructure and property in the vicinity of the project. These dilapidation surveys will establish the extent of any existing damage and enable any deterioration during construction to be observed. The submission of a detailed dilapidation report to TfNSW and the Sydney Light Rail Operator will be required unless otherwise notified by TfNSW. The applicant needs to undertake rectification of any damage to the satisfaction of TfNSW and the Sydney Light Rail Operator and if applicable the local council.

Reason

To protect TfNSW infrastructure.

PART F – OCCUPATION AND ONGOING USE

There are no conditions relevant to Part F.

SCHEDULE 2

PRESCRIBED CONDITIONS

The prescribed conditions in accordance with Division 8A of the *Environmental Planning and Assessment Regulation 2021* apply:

- Clause 69 Compliance with *Building Code of Australia* and insurance requirements under the *Home Building Act 1989*
- Clause 70 Erection of signs
- Clause 71 Notification of *Home Building Act 1989* requirements
- Clause 72 Conditions relating to entertainment venues
- Clause 73 Conditions relating to maximum capacity signage
- Clause 74 Conditions relating to shoring and adequacy of adjoining property

Refer to the NSW State legislation for full text of the clauses under Division 2 conditions of development consent of the *Environmental Planning and Assessment Regulation 2021*. This can be accessed at: <http://www.legislation.nsw.gov.au>