

Attachment A

Recommended Conditions of Consent

SCHEDULE 1
CONDITIONS OF CONSENT
PART A - GENERAL

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2022/792 dated 5 August 2022 and the following drawings prepared by SN Architects:

Drawing Number	Drawing Name	Date
DA1005 Rev C	Site Plan	17 November 2023
DA1102 Rev C	Ground Level	24 August 2023
DA1103 Rev C	Level 01	24 August 2023
DA1104 Rev D	Level 02	17 November 2023
DA2001 Rev D	Elevations_Sheet 1	17 November 2023
DA2002 Rev D	Elevations_Sheet 2	17 November 2023
DA2003 Rev B	Elevations_Sheet 3	23 June 2023
DA3001 Rev C	Section A	17 November 2023
DA7041 Rev B	Finishes Schedule	23 June 2023

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the plans will prevail.

Reason

To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

(2) UPDATED BASIX CERTIFICATE

- (a) An updated BASIX certificate must be submitted to the appointed Certifier prior to issue of a construction certificate.
- (b) A copy of the required completed BASIX certificate, must be lodged with an application for a construction certificate and the items nominated as part of the subject BASIX certificate must be specified on the plans submitted with the construction certificate application.

Reason

To ensure BASIX commitments are fulfilled in accordance with the BASIX certificate (prescribed condition under clause 75 EP&A Regulation, 2021).

(3) SECTION 7.11 CONTRIBUTIONS PAYABLE - CONTRIBUTION TOWARDS PUBLIC AMENITIES – CITY OF SYDNEY DEVELOPMENT CONTRIBUTIONS PLAN 2015 – SOUTH PRECINCT

Council has identified the development will increase demand for public amenities and facilities. Pursuant to Section 7.11 of the Environmental Planning and Assessment Act, 1979 (as amended), and the City of Sydney Development Contributions Plan 2015 the following monetary contributions are required towards the cost of public amenities.

<u>Contribution Category</u>	<u>Amount</u>
Open Space	\$12,875.00
Community Facilities	\$2,563.00
Traffic and Transport	\$3,269.00
Stormwater Drainage	\$1,293.00
Total	\$20,000.00

The City of Sydney will index the above contribution for inflation at the time of payment using the following formula.

$$C_{\text{payment}} = C_{\text{consent}} \times (CPI_{\text{payment}} \div CPI_{\text{consent}})$$

Where:

C_{payment} = Is the contribution at time of payment;

C_{consent} = Is the contribution at the time of consent, as shown above;

CPI_{payment} = Is the Consumer Price Index (All Groups Index) for Sydney published by the Australian Bureau of Statistics that applies at the time of payment; and

CPI_{consent} = Is the Consumer Price Index (All Groups Index) for Sydney at the date the contribution amount above was calculated being – 134 for the June 2023 quarter.

The contribution must be paid prior to the issue of any Construction Certificate in relation to this development.

Please contact Council's Planning Administration staff at planningsystemsadmin@cityofsydney.nsw.gov.au to request a letter confirming the indexed contribution amount payable.

Once the letter confirming the indexed contribution is obtained, payment may be made at any of the City's Neighbourhood Service Centres or the One Stop Shop at Town Hall House. Acceptable payment methods are EFTPOS (debit card only), cash (up to 10K only), Credit Card (up to 50K only) or a bank cheque made payable to the City of Sydney. Personal or company cheques will not be accepted.

Reason

To ensure development contributions are paid to address the increased demand for public amenities and services resulting from the approved development.

(4) SECONDARY DWELLINGS ANCILLARY TO PRINCIPAL DWELLING

The secondary dwelling is:

- (a) To be established in conjunction with the principal dwelling contained within the lot; and
- (b) To remain within the same lot as the principal dwelling.

Reason

To restrict the subdivision of the site.

(5) REDUCTION OF RISING DAMP AND SALT ATTACK IN BUILDINGS CONSTRUCTED PRIOR TO 1920

- (a) To avoid potential damage caused by rising damp and migrating salts the following is to apply to the ground floor.
 - (i) No concrete slab is to be laid directly on the ground within the primary dwelling;
 - (ii) Expansion strips should be used in conjunction with external walls; and
 - (iii) External slabs must be set down from internal levels to improve cross ventilation.
- (b) The existing suspended timber floor at ground floor level, and the ventilated subfloor space is to be retained or where retention is not possible, reconstructed.

Reason

To avoid potential damage caused by rising damp and migrating salts.

(6) TIMBER FRONT DORMERS

- (a) The front dormer must use timber joinery and double-hung windows and must be a rectangular, timber framed, vertically proportioned, double hung sash window with a ratio of 1.5:1 measured from base to top of the window frame.
- (b) The dormers must be symmetrically placed on the roof plane.
- (c) The total external width of the dormer including frames must not exceed 1200mm (exclusive of eave overhangs and gutters) and the eave and gable overhang must not exceed 100mm.

- (d) Glazing must not be used in the gable or sides of the dormer.
- (e) Roof materials must match the existing roof material and the roof pitch must be between 32 degrees and 45 degrees.
- (f) The external side walls of the dormer are to be of timber weatherboards of a profile and section consistent with the period and style of the building.
- (g) The external joinery must be detailed in a manner appropriate to the style and period of the building.
- (h) The architraves that cover the side walls and boxed window frames should not exceed 150mm in width.

Details of the dormer (at a scale of 1:20) and of the weatherboard profile must be submitted to and approved by Council's Area Coordinator Planning Assessments or Area Planning Manger prior to the issue of any Construction Certificate.

Reason

To ensure that the front dormer is of an appropriate design and does not have adverse heritage impacts.

(7) NO AIR CONDITIONING UNITS TO FACADE OR BALCONIES OF BUILDING

Approval is not granted for the installation of individual air conditioning units to the facade or balconies of the building.

Reason

To clarify the scope of the consent.

(8) TREES APPROVED FOR REMOVAL

- (a) All trees detailed in Table 1 below are approved for removal. Tree removal must not occur until the Construction Certificate has been issued.

Table 1 – Tree Removal:

Tree No	Species:	Location
1	Vitis vinifera	Southern boundary – within building footprint
4	Nerium oleander	Southern boundary – within building footprint

- (b) All tree removal works must be carried out by a qualified Arborist, with a minimum AQF Level 3 and in accordance with SafeWork's Code of Practice – Amenity Tree Industry.

Reason

To identify the trees that can be removed.

(9) TREES THAT MUST BE RETAINED

The existing trees detailed in Table 2 below be retained and protected in accordance with the conditions throughout construction and development.

Table 2 – Tree Retention:

Approval is NOT granted for the removal of the following trees, which Council has determined to be prominent landscape elements.

Tree No	Species:	Location
2	Howea forsteriana	Rear yard – refer to approved ground floor plan for tree numbers and locations
3	Jacaranda mimosifolia	
5	Howea forsteriana	
6	Eucalyptus nicholii	
7	Howea forsteriana	
8	Eucalyptus nicholii	

Reason

To identify the trees that cannot be removed, must be retained and protected.

(10) WASTE AND RECYCLING MANAGEMENT - GENERAL

The proposal must comply with the relevant provisions of Council's *Guidelines for Waste Management in New Developments 2018* which requires facilities to promote the efficient storage, separation, collection and handling of waste to maximise resources recovery.

Reason

To ensure that waste and recycling is appropriately managed.

PART B – BEFORE THE ISSUE OF A CONSTRUCTION CERTIFICATE

(11) CONSTRUCTION TRAFFIC MANAGEMENT PLAN

- (a) A Construction Traffic Management Plan must be submitted to and approved by Council's Area Planning Coordinator or Area Planning Manager prior to a Construction Certificate being issued.
- (b) The approved plan must be complied with during any demolition and/or construction work.

Reason

To ensure that the impacts of construction traffic is appropriately managed.

(12) CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN

Prior to the issue of a Construction Certificate a Construction Environmental Management Plan (CEMP) must be prepared by appropriately qualified person for the site and submitted to Council's Area Planning Coordinator or Area Planning Manager for written approval. The CEMP must consider all potential environmental impacts from the approved works including but not limited to sedimentation control, contamination containment, stockpiles, noise and vibration, odours and dust emissions.

All works must be undertaken onsite in accordance with the approved Construction Environmental Management Plan.

Reason

To ensure that construction is appropriately managed.

(13) SITE SUPERVISION AND REPORTING

- (a) An Arborist with minimum qualifications in Arboriculture of Level 5 (under the Australian Qualification Framework) must oversee various stages of work within the Tree Protection Zone of any tree listed for retention. The Arborist must certify compliance with each key milestone detailed below:
 - (i) The installation of tree protection measures prior to the commencement of any construction works;
 - (ii) During demolition of any ground surface materials (pavers, concrete, grass etc.) within the Tree Protection Zone (TPZ) of any tree to be retained;
 - (iii) During excavations for the main building extension within the TPZ of tree 3;
 - (iv) During construction of the concrete slab for the secondary dwelling within the TPZ of any tree listed for retention;
 - (v) During any excavation and trenching within the TPZ;

- (v) During any Landscape works within the TPZ which has been approved by Council.
- (b) An Arboricultural Compliance Report which includes photographic evidence and provides details on the health and structure of tree/s must be submitted to and acknowledged by Council's Area Planning Coordinator or Area Planning Manager at each hold point listed below:
 - (i) Certification that tree protection measures have been installed in accordance with these consent conditions;
 - (ii) Certification of compliance with each key milestone listed above within 48 hours of completion;
 - (iii) Monthly reporting for the duration of construction and development works within the site;
 - (iv) Details of any other works undertaken on any tree to be retained or any works within the TPZ which has been approved by Council.
- (c) A final compliance report must be submitted to and approved by Council's Area Planning Coordinator or Area Planning Manager prior to the issue of any Occupation Certificate.

Reason

To ensure the protection and ongoing health of trees on the site.

(14) WASTE AND RECYCLING MANAGEMENT - RESIDENTIAL

- (a) The Waste and Recycling Management Plan accompanying this Development Application has not been approved by this consent.
- (b) A Waste and Recycling Management Plan including demolition and construction waste and recycling details, is to be submitted to and approved by Council's Area Coordinator Planning Assessments or Area Planning Manager prior to a Construction Certificate being issued. The plan must comply with the Council's *Guidelines for Waste Management in New Developments 2018*.
- (c) The Waste and Recycling Management Plan must include:
 - (i) The path of travel between the bin storage areas/bulky waste storage areas and the designated waste/recycling collection point is to have a minimum 1,200mm wall-to-wall clearance, be slip-proof, of a hard surface, be free of obstructions and at no point have a gradient exceeding 1:14. The use of a lift is permitted, but consideration should be given to the inclusion of a service lift in this instance.
 - (ii) All nominated waste and recycling storage areas must be constructed to meet the relevant conditions required by Council's *Guidelines for Waste Management in New Developments 2018*.

UPON COMPLETION OF THE DEVELOPMENT

- (d) Prior to any Occupation Certificate being issued or the use commencing, whichever is earlier, the Principal Certifier must obtain Council's approval of the waste and recycling management facilities provided in the development and ensure arrangements are in place for domestic waste collection by Council.

Reason

To ensure that waste and recycling is appropriately managed.

PART C – BEFORE THE COMMENCEMENT OF BUILDING WORK

(15) TREE PROTECTION ZONE

- (a) Before the commencement of works, Tree Protection Zone/s (TPZ) must be established around all trees to be retained not less than the distance indicated in the TPZ schedule below.
- (b) Tree protection must be installed and maintained in accordance with the Australian Standard 4970 Protection of Trees on Development Sites and with the following schedule:

TPZ Schedule

Tree No.	Species Name	Location	Radius (m) From Trunk
2	Howea forsteriana	Rear Yard – refer to approved ground floor plan for tree numbers and locations	2.5m
3	Jacaranda mimosifolia	Rear Yard – refer to approved ground floor plan for tree numbers and locations	7.8m
5	Howea forsteriana	Rear Yard – refer to approved ground floor plan for tree numbers and locations	3m
6	Eucalyptus nicholii	Rear Yard – refer to approved ground floor plan for tree numbers and locations	4.8m
7	Howea forsteriana	Rear Yard – refer to approved ground floor plan for tree numbers and locations	3m
8	Eucalyptus nicholii	Rear Yard – refer to approved ground floor plan for tree numbers and locations	5.9m

Note: Only applies to the TPZ within the subject development site and the public domain.

- (c) Tree trunks and major branch protection must be undertaken prior to the commencement of any works. The protection must be installed and certified by a qualified Arborist (minimum AQF 3) and must include;
 - (i) Tree trunk/s and/or major branches must be protected by wrapped thick carpet underlay or similar padding material to limit damage.
 - (ii) Timber planks (50mm x 100mm must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals and must be fixed against the trunk with tie wire, or strapping. The thick carpet underlay or padding material and timber planks must not be fixed to the tree in any instance, or in any fashion.
 - (iii) Tree trunk and major branch protection is to remain in place for the duration of construction and development works and must be removed at the completion of the project.
- (d) Ground surface protection must be installed if construction access is required through any TPZ of this condition where hard surface / paving is not existing. The ground protection must be:
 - (i) Protected with boarding (ie scaffolding board or plywood sheeting or similar material), placed over a layer of mulch to a depth of at least 75mm and geotextile fabric;
 - (ii) The protective boarding must be left in place for the duration of the construction and development.
- (e) The following works must be excluded from within any TPZs:
 - (i) Excavation (except for the area required for the approved main building extension);
 - (ii) Soil cut or fill including trenching;
 - (iii) Soil cultivation, disturbance or compaction;
 - (iv) Stockpiling, storage or mixing of materials;
 - (v) The storing, washing and repairing of tools, equipment and machinery;
 - (vi) The disposal of liquids and refuelling;
 - (vii) The disposal of building materials;
 - (viii) The siting of offices or sheds;
 - (ix) Any action leading to the impact on tree health or structure.
- (f) Any trenching works for services / hydraulics / drainage etc must not be undertaken within any TPZ. Alternative installation methods for services, such as directional boring/drilling, or redirection of services must be employed.
- (g) All work undertaken within or above the TPZ must be:

- (i) Carried out in accordance with a work methodology statement prepared by an Arborist (minimum AQF Level 5) and written approval is obtained from Council's Tree Management Officer before its implementation; and
- (ii) Supervised by a Project Arborist (minimum AQF Level 5).

Reason

To ensure the protection and ongoing health of trees.

(16) DILAPIDATION REPORT – MINOR

Subject to the receipt of permission of the affected landowner, dilapidation report/s of adjoining buildings are to be prepared by an appropriately qualified practising structural engineer and submitted for the approval of the Registered Certifier prior to the issue of a construction certification.

Reason

To ensure that dilapidation reports are prepared and to identify damage to for adjoining/nearby properties resulting from building work on the development site.

(17) STRUCTURAL INTEGRITY OF RETAINED BUILDING ELEMENTS

Prior to a commencement of demolition, excavation or construction work, a report or certification from a practicing structural engineer experienced in dealing with heritage buildings must be submitted to and approved by Area Coordinator Planning Assessments or Area Planning Manager. The report must explain how the retained building elements, such as building facades or chimneys are to be retained, supported and not undermined by the proposed development and give details of any intervention or retrofitting needed.

Reason

To ensure the preservation of the building elements that are proposed to be retained.

(18) OTHER APPROVALS

Any activity which is proposed to be undertaken in, on or above a road reserve or the public domain (including a public footway) must have separate approval(s) obtainable through the lodgement of an application under Section 68 of the Local Government Act 1993 and/or Section 138/139 of the Roads Act 1993 prior to the commencement of work/activities within the road reserve/public domain. Such activities include but not limited to:

- (a) installation of construction-related temporary structures including hoardings/scaffolding;
- (b) installation and/or alterations to advertising/business signs;
- (c) installation and/or alterations to street awnings;

- (d) crane operation and other hoisting activities;
- (e) temporary works (e.g. barricading, road openings, mobile hoisting devices);
- (f) works zones (for loading and unloading from the roadway); and
- (g) temporary ground anchoring and shoring to support a roadway when excavating; and
- (h) any other structure or encroachment including facade elements/architectural features.

Reason

To ensure use of a public place is managed appropriately.

PART D – WHILE BUILDING WORK IS BEING CARRIED OUT

(19) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. Loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 – 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on-site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Team, prior to works proceeding

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

Reason

To protect the amenity of the surrounding area.

(20) ARCHAEOLOGICAL DISCOVERY DURING EXCAVATION

- (a) Should any relics be unexpectedly discovered on the site during excavation, all excavation or disturbance to the area is to stop immediately and the Heritage Council of NSW should be informed in accordance with section 146 of the Heritage Act 1977.
- (b) Should any Aboriginal objects be unexpectedly discovered then all excavation or disturbance of the area is to stop immediately and NSW Government Office of Environment and Heritage is to be informed in accordance with Section 89A of the *National Parks and Wildlife Act 1974*.

- (c) Should any archaeological remains or Aboriginal objects be discovered, a copy of recording of the finds and the final archaeological summary report is to be submitted to Council prior to the issue of any Occupational Certificate.
- (d) If the discovery is on Council's land, Council must be informed.

Reason

To ensure that the archaeology of the site is appropriately managed and protected.

(21) TREE SENSITIVE EXCAVATION

Structural Root Zone (SRZ) Schedule:

Tree No	Species	TPZ radius (m) from Trunk	SRZ (m) from Trunk
2	Howea forsteriana	2.5m	n/a
3	Jacaranda mimosifolia	7.8m	3m
5	Howea forsteriana	3m	n/a
6	Eucalyptus nicholii	4.8m	2.4m
7	Howea forsteriana	3m	n/a
8	Eucalyptus nicholii	5.9m	2.6m

- (a) Within the SRZ;
 - (i) Excavation must not occur within the SRZ. If excavation is proposed within this zone, the Council's Tree Management Officer must be contacted immediately and the excavation must be carried out in accordance with Council's direction.
- (b) Within the TPZ;
 - (i) Small hand tools such as mattocks or using compressed air or water jetting only shall be used. Roots with a diameter equal to or greater than 40mm shall not be severed or damaged unless approved in writing by Council's Tree Management Officer.

Mechanical excavation is permitted beyond this radius when root pruning by hand along the perimeter line is completed. Exposed roots to be retained shall be covered with mulch or a geotextile fabric and kept in a moist condition and prevented from drying out.
 - (ii) All excavations must be supervised by a Project Arborist (minimum AQF Level 5).
- (c) Footings must be relocated / realigned if any tree root greater than 40mm in diameter is encountered during excavations. A minimum of 150mm clearance must be provided between the tree root and footing.

- (d) All excavations located within the TPZ must be supervised by a Project qualified Consultant Arborist (minimum AQF Level 5), who holds the Diploma in Horticulture (Arboriculture), Level 5 under the Australian Qualification Framework.
- (e) All root pruning must be undertaken in accordance with the Australian Standard 4373 'Pruning of Amenity Trees' and by a qualified Arborist with a minimum AQF level 3.

Reason

To ensure the protection and ongoing health of trees.

(22) TREE PRUNING – FURTHER APPROVAL REQUIRED

Consent from Council's Tree Management Officer must be obtained prior to any tree pruning work being undertaken, including tree roots greater than 40mm in diameter, for any trees located within or adjacent to the site. Only minor pruning works will be approved by Council.

Reason

To ensure that pruning works to trees are carried out in an appropriate manner.

(23) PROTECTION OF NATIVE WILDLIFE

- (a) In the event that wildlife is found during the course of tree removal works, work must stop until a trained wildlife handler attends the site or the animal relocates itself. In regards to tree pruning, works may only proceed if the animals will not come into direct harm.
- (b) In the event that the tree has nesting birds or native animals, works must be delayed until after the nesting period has been completed, unless in the event of an emergency.

Reason

To ensure that wildlife is adequately protected during tree removal/pruning works.

(24) COMPLIANCE WITH NATIONAL CONSTRUCTION CODE

All proposed work must comply with the *National Construction Code (previously known as Building Code of Australia)*.

Reason

(Prescribed condition - EP&A Regulation 2021 clause 69(1)).

(25) EROSION AND SEDIMENT CONTROL - LESS THAN 250SQM

Where less than 250 square metres are being disturbed, no formal plan is required however, the site is to be provided with sediment control measures and these must be implemented so that sediment, including soil, excavated material, building material or other materials cannot fall, descend, percolate, be pumped, drained, washed or allowed to flow to the street, stormwater system or waterways.

Reason

To ensure that appropriate erosion and sediment control measures are put in place during construction to protect the environment.

(26) SURVEY

All footings, walls and floor slabs adjacent to a boundary must be set out by a registered surveyor. On commencement of brickwork or wall construction a survey and report, prepared by a Registered Surveyor, must be submitted to the Principal Certifier indicating the position of external walls in relation to the boundaries of the allotment. Any encroachments by the subject building over adjoining boundaries or roads must be removed prior to continuation of building construction work.

Reason

To ensure the development does not encroach onto neighbouring properties.

(27) COVERING OF LOADS

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

Reason

To ensure loads are managed appropriately and do not impact local amenity.

(28) EROSION AND SEDIMENT CONTROL

The Soil and Water Management Plan (SWMP) or Erosion and Sediment Control Plan (ESCP) which has been approved by the Principal Certifier must be implemented in full during the construction period.

During the construction period:-

- (a) erosion and sediment controls must be regularly inspected, repaired and maintained in working order sufficient for a 10 year Average Recurrence Interval (ARI) rainfall event;
- (b) erosion and sediment control signage available from Council must be completed and attached to the most prominent structure visible at all times when entering the site for the duration of construction; and

- (c) building operations and stockpiles must not be located on the public footway or any other locations which could lead to the discharge of materials into the stormwater system.

Reason

To ensure no substance other than rainwater enters the stormwater system and waterways.

(29) VEHICLE CLEANSING

Prior to the commencement of work, suitable measures are to be implemented to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site. It is an offence to allow, permit or cause materials to pollute or be placed in a position from which they may pollute waters.

Reason

To ensure sediment is not tracked onto the roadway.

(30) LOADING AND UNLOADING DURING CONSTRUCTION

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site, where possible.
- (b) If, it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.
- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.
- (d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate application under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993 must be submitted to and approved by Council.

Reason

To protect the amenity of the public domain.

(31) NO OBSTRUCTION OF PUBLIC WAY

Unless otherwise approved by Council, the public way must not be obstructed by any materials, vehicles, waste receptacles, skip-bins or the like. Non-compliance with this requirement may result in the issue of a notice by Council to stop all work on the site.

Reason

To protect the amenity of the public domain.

(32) USE OF MOBILE CRANES

The following requirements apply:

- (a) Mobile cranes operating from the road must not be used as a method of demolishing or constructing a building.
- (b) For special operations including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes, permits must be obtained from Council for the use of a mobile crane. The permits must be obtained 48 hours beforehand for partial road closures which, in the opinion of Council will create minimal traffic disruptions and 4 weeks beforehand in the case of full road closures and partial road closures which, in the opinion of Council, will create significant traffic disruptions.
- (c) The use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of approved hours of construction can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Reason

To ensure mobile cranes are used appropriately.

PART E – BEFORE THE ISSUE OF AN OCCUPATION CERTIFICATE

(33) BASIX

All commitments listed in each relevant BASIX Certificate for the development must be fulfilled prior to any Occupation Certificate being issued.

Reason

To ensure BASIX commitments are fulfilled in accordance with the BASIX certificate (prescribed condition under clause 75 EP&A Regulation 2021).

(34) SURVEY CERTIFICATE AT COMPLETION

A Survey Certificate prepared by a Registered Surveyor must be submitted to the Principal Certifier at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

Reason

To ensure the development does not encroach onto neighbouring properties.

PART F – OCCUPATION AND ONGOING USE

(35) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

Reason

To ensure the site is authorised for occupation.

(36) ENCROACHMENTS – NEIGHBOURING PROPERTIES

No portion of the proposed structure shall encroach onto the adjoining properties.

Reason

To protect neighbouring properties.

(37) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

Reason

To protect the public way.