

Attachment A

Recommended Conditions of Consent
--

SCHEDULE 1

CONDITIONS OF CONSENT

PART A - GENERAL

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2022/1251 dated 07 December 2022 and the following drawings prepared by David Mitchell Architects:

Drawing Number	Drawing Name	Date
DA 1101 Issue F	Basement Level Plan	22 November 2023
DA 1102 Issue F	Ground Level Plan	22 November 2023
DA 1103 Issue F	Level 1 Plan	22 November 2023
DA 1104 Issue F	Level 2 Plan	22 November 2023
DA 1105 Issue F	Level 3 Plan	22 November 2023
DA 1106 Issue F	Level 4 Plan	22 November 2023
DA 1107 Issue F	Level 5 Plan	22 November 2023
DA 1108 Issue F	Level 6 Plan	22 November 2023
DA 1109 Issue F	Roof Plan	22 November 2023
DA 1301 Issue F	Elevation East	22 November 2023
DA 1302 Issue F	Elevation South	22 November 2023
DA 1303 Issue F	Elevation North	22 November 2023
DA 1304 Issue F	Elevation West	22 November 2023
DA 1201 Issue F	Section A	22 November 2023
DA 1202 Issue F	Section B	22 November 2023

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the plans will prevail.

Reason

To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

(2) DESIGN MODIFICATIONS

The design of the building must be modified as follows:

- (a) The private rooftop terrace is to be amended to allow for a minimum area of 3m x 3m (minimum area of 9 sqm) for the tree planter on the eastern side of the pool. The eastern tree planter is to be free of all structures, including pool stairs.
- (b) The design of the waste layout within the basement plan is to be amended to provide compliant separate bulky waste storage for both residential and commercial waste (4 sqm each). The commercial bulky waste area can be combined with the general waste commercial waste storage area. Residential bulky waste must be in a separate area.
- (c) The awning along Macleay Street is to be amended to comply with the provisions in 3.2.4 and Schedule 4 of the City of Sydney Development Control Plan 2012. The awning must be at least 3m above the footpath and at least 800mm from the face of the kerb along Hughes Street and Macleay Street.
- (d) The following windows within the building are to be obscured glazed:
 - i. Level 1 – lower portion of W06-L1 & W07-L1
 - ii. Level 2 – lower portion of W03-L2, full extent of W08-L2 & W09-L2
 - iii. Level 3 – lower portion of W03-L3, full extent of W08-L3 & W09-L3
 - iv. Level 4 – lower portion of W03-L4, full extent of W04-L4, W05-L4, W08-L4 & W09-L4

Amended architectural plans with levels (RL, TW, SSL) must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the issue of a Construction Certificate.

Reason

To ensure an appropriate design outcome.

(3) DESIGN MODIFICATIONS – ACOUSTICALLY TREATED PLENUM TO BE DESIGNED & INCORPORATED INTO THE DEVELOPMENT

The design of the building must be modified to incorporate acoustically treated, naturally ventilated plenums. The below documentation is to be provided to Council's Area Planning Manager prior to issue of a Construction Certificate to demonstrate the adequacy of the plenums:

- (a) The plenum design must be demonstrated to comply with the following:
 - (i) No mechanical assistance is to be provided to the plenums and/or alternative façade treatments. The plenum must incorporate acoustic lagging, be accessible for cleaning and be fitted with an insect screen. The plenum must not incorporate baffles that choke airflow.

- (ii) The plenums and/or alternative façade treatments are to be designed to integrate with the building design. Detailed elevations, plans and sections are to be provided.
 - (iii) The plenum design must be captured by specific drawing detailing the construction of the plenum and a written document outlining the specifications, manufacturing requirements and performance requirements for the plenum.
- (b) A suitably qualified ventilation expert must be engaged and prepare a Ventilation Assessment of the proposed plenums to demonstrate compliance with the City of Sydney's *Draft Alternative Natural Ventilation of Apartments in Noisy Environments: Performance Pathway Guideline*.

The below documentation is to be provided to Council's Area Planning Manager prior to issue of an Occupation Certificate to demonstrate the adequacy of the plenums:

- (c) The plenum design must be certified by a written acoustic compliance statement prepared by a suitably qualified acoustic consultant which demonstrates the following:
 - a. The plenum must have an acoustic performance requirement expressed in terms of 1/1 octave bands (centre frequencies 31.5Hz through 8 kHz) to afford compliance with the noise criteria below, whilst the ventilators are operating, and external windows and doors are closed.
 - b. LAeq, 1 hour 45 dB(A) in any main living area (24-hours) and LAeq, 1 hour 35 dB(A) in any bedroom (10:00pm-7:00am), as outlined in Section 4.2.3.11 of the Sydney Development Control Plan (SDCP) 2012.
 - c. The written acoustic compliance statement will form part of the COMPLIANCE WITH THE ACOUSTIC REPORT PRIOR TO CONSTRUCTION AND OCCUPATION CERTIFICATES condition, as a report that must be certified and verified prior to a relevant construction and occupation certificate in accordance with the condition.
- (d) A maintenance report prepared by a suitably qualified engineer which demonstrates how the plenums will be maintained for the life of the development must be submitted.

The plenums must be retained for the life of the development.

Where the requirements of this condition conflict with another report (for example a separate acoustic report), this condition prevails.

Reason

To require amendments to the approved plans and supporting documentation following assessment of the development.

(4) BUILDING HEIGHT

- (a) The height of the building must not exceed RL 60.82 (AHD) to the top of the building.
- (b) Prior to an Occupation Certificate being issued, a Registered Surveyor must provide certification that the height of the building accords with (a) above, to the satisfaction of the Principal Certifier.

Reason

To ensure the constructed development complies with the approved height.

(5) FLOOR SPACE RATIO - ALL OTHER AREAS

The following applies to Floor Space Ratio:

- (a) The Floor Space Ratio for the commercial use must not exceed 0.47:1 FSR and for the residential use must not exceed 2.03:1 FSR; calculated in accordance with the Sydney Local Environmental Plan (SLEP) 2012. For the purposes of the calculation of FSR, the Gross Floor Area of the commercial component is 153.50 sqm, for the residential component is 665.30 sqm, and the total Gross Floor Area is 818.8 sqm.
- (b) Prior to an Occupation Certificate being issued, a Registered Surveyor must provide certification of the total and component Gross Floor Areas (by use) in the development, utilising the definition within the Sydney Local Environmental Plan (SLEP) 2012, applicable at the time of development consent, to the satisfaction of the Principal Certifier.

Reason

To ensure the constructed development complies with the approved floor space ratio.

(6) USE - SEPARATE DA REQUIRED

No consent is granted or implied for the fitout or specific use of each individual tenancy.

A development consent or Complying Development Certificate (as appropriate) is required to be obtained for the fitout and use of each individual retail tenancy prior to that fitout or use commencing.

Reason

To require separate consent to be obtained for a use.

(7) SIGNS - SEPARATE DA REQUIRED

A separate development application for any proposed signs additional to those approved as part of this consent (other than exempt or complying signs) must be submitted to and approved by Council prior to the erection or display of any such signs.

Reason

To require separate consent to be obtained for any additional signs.

(8) SIGNS AT EGRESS

The following signs must be provided and maintained within the site at the point(s) of vehicle egress:

- (a) Compelling drivers to stop before proceeding onto the public way.

Reason

To ensure the safety of surrounding pedestrians and cyclists.

(9) VEHICLE FOOTWAY CROSSING

A separate application is to be made to, and approved by, Council for the construction of any proposed vehicle footway crossing or for the removal of any existing crossing and replacement of the footpath formation where any such crossings are no longer required.

All disused or redundant vehicle crossings and laybacks must be removed and footway, kerb, gutter and road restoration reinstated in accordance with Council's standards, to suit the adjacent finished footway and edge treatment materials, levels and details, or as otherwise directed by Council officers. All construction and replacement works are to be completed in accordance with the approved plans prior to the issue of any Occupation Certificate.

Note: In all cases the construction materials should reinforce the priority of pedestrian movement over that of the crossing vehicle.

Reason

To ensure all relevant approvals for traffic and parking works are obtained and designed in accordance with Council requirements.

(10) ASSOCIATED ROADWAY COSTS

All costs associated with the construction of any new road works including kerb and gutter, road pavement, drainage system and footway shall be borne by the developer. The new road works must be designed and constructed in accordance with the City's "Sydney Streets Technical Specification" including amendments and "Sydney Streets Design Code".

Reason

To ensure all roadway works are designed and constructed in accordance with Council requirements.

(11) COST OF SIGNPOSTING

All costs associated with signposting for any kerbside parking restrictions and traffic management measures associated with the development shall be borne by the developer.

Reason

To ensure all associated roadway works costs are borne by the developer.

(12) CHANGES TO KERB SIDE PARKING RESTRICTIONS

A separate submission must be made to the Local Pedestrian, Cycling and Traffic Calming Committee via the City Infrastructure and Traffic Operations Unit seeking the City's approval for any changes to kerb side parking arrangements. There is no guarantee kerb side parking will be changed, or that any change will remain in place for the duration of the development use.

The submission must include two plans. One showing the existing kerb side parking restriction signs and stems, the second showing the proposed kerb side parking restriction signs and stems. Both plans must include chainages to all signs and stems from the kerb line of the nearest intersection.

All costs associated with the parking proposal will be borne by the developer.

Note: As parking in the LGA is at a premium, it is recommended that the applicant should approach the Area Traffic Engineer to discuss the proposal before making a submission.

Reason

To require separate consent to be obtained for changes to kerb side parking arrangements.

(13) MECHANICAL PARKING FACILITIES (CAR STACKER AND TURNTABLE)

The following details being submitted to an approved by the Principal Certifying Authority prior to the issue of the issue of a Construction Certificate:

- (a) A review of the proposed installation by the manufacturer and its suitability for implementation in accordance with the manufacturer's specifications including but not limited to compliance with AS/NZS2890.1 2004 and its references to AS/NZS 28590.6.
- (b) Implementation of mechanisms addressing potential safety concerns including noise and vibration levels and compliance to the relevant Australian Standards.
- (c) A plan for responding to the mechanical breakdown and/or system failures. This includes options for necessary trainings/ induction prior to use.
- (d) Stacker cannot be used for visitor parking.
- (e) User induction/ training prior to use of car stacker and turn table.
- (f) Any further information requested by the Principal Certifying Authority.

Reason

To ensure that traffic ingress and egress is appropriately managed.

(14) CAR STACKER USE AND OPERATION

The following details being submitted to an approved by the Principal Certifying Authority prior to the issue of the issue of a Construction Certificate:

- (a) The mechanical car stacker must be in a lowered/ 'closed' position at all times when not in operation
- (b) The mechanical car stacker shall be remote system operated only and no vehicles shall be left unattended on the turntable and stacker area
- (c) Specifications of the mechanical car stacker shall be provided to the certifier
- (d) The terrace area above the mechanical car stacker must not be occupied whilst the mechanical car stacker is in use.
- (e) The terrace area above the mechanical car stacker must not be occupied whilst the car stacker is in use.
- (f) Vehicle turntable area must be kept free at all time and cannot be used for loading goods or any other purpose.

Reason

To ensure that traffic ingress and egress is appropriately managed.

(15) FORWARD IN/OUT ONLY VEHICLES ACCESS

The site must be configured to allow all vehicles to be driven onto and off the site in a forward direction. A vehicle turntable must be used (if necessary) to achieve forward in and forward out movements.

Reason

To ensure that traffic ingress and egress is appropriately managed.

(16) WASTE AND RECYCLING MANAGEMENT - GENERAL

The proposal must comply with the relevant provisions of Council's *Guidelines for Waste Management in New Developments 2018* which requires facilities to promote the efficient storage, separation, collection and handling of waste to maximise resources recovery.

Reason

To ensure that waste and recycling is appropriately managed.

(17) NO OBSTRUCTIONS

All public footways and paths of travel must be free from obstructions. If services are required to be relocated to clear paths of travel then this must be undertaken at the developer's expense. All obstructions are to be removed prior to the issue of any Occupation Certificate.

Reason

To ensure there are no obstructions on public footways and paths of travel.

(18) PAVING MATERIALS

The surface of any material used or proposed to be used for the paving of colonnades, thoroughfares, plazas, arcades and the like which are used by the public must comply with AS/NZS 4586:2004 (including amendments) "Slip resistance classification of new pedestrian surface materials".

Reason

To ensure appropriate and safe paving materials are used.

(19) LETTERBOXES

(a) Letterboxes are to be discreetly located, must not obstruct and/or dominate the public way and must be of a type and specification that minimises opportunities for mail theft.

(c) Letterboxes are to be installed with non-master key locks for security.

Note: The applicant is advised to contact Australia Post to discuss how the letterboxes within the lobby will be accessed.

Reason

To ensure letterboxes are located in an appropriate location on the site to prevent mail theft.

(20) NO AIR CONDITIONING UNITS TO FACADE OR BALCONIES OF BUILDING

Approval is not granted for the installation of individual air conditioning units to the facade or balconies of the building.

Reason

To clarify the scope of the consent.

PART B – BEFORE THE ISSUE OF A CONSTRUCTION CERTIFICATE

(21) SECTION 7.11 CONTRIBUTIONS PAYABLE - CONTRIBUTION TOWARDS PUBLIC AMENITIES – CITY OF SYDNEY DEVELOPMENT CONTRIBUTIONS PLAN 2015 – EAST PRECINCT

Council has identified the development will increase demand for public amenities and facilities. Pursuant to Section 7.11 of the Environmental Planning and Assessment Act, 1979 (as amended), and the City of Sydney Development Contributions Plan 2015 the following monetary contributions are required towards the cost of public amenities.

<u>Contribution Category</u>	<u>Amount</u>
Open Space	\$20,374.81
Community Facilities	\$5,807.59
Traffic and Transport	\$-515.67
Stormwater Drainage	\$0.00
Total	\$25,666.73

The City of Sydney will index the above contribution for inflation at the time of payment using the following formula.

$$C_{\text{payment}} = C_{\text{consent}} \times (CPI_{\text{payment}} \div CPI_{\text{consent}})$$

Where:

C_{payment} = Is the contribution at time of payment;

C_{consent} = Is the contribution at the time of consent, as shown above;

CPI_{payment} = Is the Consumer Price Index (All Groups Index) for Sydney published by the Australian Bureau of Statistics that applies at the time of payment; and

CPI_{consent} = Is the Consumer Price Index (All Groups Index) for Sydney at the date the contribution amount above was calculated being – 135.8 for the September 2023 quarter.

The contribution must be paid prior to the issue of any Construction Certificate in relation to this development.

Please contact Council's Planning Administration staff at planningsystemsadmin@cityofsydney.nsw.gov.au to request a letter confirming the indexed contribution amount payable.

Once the letter confirming the indexed contribution is obtained, payment may be made at any of the City's Neighbourhood Service Centres or the One Stop Shop at Town Hall House. Acceptable payment methods are EFTPOS (debit card only), cash (up to 10K only), Credit Card (up to 50K only) or a bank cheque made payable to the City of Sydney. Personal or company cheques will not be accepted.

Reason

To ensure development contributions are paid to address the increased demand for public amenities and services resulting from the approved development.

(22) AFFORDABLE HOUSING CONTRIBUTION – RESIDUAL LAND OR CENTRAL SYDNEY – PAYMENT IN LIEU OF FLOOR SPACE CONTRIBUTION – PRIOR TO CONSTRUCTION CERTIFICATE

- (a) In accordance with the City of Sydney Affordable Housing Program and prior to the issue of a Construction Certificate, the applicant must provide evidence that a monetary contribution towards the provision of affordable housing has been paid to the City of Sydney Council.
- (b) The contribution is \$228,052.37 (indexed at 4 January 2024). This is calculated by establishing the sum of the equivalent monetary contribution \$10,611.53 multiplied by 1% of the total floor area for non-residential development (153.50 sqm) and the equivalent monetary contribution \$10,611.53 multiplied by 3% of the total floor area for residential development (665.20 sqm).
- (c) If the contribution is paid after the indexation period in which the consent is granted, being 01 March 2023 to 29 February 2024, the above contribution will be adjusted according to the Sydney LGA median strata dwelling price ('MDP') using the following formula.
- (d) Contribution payable at Time of Payment = $C \times \text{MDP2} / \text{MDP1}$, where:
 - (i) C is the original total contribution amount payable to the City of Sydney as shown above;
 - (ii) MDP2 is the Median Strata Dwelling Price in Sydney LGA taken from the most recent NSW Government Rent and Sales Report at the time of indexation of the equivalent monetary contribution rate; and
 - (iii) MDP1 is the Median Strata Dwelling Price in Sydney LGA taken from the NSW Government Rent and Sales Report used to establish the current equivalent monetary contribution rate, being 01 March 2023 to 29 February 2024.

Contact Council's Planning Assessment Unit at planningsystemsadmin@cityofsydney.nsw.gov.au for written confirmation of the amount payable, with indexation as necessary, prior to payment.

Reason

To ensure development contributions are paid to contribute to the provision of essential affordable rental housing infrastructure.

(23) DETAILED SITE INVESTIGATION

A Detailed Environmental Site Investigation (DESI) is to be carried out by a suitably qualified and competent environmental consultant and submitted to the City Area Planning Manager for further review in accordance with the NSW Government Office of Environment and Heritage, Guidelines for Consultants Reporting on Contaminated Sites, Contaminated Land Management Act 1997 and SEPP (Resilience and Hazards), confirming that the site is suitable (or will be suitable, after remediation) for the proposed use.

Where the DESI states that the site requires remediation, a Remediation Action Plan (RAP) is to be prepared by a suitably qualified and competent environmental consultant in accordance with the NSW Government Office of Environment and Heritage, Guidelines for Consultants Reporting on Contaminated Sites and the Contaminated Land Management Act 1997 and submitted to the City Area Planning Manager for approval.

Note: Where the DESI concludes that the site is suitable for the proposed use it is to be peer reviewed by a NSW EPA Accredited Site Auditor and a Section A Site Audit Statement submitted to the City Area Planning Manager certifying that the site is suitable for the proposed use.

The DESI and RAP must be peer reviewed by a NSW EPA Accredited Site Auditor and include a section B Site Audit Statement or a letter of Interim advice from the Site Auditor certifying that the RAP is practical, and the site will be suitable after remediation for the proposed use.

Reason

To ensure that any contamination impacts uncovered through demolition, excavation and construction are appropriately managed.

(24) BASIX CERTIFICATE – DETAILS TO BE LODGED WITH A CC

A copy of the required completed BASIX certificate accepted as part of this Development Consent with respect to the proposed residential building works, must be lodged with an application for a construction certificate and the items nominated as part of the subject BASIX certificate must be specified on the plans submitted with the construction certificate application. – See Note.

IMPORTANT NOTE:

Any requirement detailed in the accompanying BASIX Certificate, **MUST** be included as a specific notation or inclusion on any future Construction Certificate plans and specification in accordance with Part 3 of Schedule 1 of the EP&A Regulation, 2021.

Reason

To ensure BASIX commitments are fulfilled in accordance with the BASIX certificate (prescribed condition under clause 75 EP&A Regulation, 2021).

(25) EXTERNAL WALLS AND CLADDING FLAMMABILITY

The external walls of the building including attachments must comply with the relevant requirements of the *Building Code of Australia*. Prior to the issue of a Construction Certificate and Occupation Certificate the Registered Certifier and the Principal Certifier must:

- (a) Be satisfied that suitable evidence is provided to demonstrate that the products and systems proposed for use or used in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the BCA; and
- (b) Ensure that the documentation relied upon in the approval processes include an appropriate level of detail to demonstrate compliance with the BCA as proposed and as built.

Reason

To ensure the external walls and cladding comply with relevant requirements.

(26) UTILITY SERVICES

To ensure that utility authorities are advised of the development:

- (a) Prior to the issue of a Construction Certificate a survey is to be carried out of all utility services within and adjacent to the site including relevant information from utility authorities and excavation if necessary, to determine the position and level of services.
- (b) Prior to the commencement of work the applicant is to obtain written approval from the utility authorities (e.g. Energy Australia, Sydney Water, and Telecommunications Carriers) in connection with the relocation and/or adjustment of the services affected by the construction of the underground structure. Any costs in the relocation, adjustment or support of services are to be the responsibility of the developer.

Reason

To ensure that utility authorities are advised of the development and their approval is obtained in connection with the relocation and/or adjustment of services affected by the development.

(27) MATERIALS AND SAMPLES BOARD

A physical material sample board which specifies all proposed materials, finishes and colours, (including visible rainwater goods and services) keyed to each building elevation must be submitted to and approved by Council's Urban Design Officer / Heritage Specialist, prior to a Construction Certificate being issued. The materials and samples board must not include generic material or colour descriptions or use terminology such as 'or similar'.

Reason

To require the submission of a materials and samples board following assessment of the development.

(28) FLOOR TO CEILING HEIGHT

Prior to a Construction Certificate being issued, the Registered Certifier must ensure that all living rooms and bedrooms in sole occupancy units must have a minimum finished floor to ceiling height of not less than 2.7 metres.

Reason

To ensure an adequate minimum floor to ceiling height to provide an acceptable level of amenity.

(29) COMPLIANCE WITH THE ACOUSTIC REPORT PRIOR TO CONSTRUCTION AND OR OCCUPATION CERTIFICATES

- (a) All relevant performance parameters (including but not limited to requirements, engineering assumptions and recommendations) in the DA Acoustic Report, prepared by "Koikas Acoustics", Ref: 5087R20220323Im95MacleayStPottsPoint_DAv3, dated 24 November 2022; must be implemented in the development prior to the commencement of its use.
- (b) Prior to the issue of any relevant Construction Certificate, the final construction drawings and final construction methodology must be assessed and reported to be in accordance with the requirements of the DA Acoustic Report in (a) above, with reference to relevant documentation. This must be done by a Suitably Qualified Acoustic Consultant* (see definition below). This work will be to the satisfaction of the accredited certifier.
- (c) Prior to the issue of any Occupation Certificate, a Suitably Qualified Acoustic Consultant* is to provide a written Acoustic Verification Report to the satisfaction of the Principal Certifier that the development complies with the requirements set out in the Report and in (a) and (b) above.

Note: Suitably Qualified Acoustic Consultant means a consultant who possesses the qualifications to join the Australian Acoustical Society, Institution of Engineers Australia (grade of member) or the Association of Australasian Acoustical Consultants (grade of member firm).

- (d) All physical aspects of the building's structure installed in order to meet performance parameters in accordance with this condition must be maintained at all times.

Reason

To ensure all parties are aware of the supporting documentation that applies to the development.

(30) WASTE AND RECYCLING MANAGEMENT - COMMERCIAL

- (a) A Waste and Recycling Management Plan, which meets the requirements as set out in Council's *Guidelines for Waste Management in New Developments 2018*, is to be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to a Construction Certificate being issued.

- (b) All requirements of the approved Waste and Recycling Management Plan must be implemented during construction and operation of the development and include:
- (i) Dedicated space to be provided within the development for the storage and recycling of bulky waste, problem waste, strip out and food waste.
 - (ii) Collection points for waste and recycling must be wholly located within the boundary of the development.
 - (iii) The nominated waste and recycling storage areas must be constructed to meet the relevant conditions required by the City's Guidelines for Waste Management in New Developments 2018.
 - (iv) Provision and storage within the boundary of the development of waste and recycling receptacles and any bulky waste at all times.
 - (v) Commercial tenancies must have a commercial waste contract(s) in place prior to commencement of business trading.
 - (vi) The path of travel between the bin storage areas/bulky waste storage areas and the designated waste/recycling collection point is to have a minimum 1,200mm wall-to-wall clearance, be slip-proof, of a hard surface, be free of obstructions and at no point have a gradient exceeding 1:14. The use of a lift is permitted, but consideration should be given to the inclusion of a service lift in this instance.

Note: The building manager/strata title manager or body corporate is responsible for ensuring all tenants are kept informed regarding Council's policies, and best practice waste and recycling source separation.

UPON COMPLETION OF THE DEVELOPMENT

- (c) Prior to any Occupation Certificate being issued or the use commencing, whichever is earlier, the Principal Certifier must obtain Council's approval of the waste and recycling management facilities provided in the development and ensure arrangements are in place for domestic waste collection by Council.

Reason

To ensure that waste and recycling is appropriately managed.

(31) DEMOLITION, EXCAVATION AND CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

A site-specific noise management plan must be submitted to the Council for comment and approval prior to issue of any Construction Certificate. The Plan must be prepared by a suitably qualified acoustic consultant who is a person who possesses the qualifications to join the Australian Acoustic Society, Institution of Engineers Australia (grade of member) or the Association of Australasian Acoustic Consultants (grade of member firm).

The plan must include but not be limited to the following:-

- (a) identification of noise sensitive receivers near to the site.
- (b) A prediction as to the level of noise impact likely to affect the nearest noise sensitive receivers from the use and proposed number of high noise intrusive appliances intended to be operated onsite. A statement should also be submitted outlining whether or not predicted noise levels will comply with the noise criteria stated within the *City of Sydney Construction Hours /Noise Code of Practice 1992* for the typical construction hours of 07.00am to 7.00pm. Where resultant site noise levels are likely to be in exceedance of this noise criteria then a suitable proposal must be given as to the duration and frequency of respite periods that will be afforded to the occupiers of neighbouring property.
- (c) A representative background noise measurement (LA90, 15 minute) should be submitted, assessed in the vicinity of any potentially affected receiver locations and measured in accordance with AS 1055:1.2.1997.
- (d) Confirmation of the level of community consultation that has/is and will be undertaken with Building Managers/ occupiers of the main adjoining noise sensitive properties likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.
- (e) Confirmation of noise monitoring methodology that is to be undertaken during the main stages of work at neighbouring noise sensitive properties in order to keep complaints to a minimum and to ensure that noise from site works complies with the noise criteria contained within City's Construction Noise Code.
- (f) What course of action will be undertaken following receipt of a complaint concerning offensive noise.
- (g) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupiers of neighbouring noise sensitive property to a minimum.
- (h) What plant and equipment is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on the occupiers of neighbouring property and other less intrusive technologies available.

Reason

To ensure an adequate construction noise and vibration management plan is prepared.

(32) BALCONY BALUSTRADE

Details of the balcony balustrades are to be provided at a scale of 1:20, prior to the issue of a Construction Certificate.

Plans must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager, prior to the issue of a Construction Certificate.

Reason

To protect the amenity of the neighbouring properties.

(33) PARKING DESIGN

The design, layout, signage, line marking, lighting and physical controls of all off-street parking facilities must comply with the minimum requirements of Australian Standard AS/NZS 2890.1 Parking facilities Part 1: Off-street car parking, AS/NZS 2890.2 Parking facilities Part 2: Off-commercial vehicle facilities and AS/NZS 2890.6 Parking facilities Part 6: Off-street parking for people with disabilities. The details must be submitted to and approved by the Accredited Certifier prior to a Construction Certificate being issued.

Reason

To ensure parking facilities are designed in accordance with the Australian Standards.

(34) ALLOCATION OF PARKING

The number of car parking spaces to be provided for the development must comply with the table below. Details confirming the parking numbers must be submitted to the satisfaction of the Accredited Certifier prior to the issue of a Construction Certificate.

Car Parking Type	Number
Residential spaces	4
Retail Employee / Staff spaces	2
Total	6

Reason

To ensure the allocation of parking is in accordance with the Council's DCP.

(35) BICYCLE PARKING AND END OF TRIP FACILITIES

- (a) The minimum number of bicycle parking spaces and end of trip facilities to be provided for the development must comply with the table below.

Bicycle Parking Type	Number	Requirements
Residential	6	Spaces must be a class 1 bicycle locker [1]
Residential visitor	1	Spaces must be Class 3 bicycle rails
Retail Staff/Employee	3	Spaces must be Class 2 bicycle facilities
End of Trip Facility Type	Number	
Showers with change area		
Personal lockers	3	

Notes:

- (i) If a basement storage area on title that is large enough to store a bike and is no smaller than a class 1 bike locker this can be counted as a space.
- (b) The layout, design and security of bicycle facilities must comply with the minimum requirements of Australian Standard AS 2890.3 Parking Facilities Part 3: Bicycle Parking Facilities. The details must be submitted to and approved by the Accredited Certifier confirming prior to and form part of the Construction Certificate being issued.

Reason

To ensure the allocation of bicycle parking is in accordance with Australian Standards and the Council's DCP.

(36) CONSTRUCTION TRAFFIC MANAGEMENT PLAN

- (a) A Construction Traffic Management Plan must be submitted to and approved by Council prior to a Construction Certificate being issued.
- (b) The approved plan must be complied with during any demolition and/or construction work.

Reason

To ensure that the impacts of construction traffic is appropriately managed.

(37) LANDSCAPING OF THE SITE

This condition applies to landscape at grade deep soil area.

- (a) A detailed landscape design including plans and details drawn to scale, and technical specification, by a registered landscape architect must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the issue of a Construction Certificate. These documents must include:
 - (i) Location of existing and proposed planting on the site including existing and proposed trees, planting in natural ground, and planting on structure.
 - (ii) Location and details of existing and proposed structures on the site including, but not limited to, paving, walls, services, furniture, shade structures, lighting and other features.
 - (iii) Details of earthworks and soil depths including finished levels and any mounding. The minimum soil depths for planting on structure must be 1000mm for trees, 450mm for shrubs and 200mm for groundcovers, excluding mulch and drainage layers.
 - (iv) Planting details, and location, numbers, type and supply size of plant species, with reference to Australian Standards and preference for drought resistant species that contribute to habitat creation and biodiversity.
 - (v) Details of drainage, waterproofing and watering systems.
 - (vi) Landscape maintenance plan. This plan is to be complied with during occupation of the property.
- (b) All landscaping in the approved plan is to be complete prior to any Occupation Certificate being issued.

Reason

To ensure the development is supported by a good quality, buildable landscape scheme that meets the City's controls.

(38) INACCESSIBLE GREEN ROOFS

This condition applies to inaccessible green roof for façade planters to levels 2-5.

- (a) A detailed green roof design including plans and details drawn to scale, and technical specification, by a registered landscape architect must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the issue of a Construction Certificate. These documents must include:
 - (i) Location and details of existing and proposed services, walls, fixings and other structural elements that may interrupt waterproofing, including cross-sectional details of all components.
 - (ii) Engineers report confirming structural capacity of building for proposed green roof loads.
 - (iii) Details of soil types and depth including any mounding.

- (iv) Details of drainage and irrigation systems, including overflow provisions and water retention cells in the drainage layer.
 - (v) Planting details, and location, numbers, type and supply size of plant species, with reference to Australian Standards and preference for drought resistant species that contribute to habitat creation and biodiversity.
 - (vi) Green roof maintenance plan. This plan is to be complied with during occupation of the property, and must include any relevant maintenance methodology for safe working at height such as access requirements, location of any anchor points, gates, and transport of materials and green waste.
 - (vii) A plan outlining the intended strategy for decommissioning if planting works fail. This is to ensure green roof maintained is throughout its life.
- (b) Prior to the issue of an Occupation Certificate, structural and waterproofing certifications for the green roof are to be submitted to and approved by the Principal Certifying Authority.
 - (c) All landscaping in the approved plan must be complete prior to the issue of an Occupation Certificate.
 - (d) Inaccessible green roofs must remain inaccessible for the lifetime of the property.

Reason

To ensure that the inaccessible green roof is designed to accommodate suitable landscaping and to ensure that adequate maintenance procedures are put in place.

(39) ACCESSIBLE GREEN ROOFS

This condition applies to accessible green roofs on Level 1 and the rooftop, and balconies on Levels 1-5.

- (a) A detailed green roof design including plans and details drawn to scale, and technical specification, by a registered landscape architect must be submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager prior to the issue of a Construction Certificate. These documents must include:
 - (i) A statement that includes details of proposed use of the green roof, accessibility, and any noise and privacy treatments.
 - (ii) Location and details of existing and proposed services, walls, balustrades, hard surfaces, furniture, screens and shade structures, fixings and other structural elements that may interrupt waterproofing, including cross-sectional details of all components.
 - (iii) Engineers report confirming structural capacity of building for proposed roof terrace loads.

- (iv) Wind study (if applicable) confirming suitability of the roof for intended use.
 - (v) Details of soil types and depth including any mounding. The minimum soil depths for planting on structure must be 1000mm for trees, 450mm for shrubs and 200mm for groundcovers, excluding mulch and drainage layers.
 - (vi) Planting details, and location, numbers, type and supply size of plant species, with reference to Australian Standards and preference for drought resistant species that contribute to habitat creation and biodiversity.
 - (vii) Details of drainage and irrigation systems, including overflow provisions and water retention cells in the drainage layer.
 - (viii) Green roof maintenance plan. This plan is to be complied with during occupation of the property and must include any relevant maintenance methodology for safe working at height such as access requirements, location of any anchor points, gates, and transport of materials and green waste.
- (b) Prior to the issue of an Occupation Certificate, structural and waterproofing certifications for the green roof are to be submitted to and approved by the Principal Certifying Authority.
 - (c) All landscaping in the approved plan must be complete prior to the issue of an Occupation Certificate.

Reason

To ensure that the accessible green roof is designed to accommodate suitable landscaping and to ensure that adequate maintenance procedures are put in place.

(40) TREE PRUNING SPECIFICATION

- (a) A 'Pruning Specification Report' prepared by a qualified Arborist (minimum AQF Level 5) must be submitted to and approved by Council's Area Planning Manager prior to the issuing of the Construction Certificate for the *Celtis sinensis* (Chinese Hackberry) located 12 Hughes Street which overhangs the subject site. The report must include:
 - (i) Number of branches and orientation, branch diameter, percentage of canopy to be pruned/removed.
 - (ii) Photos with individual branches which are recommended for pruning/removal to be clearly marked. (Please note reports which include photos with a single vertical line as the area recommended for pruning will not be accepted).
 - (iii) A maximum of 5% canopy removal and maximum of 100mm diameter branches will be permitted by Council.

- (iv) Pruning work must be specified in accordance with Australian Standard 4373–2007, Pruning of Amenity Trees.
- (v) Tree removal must not be recommended in this report.
- (b) All approved tree pruning works must be carried out by a qualified Arborist, with a minimum Level 3 AQF in arboriculture and in accordance with Work Cover’s Code of Practice – Amenity Tree Industry.
- (c) Any pruning works carried out under this consent must not result in the death of the tree, the creation of a hazard or in excessive or inappropriate amounts of pruning, which result in the overall shape of the tree becoming unbalanced and/or unstable.
- (d) This consent does not authorise the applicant, or the contractor engaged to do the tree works to enter a neighbouring property.
- (e) All tree works must be undertaken from within the subject property unless consent from the neighbour is obtained to enter their property.
- (f) The consent from Council’s Tree Management Officer must be obtained prior to the undertaking of any additional tree pruning works or pruning of any tree roots greater than 40mm in diameter.

Reason

To ensure the appropriate management and protection of Council’s street trees.

(41) SITE RECTIFICATION/HOARDING APPROVAL/THE PUBLIC WAY - PUBLIC DOMAIN DAMAGE BOND

- (a) A Public Domain Damage Deposit calculated on the basis of 98 square metres of paver and 35 square metres of asphalt site frontage must be lodged with Council in accordance with the City of Sydney’s adopted Schedule of Fees and Charges. The bond must be provided as security for repairing any damage to the public domain in the vicinity of the site.
- (b) The City’s Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The Bond must be lodged with the City prior to an approval for demolition being granted or any Construction Certificate being issued, whichever is earlier.
- (c) The bond in this condition will be released in full when the Public Domain Works Security Bond is lodged with the City.

Reason

To allow for the appropriate management and rectification of damage to the public domain.

(42) PROTECTION OF STONE KERBS

- (a) The existing stone kerbs on the Macleay Street and Hughes Street frontages of the site are to be retained and properly protected during demolition, excavation and construction works.

- (b) To avoid damage to stone kerbs during excavation and construction works for the development, temporary removal and storage of the stone kerbs may be approved by Council. Removed, serviceable stone kerbs (i.e. those that are in good condition as agreed by Council officers) must be re-installed in accordance with the City of Sydney's standard details and specifications after the construction works have been completed. A temporary concrete kerb will need to be constructed to retain the footpath until the stone kerbs can be reinstalled.
- (c) Note the following:
 - (i) all costs associated with the works are to be borne by the developer.
 - (ii) Damaged kerbs are to be replaced to match existing to Council's satisfaction or as otherwise advised by Council officers.
 - (iii) Where new vehicle crossings or temporary crossings are to be constructed to access the property, the affected kerb stones should be salvaged and reused wherever possible.
 - (iv) All new driveway laybacks and kerbs are to be constructed with stone kerbs to match existing stones or as specified by City officers.
 - (v) Council approval is required before kerbs are removed.
 - (vi) Council approval is required prior to the cutting of existing stone kerbs for stormwater kerb outlets.
 - (vii) Stone kerbs and gutters may be bonded in accordance with the City of Sydney's adopted Schedule of Fees and Charges. If so, this will be included with the Public Domain Damage Bond.

Reason

To ensure the protection of stone kerbs.

(43) SURVEY INFRASTRUCTURE – IDENTIFICATION AND RECOVERY

Under Section 24 of the Surveying and Spatial Information Act 2002, it is an offence to remove, damage, destroy, displace, obliterate or deface any survey mark unless authorised to do so by the Surveyor-General. Accordingly, the applicant must, where possible, ensure the preservation of existing survey infrastructure undisturbed and in its original state or else provide evidence of the Surveyor-General's authorisation to remove or replace marks.

Prior to the issue of any Construction Certificate, documentary evidence must be prepared by a Registered Surveyor and submitted to and approved by Council's Area Planning Manager / Coordinator. This evidence must include either:

- (a) A copy of any Surveyor-General's Approval for Survey Mark Removal granted by NSW Spatial Services for the subject site, including all documentation submitted as part of that application (for example the survey mark audit schedule, strategy plan and strategy report); or

- (b) A letter, signed by a current NSW Registered Land Surveyor and including his or her Board of Surveying and Spatial Information (BOSSI) identification number, stating that all investigations required under Surveyor-General's Direction No.11 have been made for the subject site and that no survey infrastructure will be affected by the proposal.

Council's Principal Surveyor may request further information and/or add conditions to any Surveyor-General's Approval at their discretion.

Reason

To ensure the preservation of existing survey infrastructure.

(44) PUBLIC DOMAIN LEVELS AND GRADIENTS

Prior to the issue of any Construction Certificate, a Public Domain Levels and Gradients submission for the building and site frontages must be submitted to and approved by the City's Public Domain Unit. The submission must be prepared in accordance with the City's *Public Domain Manual* and submitted with a completed Application for *Public Domain Levels and Gradients*. Information on how to complete the submission can be downloaded from the City's website at <https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

Any requirements to comply with Disability Discrimination Act at the entrance to a building or publicly accessible space must be resolved inside the site boundary.

Note: Public Domain Levels and Gradient plans are to be included with the Public Domain Plan – Detailed Documentation for Construction condition submission.

Reason

To ensure public domain levels and gradients comply with Council's requirements.

(45) DILAPIDATION REPORT - PUBLIC DOMAIN

Prior to an approval for demolition and preparatory works being granted or the issue of any Construction Certificate, whichever is earlier, a photographic recording of the public domain site frontages is to be prepared as described in the Public Domain Manual and submitted for approval by Council's Public Domain Unit. The City's *Public Domain Manual* is available for download from the City's website at <https://www.cityofsydney.nsw.gov.au/>

The submission is to include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

Reason

To establish and document the condition of the public domain for comparison as building work progresses and is completed.

(46) TEMPORARY DEWATERING DURING CONSTRUCTION

Prior to discharging any water collected during excavation and construction into the City's stormwater drainage system, approval must be sought from the City's Public Domain Unit. A dewatering management plan must be submitted with an *Application for Temporary Dewatering* available to download on the City's website.

Other options for dewatering include disposal to sewer with prior approval from Sydney Water, or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

Reason

To ensure dewatering is managed appropriately.

(47) STORMWATER AND DRAINAGE - MINOR DEVELOPMENT

The drainage system is to be constructed in accordance with the City's standard requirements as detailed in the City of Sydney's Stormwater Drainage Manual. The development is to be designed so that the flow of pollutants from the site due to stormwater is reduced.

Reason

To ensure the drainage system is constructed in accordance with Council's requirements.

(48) STORMWATER – BASEMENT PUMP TIMINGS

A note is to be included on the stormwater plan stipulating that the stormwater basement pump discharge system is subject to timed pumping between the hours of 12:00midnight and 04:00am and submitted to and approved by Council's Area Coordinator Planning Assessments / Area Planning Manager, prior to the issue of a Construction Certificate.

Reason

To ensure the drainage system is operated in accordance with Council's requirements.

(49) SWIMMING POOL SAFETY

(a) To minimise the impact of the pool on adjoining properties and to ensure the safety of the pool area, the design and construction of the swimming pool and associated equipment and fencing must comply with the following requirements:

(i) The *Swimming Pools Act 1992* and Regulations.

- (ii) The swimming pool must have safety barriers installed in accordance with the requirements of AS 1926.1 - 2007 - 'Safety barriers for swimming pools' and AS 1926.2 - 2007 'Location of safety barriers for swimming pools'.
- (iii) Australian Standards 1926.3 - Water Recirculation and Filtration; and
- (iv) *Protection of the Environment Operations Act 1997*

Reason

To minimise the impact of the pool on adjoining properties and to ensure the safety of the pool area.

(50) SWIMMING POOL - WASTE AND OVERFLOW WATERS

Swimming pool waste and overflow waters must be collected and directed to the sewer in accordance with the requirements of Sydney Water, and details are to be submitted with the application for a Construction Certificate to the satisfaction of Council or the accredited certifier and approved by the Accredited Certifier.

Reason

To ensure waste and overflow waters are managed appropriately.

(51) SWIMMING POOL - CONSULTATION WITH AUSGRID

Ausgrid must be consulted in respect to the location of the proposed swimming pool relative to any overhead electrical wiring within a distance of 9 metres around the pool. Details of consultation with Ausgrid are to be submitted to the Accredited Certifier prior to a Construction Certificate being issued.

Reason

To ensure consultation with Ausgrid is undertaken where required.

(52) MECHANICAL VENTILATION

- (a) The premises must be ventilated in accordance with the *Building Code of Australia* and *AS1668.1 and AS1668.2 - The Use of Ventilation and Air-conditioning in Buildings - Mechanical Ventilation in Buildings*.
- (b) Details of any mechanical ventilation and/or air conditioning system complying with *AS1668.1 and AS1668.2 - The Use of Ventilation and Air-conditioning in Buildings - Mechanical Ventilation in Buildings*, the *Building Code of Australia* and relevant Australian Standards must be prepared and certified in accordance with Clause A5.2(1)(e) of the *Building Code of Australia*, to the satisfaction of the Accredited Certifier prior to the issue of a Construction Certificate.
- (c) Prior to issue of any Occupation Certificate and following the completion, installation, and testing of all the mechanical ventilation systems, a Mechanical Ventilation Certificate of Completion and Performance in accordance with Clause A5.2(1)(e) of the *Building Code of Australia*, must be submitted to the Principal Certifier.

Reason

To ensure the ventilation complies with relevant standards.

(53) FUTURE FOOD USE - MECHANICAL VENTILATION PROVISION

Prior to the issue of a Construction Certificate, the mechanical exhaust systems and/or shafts must be designed to allow for the discharge of effluent air above roof level and must be designed with capacity to accommodate exhaust ducts and mechanical ventilation systems for all commercial tenancies proposed with the potential to become a food premises in future.

Systems must be designed in accordance with *AS1668.2 – The Use of Ventilation and Air-conditioning in Buildings – Mechanical Ventilation in Buildings*, and *AS1668.1 – The Use of Ventilation and Air-conditioning in Buildings – Fire and Smoke Control in Buildings*.

Reason

To ensure the mechanical ventilation complies with relevant standards.

PART C – BEFORE THE COMMENCEMENT OF BUILDING WORK

(54) DILAPIDATION REPORT – MAJOR EXCAVATION/DEMOLITION

- (a) Subject to the receipt of permission of the affected landowner, dilapidation report/s, including a photographic survey of adjoining properties (and any other properties identified by the qualified structural engineer engaged to undertake the report) are to be prepared by an appropriately qualified structural engineer prior to commencement of demolition/excavation works. A copy of the dilapidation report/s together with the accompanying photographs must be given to the above property owners, and a copy lodged with the Registered Certifier and the Council prior to the issue of a Construction Certificate.

UPON COMPLETION OF EXCAVATION/DEMOLITION

- (b) A second Dilapidation Report/s, including a photographic survey must then be submitted at least one month after the completion of demolition/excavation works. A copy of the second dilapidation report/s, together with the accompanying photographs must be given to the above property owners, and a copy lodged with the Principal Certifier and the Council prior to the issue of any Occupation Certificate.

Any damage to buildings, structures, lawns, trees, sheds, gardens and the like must be fully rectified by the applicant or owner, at no cost to the affected property owner.

Note: Prior to the commencement of the building surveys, the applicant/owner must advise (in writing) all property owners of buildings to be surveyed of what the survey will entail and of the process for making a claim regarding property damage. A copy of this information must be submitted to Council.

Reason

To ensure that dilapidation reports are prepared and to identify damage to adjoining/nearby properties resulting from building work on the development site.

(55) RODENT TREATMENT PROGRAMME – PRE DEMOLITION AND/OR EXCAVATION

- (a) Prior to the commencement of any demolition and/or excavation works, a programme of baiting and monitoring of rodent activity is to be put in place at the site.
- (b) A licensed Pest Control Operative must carry out all pest control work and prepare a report, confirming that there is no evidence of any rodent activity at the site prior to the commencement of any works on site. The report must be submitted to and be approved/endorsed by Council's Area Coordinator Planning Assessments/Area Planning Manager.

Reason

To ensure that the potential impact of rodents during the demolition, excavation and construction phase is appropriately managed.

(56) DEMOLITION, EXCAVATION AND CONSTRUCTION MANAGEMENT

- (a) Prior to the commencement of demolition and/or excavation work the following details must be submitted to and be approved by the Principal Certifier:
- (i) Plans and elevations showing distances of the subject building from the location of adjoining and common/party walls, and (where applicable) the proposed method of facade retention.
 - (ii) A Demolition Work Method Statement prepared by a licensed demolisher who is registered with the Work Cover Authority. (The demolition by induced collapse, the use of explosives or on-site burning is not permitted.)
 - (iii) An Excavation Work Method Statement prepared by an appropriately qualified person.
 - (iv) A Waste and Recycling Management Plan – Demolition and Construction for the demolition and or excavation of the proposed development. The plan is to include details of materials that will be excavated and their proposed destination or reuse.
 - (v) Plans and elevations showing the location, construction and installation of temporary site fencing and any temporary structures used in connection with the construction of the development.

Note: Temporary structures, including hoardings and scaffolding, proposed for erection on City-owned and controlled land (footways and roadways), must comply with Council's *Guidelines for Hoardings and Scaffolding* and be approved by Council under the provisions of the Local Government Act 1993 and the Roads Act 1993 prior to installation.

- (b) Such statements must, where applicable, be in compliance with AS2601-2001 Demolition of Structures, the *Work, Health and Safety Act 2011* and Regulation; Council's *Guidelines for Waste Management in New Developments 2018*, the *Waste Avoidance and Resource Recovery Act 2001*, and all other relevant acts and regulations and must include provisions for:
- (i) A Materials Handling Statement for the removal of refuse from the site in accordance with the *Waste Avoidance and Resource Recovery Act 2001*.
 - (ii) The name and address of the company/contractor undertaking demolition/excavation works.
 - (iii) The name and address of the company/contractor undertaking off site remediation/disposal of excavated materials.
 - (iv) The name and address of the transport contractor.
 - (v) The type and quantity of material to be removed from site.
 - (vi) Location and method of waste disposal and recycling.

- (vii) Proposed truck routes, in accordance with this development consent.
 - (viii) Procedures to be adopted for the prevention of loose or contaminated material, spoil, dust and litter from being deposited onto the public way from trucks and associated equipment and the proposed method of cleaning surrounding roadways from such deposits. (Note: With regard to demolition of buildings, dust emission must be minimised for the full height of the building. A minimum requirement is that perimeter scaffolding, combined with chain wire and shade cloth must be used, together with continuous water spray during the demolition process. Compressed air must not be used to blow dust from the building site).
 - (ix) Measures to control noise emissions from the site.
 - (x) Measures to suppress odours.
 - (xi) Enclosing and making the site safe.
 - (xii) Induction training for on-site personnel.
 - (xiii) Written confirmation that an appropriately qualified Occupational Hygiene Consultant has inspected the building/site for asbestos, contamination and other hazardous materials, in accordance with the procedures acceptable to SafeWork NSW.
 - (xiv) An Asbestos and Hazardous Materials Clearance Certificate by a person approved by the SafeWork NSW.
 - (xv) Disconnection of utilities.
 - (xvi) Fire Fighting. (Fire fighting services on site are to be maintained at all times during demolition work. Access to fire services in the street must not be obstructed).
 - (xvii) Access and egress. (Demolition and excavation activity must not cause damage to or adversely affect the safe access and egress of the subject building or any adjacent buildings).
 - (xviii) Waterproofing of any exposed surfaces of adjoining buildings.
 - (xix) Control of water pollution and leachate and cleaning of vehicles tyres (proposals must be in accordance with the *Protection of the Environmental Operations Act 1997*).
 - (xx) Working hours, in accordance with this development consent.
 - (xxi) Any SafeWork NSW requirements.
- (c) The approved work method statements and a waste management plan as required by this condition must be implemented in full during the period of construction.
 - (d) All waste records from the recycling and/or disposal of any demolition and construction waste generated from the works must be retained on site.

These records must be available for sighting on request by an authorised Council officer.

Reason

To ensure that impacts arising from demolition, excavation and construction are appropriately managed.

(57) SURVEY

All footings, walls and floor slabs adjacent to a boundary must be set out by a registered surveyor. On commencement of brickwork or wall construction a survey and report, prepared by a Registered Surveyor, must be submitted to the Principal Certifier indicating the position of external walls in relation to the boundaries of the allotment. Any encroachments by the subject building over adjoining boundaries or roads must be removed prior to continuation of building construction work.

Reason

To ensure the development does not encroach onto neighbouring properties.

(58) APPLICATION FOR HOARDINGS AND SCAFFOLDING INSTALLED ON OR ABOVE A PUBLIC ROAD AND OPERATING HOISTING DEVICES INCLUDING BUILDING MAINTENANCE UNITS OVER A PUBLIC ROAD

- (a) Where a hoarding and/or scaffolding (temporary structures) are proposed to be installed on or above a road reservation (footway and/or roadway), a separate application under Section 68 of the *Local Government Act 1993* and Sections 138/139 of the *Roads Act 1993* must be submitted to and approved by Council for such structures.
- (b) Where an approval (Permit) is granted allowing the placement of temporary structures on or above a public road the structures must comply fully with Council's *Hoarding and Scaffolding Policy; Guidelines for Hoardings and Scaffolding*; and the conditions of approval (Permit) granted including:
 - (i) maintaining a current and valid approval for the full duration that the temporary structure/s is in place;
 - (ii) maintaining temporary structure/s in a structurally sound and stable condition for the full duration of installation (Clause 2.11.1);
 - (iii) bill posters and graffiti being removed within 24 hours of their placement (Clause 2.11.2);
 - (iv) maintaining temporary structures and the public place adjoining the work site in a clean and tidy condition including repainting and/or repair of graphics (Clauses 2.11.1, 2.11.4, 2.14.1 and 3.9.3);
 - (v) maintaining a watertight deck (Type B hoardings) to prevent liquids including rainwater, falling onto the footway/roadway surfaces (Clauses 3.9.1 and 3.9.4);

- (vi) approved site sheds on the decks of a Type B hoarding being fully screened from the public place (Clause 3.9.5);
- (vii) material and equipment not being placed or stored on the deck of Type B hoardings, unless specifically approved by Council (Clause 3.9.4);
- (viii) providing and maintaining operational artificial lighting systems under Type B hoardings including at high-bay truck entry points (Clause 3.9.9); and
- (ix) ensuring all required signage, artwork or historic images are provided and fully maintained to the City's requirements (Clauses 3.4, 3.9.3, 3.9.6, 3.9.8, 3.10.1 and 4.2).

If it is proposed to operate a hoisting device including a building maintenance unit above a public road which swings, hoists material/equipment and/or slews/wind vanes any part of the device over the public road, a separate application under Section 68 of the *Local Government Act 1993* and Sections 138/139 of the *Roads Act 1993* must be made to Council to obtain approval.

Note: 'Building maintenance unit' means a power-operated suspended platform and associated equipment on a building specifically designed to provide permanent access to the faces of the building for maintenance (*Work Health and Safety Regulation 2017*).

Reason

To ensure the necessary approval is obtained for temporary structures over a public road.

(59) HAZARDOUS MATERIALS SURVEY REQUIRED

A Hazardous Materials Survey Report must be prepared by a certified Occupational Hygienist (*Australia Institute of Occupational Hygienists*) and submitted to the satisfaction of Council's Area Coordinator Planning Assessments / Area Planning Manager prior to any demolition / refurbishment work commencing at the site. The report must identify and record the type, location and extent of any hazardous materials on the site and make recommendations as to their safe management and/or removal to ensure the site is made safe for demolition, construction and future use/occupation.

Reason

To ensure that hazardous materials on the site are identified and appropriately managed.

(60) PUBLIC DOMAIN WORK – CONSTRUCTION APPROVAL UNDER SECTION 138 ROADS ACT 1993

Prior to the construction of any public domain works, approval under Section 138 / 139 of the *Roads Act 1993* must be issued by the City's Public Domain Unit.

Reason

To ensure relevant approvals for public domain work are obtained.

PART D – WHILE BUILDING WORK IS BEING CARRIED OUT

(61) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.
- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on-site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Team, prior to works proceeding

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

Reason

To protect the amenity of the surrounding area.

(62) COMPLIANCE WITH DEMOLITION, EXCAVATION & CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN

- (a) All works conducted on site which form part of this development must be carried out in accordance with the submitted Demolition, Excavation and Construction Management Plan.

- (b) Where all such control measures have been implemented and the resultant noise and/ or vibration levels at any sensitive receiver still exceed the council's applicable criteria stated in the Construction Hours/Noise Code 1992 and are giving rise to sustained complaints then the contractor must provide regular, appropriate and sustained periods of respite in consultation with Council's Health and Building unit. Approval to vary the authorised noise and vibration levels must be received in writing by the proponent from Council prior to activities being undertaken that exceed sanctioned emission levels. (Use where respite periods not specified under the approved DEC NMP)

Such periods must be set and agreed to by Council's Health and Building Unit.

Reason

To ensure all parties are aware of the supporting documentation that applies to the development.

(63) ASBESTOS REMOVAL WORKS

- (a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence must be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.
- (c) All work must be carried out in accordance with the *Work Health and Safety Regulation 2017* and the NSW Government and SafeWork NSW document entitled *How to manage and control asbestos in the work place: Code of Practice (Safework NSW) December 2011* and the *City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines*.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.

- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 -1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.
- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).
- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.
- (i) A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

Reason

To ensure that the handling and removal of asbestos from the site is appropriately managed.

(64) NOTIFICATION NEW CONTAMINATION EVIDENCE

Council's Area Planning Manager and the Principal Certifier must be notified of any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination.

Reason

To ensure that the site is appropriately remediated.

(65) IMPORTED FILL MATERIALS

All fill imported onto the site must be validated to ensure the imported fill is suitable for the proposed land use from a contamination perspective. Fill imported on to the site shall also be compatible with the existing soil characteristic for site drainage purposes.

The City may require details of appropriate validation of imported fill material to be submitted with any application for future development of the site. Hence all fill imported onto the site should be validated by either one or both of the following methods during remediation works:

- (a) Imported fill must be accompanied by documentation from the supplier which certifies that the material is not contaminated based upon analyses of the material for the known past history of the site where the material is obtained; and/or
- (b) Sampling and analysis of the fill material shall be conducted in accordance with NSW EPA (1995) Sampling Design Guidelines.

Reason

To ensure that imported fill is not contaminated.

(66) CLASSIFICATION OF WASTE

Prior to the exportation of waste (including fill or soil) from the site, the waste materials must be classified in accordance with the provisions of the Protection of the *Environment Operations Act 1997* and the *NSW DECC Waste Classification Guidelines, Part 1: Classifying Waste (July 2009)*. The classification of the material is essential to determine where the waste may be legally taken. The *Protection of the Environment Operations Act 1997* provides for the commission of an offence for both the waste owner and the transporters if the waste is taken to a place that cannot lawfully be used as a waste facility for the particular class of waste. For the transport and disposal of industrial, hazardous or Group A liquid waste advice should be sought from the EPA.

Reason

To ensure that waste from site is classified and disposed of appropriately.

(67) PUBLIC DOMAIN WORKS SECURITY BOND

A Public Domain Works Security Bond will be required for the public domain works and for repairing damage that may be caused to the public domain in the vicinity of the site, in accordance with the City of Sydney's adopted fees and charges and the Public Domain Manual.

The City's Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The bond must be lodged with the City prior to an approval being issued for the approval of the Public Domain Plan.

The bond will be retained in full until all public domain works, including rectification of damage to the public domain, are completed to City's standards and approval and the required works-as-executed documentation are approved. On satisfying the above requirements, and the issue of the Public Domain Works Letter of Completion Operational Acceptance by the City, 90% of the bond will be released. The remaining 10% will be retained for the duration of the specified Defects Liability Period.

Reason

To ensure public domain works are completed and any damage to the public domain is rectified.

(68) DRAINAGE AND SERVICE PIT LIDS

All existing or proposed drainage and service pit lids throughout the public domain must be to City of Sydney specifications and heel/bicycle safe, slip resistant, infill with material to match surrounding surface, finished flush with the adjacent pavement to avoid trip hazards and be clear of obstructions for easy opening and cleaning. Infill pit lids are to be detailed where specified by Council's Public Domain Officer. Private pits are not permitted within the public domain. All details of pit lids must be shown on the public domain plan and must be approved by the City's Public Domain Unit prior to the issue of an approval for public domain works.

Reason

To ensure drainage and service pit lids within the public domain are appropriately designed and installed.

(69) PUBLIC DOMAIN PLAN DETAILED DOCUMENTATION FOR CONSTRUCTION

A detailed public domain plan and all relevant documentation must be submitted to and approved by City's Public Domain Unit prior to the construction of any public domain works. This Plan must document all works required to ensure that the public domain complies with the City of Sydney's *Public Domain Manual, Sydney Streets Code, Sydney Street Tree Masterplan, Sydney Lights Design Code and Sydney Streets Technical Specification*. The documentation must be *checked, accurate, and comply with specified requirements*. Plans must be based on an accurate survey, to scale and fully coordinated across all disciplines and submissions. The supplied documentation must be for Construction issue and will be approved under Section 138 of the Roads Act.

The Public Domain Manual and all other relevant documents are available for download from Council's website at:

<https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

The Public Domain Plan documentation must be submitted with an Application for Public Domain Plan Assessment and include the approved Public Domain Levels and Gradients documentation. If the proposed detailed design of the public domain requires changes to any previously approved levels an Application for Public Domain Levels and Gradients must be submitted to and approved by the City's Public Domain Unit to reflect these changes prior to an approval being issued for the construction of public domain work.

Reason

To ensure the public domain complies with Council's requirements.

(70) HOLD POINTS

Prior to an approval being issued for the construction of public domain and / or planning agreement works, including civil, drainage and subsurface works, a set of hold points will be provided by the City's Public Domain Unit in accordance with the City's Public Domain Manual and Sydney Streets Technical Specification. The list of hold point inspections will be included in the Public Domain works approval letter.

These hold point inspections must be adhered to during construction works. Prior to the issue of any Occupation Certificate, confirmation from the City's Public Domain Unit, that hold point inspections have been completed and works have been accepted by the City must be provided to the Principal Certifier.

Reason

To ensure hold points are adhered to during construction works.

(71) USE OF HIGH NOISE EMISSION APPLIANCES / PLANT

- (a) The operation of high noise emission appliances, plant and/or machinery such as pile – drivers, rock breakers and hydraulic hammers and those which are not listed in Groups B, C, D, E or F of Schedule 1 of the *City of Sydney Code of Practice for Construction Hours/Noise 1992* and Australian Standard 2436-2010 *Guide to Noise Control on Construction, Maintenance and Demolition Sites* is restricted to the hours of (EHO to specify hours)
- (b)
 - (i) Monday to Friday – 9:00am to 12:30pm and 2:00pm to 4:30pm;
 - (ii) Saturday – 9:00am to 1:00pm; and
 - (iii) Sunday and Public Holidays – No works.
- (c) All reasonable and feasible steps must be undertaken to ensure that the work, including demolition, excavation and building complies with the *City of Sydney Code of Practice for Construction Hours/Noise 1992* and Australian Standard 2436- 2010 *Guide to Noise Control on Construction, Maintenance and Demolition Sites*.

Reason

To protect the amenity of the surrounding area.

(72) NOTIFICATION OF EXCAVATION WORKS OR USE OF HIGH NOISE EMISSION APPLIANCES/PLANT

The immediately adjoining neighbours must be given a minimum of 48 hours notice that excavation, shoring or underpinning works or use of high noise emission appliances / plant are about to commence.

Reason

To protect the amenity of the surrounding area.

(73) HAZARDOUS AND INDUSTRIAL WASTE

Hazardous and/or industrial waste arising from the demolition/operational activities must be removed and/or transported in accordance with the requirements of the NSW Work Cover Authority pursuant to the provisions of the following:

- (a) *Protection of the Environment Operations Act 1997*
- (b) *Protection of the Environment Operations (Waste) Regulation 2005*
- (c) *Waste Avoidance and Resource Recovery Act 2001*
- (d) *Work Health and Safety Act 2011*
- (e) *Work Health and Safety Regulation 2017.*

Reason

To ensure hazardous/ industrial waste is managed appropriately.

(74) LOADING AND UNLOADING DURING CONSTRUCTION

The following requirements apply:

- (a) All loading and unloading associated with construction activity must be accommodated on site, where possible.
- (b) If, it is not feasible for loading and unloading to take place on site, a Works Zone on the street may be considered by Council.
- (c) A Works Zone may be required if loading and unloading is not possible on site. If a Works Zone is warranted an application must be made to Council at least 8 weeks prior to commencement of work on the site. An approval for a Works Zone may be given for a specific period and certain hours of the days to meet the particular need for the site for such facilities at various stages of construction. The approval will be reviewed periodically for any adjustment necessitated by the progress of the construction activities.
- (d) Where hoisting activity over the public place is proposed to be undertaken including hoisting from a Works Zone, a separate application under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993 must be submitted to and approved by Council.

Reason

To protect the amenity of the public domain.

(75) NO OBSTRUCTION OF PUBLIC WAY

Unless otherwise approved by Council, the public way must not be obstructed by any materials, vehicles, waste receptacles, skip-bins or the like. Non-compliance with this requirement may result in the issue of a notice by Council to stop all work on the site.

Reason

To protect the amenity of the public domain.

(76) USE OF MOBILE CRANES

The following requirements apply:

- (a) Mobile cranes operating from the road must not be used as a method of demolishing or constructing a building.
- (b) For special operations including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes, permits must be obtained from Council for the use of a mobile crane. The permits must be obtained 48 hours beforehand for partial road closures which, in the opinion of Council will create minimal traffic disruptions and 4 weeks beforehand in the case of full road closures and partial road closures which, in the opinion of Council, will create significant traffic disruptions.
- (c) The use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on site tower cranes which warrant the on-street use of mobile cranes outside of approved hours of construction can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Reason

To ensure mobile cranes are used appropriately.

(77) STREET TREE PROTECTION

All street trees located directly outside the site must be retained and protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites. All street trees must be protected during the construction works as follows:

- (a) Tree trunk and major branch protection must be undertaken prior to the commencement of any works (including demolition). The protection must be installed and certified by an arborist with a minimum AQF Level 5 qualification in arboriculture and must include:
 - (i) An adequate clearance, minimum 250mm, must be provided between the structure and tree branches, and trucks at all times.
 - (ii) Tree trunk/s and/or major branches to a height of two metres, must be protected by wrapped thick underlay carpet or similar padding material to limit damage, and

- (iii) Timber planks (50mm x 100mm or similar) must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals and must be fixed against the trunk with tie wire, or strapping. The thick underlay carpet or similar padding material and timber planks must not be fixed to the tree in any instance, or in any fashion.
- (iv) Tree trunk and major branch protection is to remain in place for the duration of construction and development works and must be removed at the completion of the project.
- (b) Temporary signs, or any other items, shall not be fixed or attached to any street tree.
- (c) All hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree pits. Supporting columns must not be placed on any tree roots that are exposed.
- (d) Young street trees must be protected by installing three (3) wooden stakes around the edge of the tree pits or a minimum of 1 metre from the base of the trunk. Hessian must be wrapped around the stakes. If existing stakes or a metal tree guard are already in place, these suffice as tree protection.
- (e) Materials or goods, including site sheds, must not be stored or placed:
 - (i) around or under the tree canopy; or
 - (ii) within two (2) metres of tree trunks or branches of any street trees.
- (f) Any excavation within any area known to or suspected of having tree roots greater than 30mm diameter must be undertaken by hand.
- (g) Any trenching works for services, hydraulics, drainage etc. must not be undertaken within [specify] metres of the trunk of any street tree. Alternate installation methods for services such as directional boring/drilling or redirection of services must be employed where roots greater than 30mm diameter are encountered during installation of any services.
- (h) Existing sections of kerbs adjacent to any street tree must not be removed without approval from the Council's Tree Management Officer.
- (i) Any damage sustained to street tree/s as a result of the erection of any construction activities (including demolition) must be immediately reported to the Council's Tree Management Officer on 9265 9333. Any damage to street trees as a result of any construction activities may result in prosecution under the Local Government Act 1993 and the Environmental Planning and Assessment Act 1979.

Reason

To ensure the protection and ongoing health of the street trees.

PART E – BEFORE THE ISSUE OF AN OCCUPATION CERTIFICATE

(78) COMPLIANCE WITH HAZARDOUS MATERIALS SURVEY REPORT

All of the recommendations for management and/or removal of hazardous materials on the site, as outlined in the Hazardous Materials Survey Report, as approved must be complied with.

Prior to the issue of any Occupation Certificate, certification must be submitted to the Principal Certifier from a certified Occupational Hygienist (*Australia Institute of Occupational Hygienists*) confirming that all hazardous materials identified have been contained, managed or removed in accordance with the recommendations given in the approved Hazardous Materials Survey Report and that the site is safe for future occupation in accordance with the approved use.

Reason

To ensure that hazardous materials on the site are appropriately managed.

(79) ADVANCE TREE PLANTING

Tree planting within the property must be undertaken in accordance with the following conditions, and to Council's satisfaction, prior to the issuing any Occupation Certificate.

- (a) All new tree planting shall be undertaken in accordance with the approved Landscape Plans.
- (b) The tree must be grown in accordance with the Australian Standard 2303 'Trees stock for landscape use'.
- (c) At the time of planting, the container size is to be a minimum of 100 litres.
- (d) The tree must be planted by a qualified Horticulturalist or Arborist of Level 3 under the Australian Qualifications Framework (AQF).
- (e) The tree must be planted in such a manner as to promote good health during the establishment period, and must be maintained, as far as practicable to ensure tree growth into maturity.
- (f) Prior to the issue of any Occupation Certificate, suitable documentation (including a written statement and photographic evidence) is to be submitted to Council for review and written confirmation is to be obtained from Council's Area Planning Coordinator | Area Planning Manager confirming all trees have been planted to Council's satisfaction (excluding tree maintenance).
- (g) Any newly planted tree that fails to establish within 2 years of the initial planting date must be replaced with a tree of comparable qualities.

Reason

To ensure the provision and maintenance of adequate tree planting on site.

(80) PUBLIC DOMAIN WORKS COMPLETION

The Public Domain works are to be constructed in accordance with the Public Domain Works Approval letter, stamped plans for Public Domain Levels and Gradients, Stormwater, Public Domain Lighting, the City's *Public Domain Manual*, *Stormwater Drainage Manual*, *Sydney Lights Design Code* and *Sydney Streets Technical Specification*.

The public domain work must be inspected and a Public Domain Work Letter of Completion Operational Acceptance must be issued by Council's Public Domain Officer prior to the issue of any Occupation Certificate or before the commencement of use, whichever is earlier.

Reason

To ensure the public domain works are completed in accordance with the approved documents and Council's requirements.

(81) PUBLIC DOMAIN COMPLETION – WORK AS EXECUTED DOCUMENTATION

Prior to a Public Domain Works Letter of Completion Operational Acceptance being issued for public domain works, works-as-executed (As-Built) plans and documentation, must be submitted to and accepted by the City of Sydney for all public domain works, including where required Stormwater, Public Domain Lighting and road construction. These works must be certified by a suitably qualified, independent professional. Details of the documentation required for approval will be advised by the City's Public Domain Unit.

Reason

To ensure Council receives works-as-executed documentation for public domain works.

(82) SURVEY INFRASTRUCTURE – RESTORATION

- (a) Prior to any Occupation Certificate being issued for the development, documentary evidence of restoration must be prepared by a Registered Surveyor and submitted to and approved by Council's Area Planning Manager / Coordinator. This evidence must include:
 - (i) Certification that all requirements requested under the Surveyor-General's Approval for Survey Mark Removal or by the City's Principal Surveyor under condition "Survey Infrastructure – Identification and Recovery" have been complied with;
 - (ii) Certification that all requirements requested under any Surveyor-General's Approval for Deferment of Survey Marks from condition "Survey Infrastructure – Pre Subdivision Certificate works" have been complied with and;
 - (iii) Time-stamped photographic records of all new survey infrastructure relating to the site clearly showing the mark itself and sufficient context to aid in identifying the mark on site.

Reason

To ensure all requirements for survey mark removal are complied with.

(83) BASIX

All commitments listed in each relevant BASIX Certificate for the development must be fulfilled prior to any Occupation Certificate being issued.

Reason

To ensure BASIX commitments are fulfilled in accordance with the BASIX certificate (prescribed condition under clause 97A(2) EP&A Regulation).

(84) SYDNEY WATER CERTIFICATE

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Coordinator. Please refer to the Building Developing and Plumbing section on the web site www.sydneywater.com.au then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Coordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

The Section 73 Certificate must be submitted to Council or the Principal Certifier prior to any Occupation Certificate or subdivision/strata certificate being issued.

Reason

To ensure the requirements of Sydney Water are met.

(85) PHYSICAL MODELS

- (a) Prior to the issue of any Occupation Certificate an accurate 1:500 scale model of the development as constructed must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the City Model in Town Hall House.

Note:

- (i) The models must be constructed in accordance with the Model Specifications available online at <http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements> Council's modellers must be consulted prior to construction of the model.
- (ii) The models are to comply with all of the conditions of the Development Consent.

- (iii) The models must be amended to reflect any further modifications to the approval (under Section 4.55 of the *Environmental Planning and Assessment Act*) that affect the external appearance of the building.

Reason

To ensure the provision of an appropriate physical model of the development.

(86) SUBMISSION OF ELECTRONIC CAD MODELS PRIOR TO OCCUPATION CERTIFICATE

- (a) Prior to any Occupation Certificate being issued, an accurate 1:1 electronic CAD model of the completed development must be submitted to and approved by Council's Area Coordinator Planning Assessments/Area Planning Manager for the electronic Visualisation City Model.
- (b) The data required to be submitted within the surveyed location must include and identify:
 - (i) building design above and below ground in accordance with the development consent;
 - (ii) all underground services and utilities, underground structures and basements, known archaeological structures and artefacts;
 - (iii) a current two points on the site boundary clearly marked to show their Northing and Easting MGA (Map Grid of Australia) coordinates, which must be based on Established Marks registered in the Department of Lands and Property Information's SCIMS Database with a Horizontal Position Equal to or better than Class C.

The data is to be submitted as a DGN or DWG file on a Compact Disc. All modelling is to be referenced to the Map Grid of Australia (MGA) spatially located in the Initial Data Extraction file.

- (c) The electronic model must be constructed in accordance with the City's 3D CAD electronic model specification. The specification is available online at <http://www.cityofsydney.nsw.gov.au/development/application-guide/application-process/model-requirements> Council's Modelling staff should be consulted prior to creation of the model. The data is to comply with all of the conditions of the Development Consent.

Reason

To ensure the provision of an appropriate electronic model of the development.

(87) SURVEY CERTIFICATE AT COMPLETION

A Survey Certificate prepared by a Registered Surveyor must be submitted to the Principal Certifier at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

Reason

To ensure the development does not encroach onto neighbouring properties.

PART F – OCCUPATION AND ONGOING USE

(88) OCCUPATION CERTIFICATE TO BE SUBMITTED

An Occupation Certificate must be obtained from the Principal Certifier and a copy submitted to Council prior to commencement of occupation or use of the whole or any part of a new building, an altered portion of, or an extension to an existing building.

Reason

To ensure the site is authorised for occupation.

(89) NO MUSIC OR SPEAKERS OUTSIDE

Speakers and/or noise amplification equipment must not be installed and music must not be played in any of the outdoor areas associated with the premises including the public domain. Speakers located within the premises must not be placed so as to direct the playing of music towards the outdoor areas associated with the premises.

Reason

To safeguard the amenity of the surrounding neighbourhood.

(90) NOISE – COMMERCIAL PLANT / INDUSTRIAL DEVELOPMENT

- (a) Noise from commercial plant and industrial development must not exceed a project amenity/intrusiveness noise level or maximum noise level in accordance with relevant requirements of the NSW EPA [Noise Policy for Industry 2017 \(NPfI\)](#) unless agreed to by the City's Area Planning Manager. Further:
 - (i) Background noise monitoring must be carried out in accordance with the long-term methodology in [Fact Sheet B](#) of the NPfI unless otherwise agreed by the City's Area Planning Manager.
 - (ii) Commercial plant is limited to heating, ventilation, air conditioning, refrigeration and energy generation equipment.
- (b) An $L_{Aeq,15 \text{ minute}}$ (noise level) emitted from the development must not exceed the $L_{A90, 15 \text{ minute}}$ (background noise level) by more than 3dB when assessed inside any habitable room of any affected residence or noise sensitive commercial premises at any time. Further:
 - (i) The noise level and the background noise level must both be measured with all external doors and windows of the affected residence closed.
 - (ii) Background noise measurements must not include noise from the development but may include noise from necessary ventilation at the affected premise.

- (c) Corrections in [Fact Sheet C](#) of the NPfI are applicable to relevant noise from the development measured in accordance with this condition, however duration corrections are excluded from commercial noise.

Reason

To protect the acoustic amenity of surrounding properties.

(91) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS

All works to the City's public domain, including rectification of identified defects, are subject to a 6 month defects liability period from the date of Completion. The date of Completion will be nominated by Council on the Public Domain Works – Letter of Completion Operational Acceptance.

Reason

To ensure all works to the City's public domain are protected under a liability period.

(92) ENCROACHMENTS – NEIGHBOURING PROPERTIES

No portion of the proposed structure shall encroach onto the adjoining properties.

Reason

To protect neighbouring properties.

(93) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

Reason

To protect the public way.

(94) USE OF COMMON AREAS AND FACILITIES

The rooftop communal open space must be available for the use all residents of the building and must be designated as common property on any strata subdivision of the site, with no exclusive use rights.

The rooftop communal open space must not be accessed between the hours of 10:00pm and 06:00am. Signage should be installed outlining the operating hours.**Reason**

To ensure designated areas within the residential development are maintained as common property.

SCHEDULE 2

PRESCRIBED CONDITIONS

The prescribed conditions in accordance with Division 8A of the *Environmental Planning and Assessment Regulation 2021* apply:

- Clause 69 Compliance with *National Construction Code (previously known as Building Code of Australia)* and insurance requirements under the *Home Building Act 1989*
- Clause 70 Erection of signs
- Clause 71 Notification of *Home Building Act 1989* requirements
- Clause 72 Conditions relating to entertainment venues
- Clause 73 Conditions relating to maximum capacity signage
- Clause 74 Conditions relating to shoring and adequacy of adjoining property

Refer to the NSW State legislation for full text of the clauses under Division 2 conditions of development consent of the *Environmental Planning and Assessment Regulation 2021*. This can be accessed at: <http://www.legislation.nsw.gov.au>