

Traffic Control Plan




Date: 7/5/2024 **Author:** Ali Fayad **Project:** 76 Forbes St, Woolloomooloo NSW 2011
Client: St Vincent de Paul, Ozanam Learning Centre **Contact:** Thor Blomfield **Plan #:** RC.TW02.23
PWZTMP: 1011477 **Number:** 0406 718 492

Comments:
 This plan has been designed by Ali Fayad of Sydney Traffic Control in accordance with Australian Standards outlined in the RMS's Traffic Control on Worksites Handbook which complies with AS1742.3 and Transport for NSW's "Traffic Control at Worksites" manual.
 This plan has been designed using Australian standards under the advice and activity information provided by the above mentioned client. Sydney Traffic will take no responsibility for the implementation of this TCP or it's impact on the area/road where it is to be implemented, Unless and only if Sydney Traffic employees are the principal onsite Traffic Controllers and will only be responsible during the agreed work times.
 The plan has been designed for the Community St Vincent de Paul, Ozanam Learning Centre event walking parade for the local people in a closed off section of Woolloomooloo in a car park in front of property 76 Forbes St, Woolloomooloo NSW 2011.
 Certified traffic controllers will be on site to implement and monitor this TCP. If you have any questions please contact Ali Fayad on 8068-1844 or 0451 153 044.

- A minimum of 3.5 Metres must be kept at all times for Traffic to pass through Work Zone Safely.
- Traffic Control Must be on site at all times to assist pedestrians across the road and past the work zone safely.
- Traffic Control Must find a suitable Gap in Between traffic to allow the Trucks to Egress.
- Road/Footpath MUST be REINSTATED back to NORMAL conditions after Business hours and 3.5 Metres MUST BE MAINTAINED AT ALL TIMES after work hours
- Pedestrians MUST NEVER WALK ON ANY PART OF THE ROAD OR THE PARKING LANE AT ANY GIVEN TIME DURING WORK HOURS OR AFTER HOURS WITHOUT TRAFFIC CONTROL ON SITE.
- FOOT PATH MUST ALWAYS REMAIN OPEN AFTER HOURS WITH PEDESTRSIN RAMP INSTALLED AND START PICKETS WITH BUNDING WIRE.

Legend

- Bollard
- North Arrow
- Pedestrian route
- Pedestrian Tape
- Site Location
- Surrounding Property's
- Traffic Controller
- Work Area



Foot Path/Road MUST be REINSTATED back to NORMAL conditions after conclusion of work hours and 1.5 Metres MUST BE MAINTAINED AT ALL TIMES after work times for pedestrians to walk past the job safely

