

Attachment A

Recommended Conditions of Consent

Terms and Reasons for Conditions

Under section 88(1)(c) of the EP&A Regulation, the consent authority must provide the terms of all conditions and reasons for imposing the conditions other than the conditions prescribed under section 4.17(11) of the EP&A Act. The terms of the conditions and reasons are set out below.

GENERAL CONDITIONS

(1) APPROVED DEVELOPMENT

- (a) Development must be in accordance with Development Application No. D/2023/894 dated 10 October 2023 and the following drawings prepared by Cracknell & Lonergan and Conzept Landscape Architects:

Drawing Number	Drawing Name	Date
DA-B 003	Existing Plan & Demolition Plan	29/04/2024
DA -B 101	Floor Plans	29/04/2024
DA -B 102	Roof Plan	29/04/2024
DA -B 201	Elevation & Sections	29/04/2024
DA -B 401	Materials and Finishes	29/04/2024
DA -B 601	Additional Details	29/04/2024
LPDA 24-15 - Sheet 2 – Issue F	Hardscape Plan	May 2024
LPDA 24-15 - Sheet 2 – Issue F	Landscape Plan	May 2024
LPDA 24-15 – Sheet 3 – Issue F	Elevations	May 2024
LPDA 24-15 – Sheet 4 – Issue E	Details	May 2024
LPDA 24-15 – Sheet 5 – Issue F	Details	May 2024
LPDA 24-15 – Sheet 6 – Issue E	Specifications	May 2024

and as amended by the conditions of this consent.

- (b) In the event of any inconsistency between the approved plans and supplementary documentation, the drawings will prevail.

Reason

To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

(2) COMPLIANCE WITH SUBMITTED MATERIALS AND SAMPLES BOARD

The design details of the proposed building facade including all external finishes, colours and glazing must be in accordance with the materials schedule and sample board, and specifications prepared by Cracknell and Lonergan dated 29/04/2024.

Reason

To ensure all parties are aware of the approved materials and finishes that apply to the development.

(3) VEHICLE FOOTWAY CROSSING

A separate application is to be made to, and approved by, Council for the construction of any proposed vehicle footway crossing or for the removal of any existing crossing and replacement of the footpath formation where any such crossings are no longer required.

All disused or redundant vehicle crossings and laybacks must be removed and footway, kerb, gutter and road restoration reinstated in accordance with Council's standards, to suit the adjacent finished footway and edge treatment materials, levels and details, or as otherwise directed by Council officers. All construction and replacement works are to be completed in accordance with the approved plans prior to the occupation or use.

Note: In all cases the construction materials should reinforce the priority of pedestrian movement over that of the crossing vehicle.

Reason

To ensure all relevant approvals for traffic and parking works are obtained and designed in accordance with Council requirements.

(4) ASSOCIATED ROADWAY COSTS

All costs associated with the construction and rectification of any new road works including kerb and gutter, road pavement, drainage system and footway shall be borne by the developer. The new road works must be designed and constructed in accordance with the City's "Sydney Streets Technical Specification and Standard Drawings" including amendments and "Sydney Streets Design Code".

Reason

To ensure all roadway works are designed and constructed in accordance with Council requirements.

(5) GENERAL HERITAGE

- (a) The proposed works are to be carried out in a manner that minimises demolition, alterations and new penetrations/fixings to the significant fabric of the existing building which is listed as a Heritage Item.
- (b) The fabric and features to be retained by the proposal must be properly protected during the process of demolition and construction.
- (c) All conservation and adaptation works are to be in accordance with the Articles of the Australian ICOMOS Burra Charter 2013.
- (d) New services to the original villa are to be installed with minimal impact on significant fabric and spaces. Where possible new services are to use existing service runs.
- (e) Appropriately qualified tradespersons (as appropriate) are to be commissioned who are skilled in traditional building and engineering trades to carry out the proposed scope of works.
- (f) The decorative arch in the central hallway of the villa is to be retained and conserved.
- (g) New external roof cladding to the villa and the proposed addition is to be of a corrugated metal profile.

Reason

To ensure that the development does not result in adverse heritage impacts.

(6) BRIEFING OF CONTRACTORS AND SUBCONTRACTORS

All contractors and subcontractors involved in the construction works are to be briefed on the heritage significance of the existing building on site prior to the work commencing. This is to form part of the on-site induction programme for all workers on the site.

Reason

To ensure that construction workers are aware of the significance of the site.

(7) SWINGING DOORS OVER PUBLIC WAY

Any access doors to enclosures housing building services and facilities, such as hydrant and sprinkler booster assemblies or the like, must not open over the footway/roadway.

Reason

To ensure no element of the development obstructs the use of the public way.

(8) AIR CONDITIONERS GENERALLY

No air-conditioning equipment is to be visible from the public domain. Equipment and associated wiring must:

- (a) Not be located on awnings or attached to the face of the building
- (b) Not be located on roofs in such a way that it is visible from any street, footpath or park
- (c) Be visually screened if located 1.8 metres above ground level in other locations
- (d) Wiring must be fully concealed.

Reason

To ensure the visual impact of air conditioners is minimised.

(9) NO OBSTRUCTIONS

All public footways and paths of travel must be free from obstructions. If services are required to be relocated to clear paths of travel then this must be undertaken at the developer's expense. All obstructions are to be removed prior to occupation or use.

Reason

To ensure there are no obstructions on public footways and paths of travel.

(10) NO AIR CONDITIONING UNITS TO FACADE OR BALCONIES OF BUILDING

Approval is not granted for the installation of individual air conditioning units to the facade or balconies of the building.

Reason

To clarify the scope of the consent.

(11) TREES THAT MUST BE RETAINED

The existing trees detailed in Table 2 below be retained and protected in accordance with the conditions throughout construction and development.

Table 2 – Tree Retention:

Approval is NOT granted for the removal of the following trees, which Council has determined to be prominent landscape elements.

Tree No	Species:	Location
1	Jacaranda mimosifolia (Jacaranda)	Neighbouring property - Rear southern boundary corner
3	Magnolia grandiflora (Southern Bay Magnolia)	Front Yard - form part of front gardens
9	Populus simonii (Simon's Poplar)	Street tree - front

Reason

To identify the trees that cannot be removed, must be retained and protected.

(12) TREES APPROVED FOR REMOVAL

- (a) All trees detailed in Table 1 below are approved for removal. Tree removal must not occur until Certification (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979) has been issued.

Table 1 – Tree Removal:

Tree No	Species:	Location
2	Magnolia grandiflora (Southern Bay Magnolia)	Front Yard - form part of front gardens
4-6	Camellia sasanqua (Sasanqua Camellia)	Front Yard - form part of front gardens
7	Cuppressus leylandii (Leighton's Green)	Front Yard - form part of front gardens
8	Celtis Sinensis (Chinese Hackberry)	Front Yard - form part of front gardens

- (b) All tree removal works must be carried out by an arborist with a minimum AWF Level 3 qualification in arboriculture in accordance with SafeWork's Code of Practice – Amenity Tree Industry.

Reason

To identify the trees that can be removed.

(13) WASTE AND RECYCLING MANAGEMENT - GENERAL

The proposal must comply with the relevant provisions of Council's *Guidelines for Waste Management in New Developments 2018* which requires facilities to promote the efficient storage, separation, collection and handling of waste to maximise resources recovery.

Reason

To ensure that waste and recycling is appropriately managed.

(14) OSD TANK TREE PROTECTION

Should any large roots from Tree 3 with a diameter equal to or greater than 40mm require removal during the excavation/installation of the OSD tank in the front yard, works relating to the OSD tank are to cease and the excavation/installation of the OSD must be carried out in accordance with Council's direction.

Reason

To ensure the installation of the OSD tank does not impact the ongoing health of Tree 3.

BUILDING WORK

PRIOR TO CERTIFICATION BEING ISSUED (PURSUANT TO SECTION 6.28 OF THE ENVIRONMENTAL PLANNING AND ASSESSMENT ACT 1979)

(15) STRUCTURAL CERTIFICATION FOR EXISTING BUILDING – ALTERATIONS AND ADDITIONS

A qualified practising registered structural engineer must provide structural certification to the Registered Certifier verifying that the existing structure can adequately support the proposed new loads and the structural design complies with the Structural Provisions of the *Building Code of Australia* prior to certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979). The proposed additional loads and/or alterations must not cause a decrease in the existing structural performance of the building including its performance under earthquake actions (AS1170.4).

Reason

To ensure the existing structure can support the new loads.

(16) PHOTOGRAPHIC ARCHIVAL DOCUMENTATION (MINOR WORKS)

Prior to certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979), an archival photographic recording of the existing building,, front fence and site s to be prepared to Council's satisfaction. The recording is to be in digital form and prepared in accordance with the NSW Heritage Division guidelines titled "Photographic Recording of Heritage Items using Film or Digital Capture". One copy of the record is to be submitted to Council to be lodged with Council's Archives.

The form of the recording is to be as follows:

- (a) The Development Application number must be noted on the submitted information.
- (b) Include a summary report detailing the project description, date and authorship of the photographic record, method of documentation and limitations of the photographic record.
- (c) Include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive licence to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.
- (d) The report is to be submitted on a USB or digital file transfer in PDF/A format, (created directly from the digital original), with the digital catalogue of images

containing the following data for each location, image subject/description and date.

- (e) The electronic images are to be taken with a minimum 8 megapixel camera, saved as JPEG TIFF or PDF files with a size of approximately 4-6MB, and cross referenced to the digital catalogue sheets and base plans. Choose only images that are necessary to document the process and avoid duplicate images.

Reason

To ensure appropriate archival documentation of the building.

(17) HERITAGE CONSERVATION WORKS

- (a) The Conservation works outlined in the Schedule of Conservation Works to the existing building and front fence, prepared by Cracknell and Lonergan dated 27 May 2024 are to be implemented to the satisfaction of Council's Area Planning Manager prior to occupation or use. The only exception to the schedule, is that all news doors to the rooms off the central hallway are to be four panelled timber doors typical of the style and period of the cottage
- (b) The conservation works are to be based on documentary and physical evidence and where these are not available based on typical details of the style and period of the villa.

Reason

To ensure the carrying out of appropriate conservation works.

(18) USE OF HERITAGE CONSULTANT

- (a) An experienced heritage consultant, with experienced in the conservation of Victorian buildings, is to be commissioned to work with the consultant team throughout the design development, contract documentation and construction stages of the project. The conservation architect is to be involved in the resolution of all matters where existing significant fabric and spaces are to be subject to preservation, restoration, reconstruction, adaptive reuse, recording and demolition. The heritage consultant is to be provided with full access to the site and authorised by the applicant to respond directly to Council where information or clarification is required regarding the resolution of heritage issues throughout the project.
- (b) The heritage consultant is to inspect and advise on managing the implementation of the heritage conditions of the approval during the programme of works
- (c) Evidence and details of the above commission on the above terms are to be provided to Council prior to certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979) or commencement of work on site whichever is the earlier.
- (d) The heritage consultant must sign off the completed project and submit a final report for approval by Council's Area Planning Manager, prior to occupation or use. This report is to specify how the heritage conditions are

satisfied, and outline the heritage advice given throughout the project, the decisions made during the project on heritage matters and on the completed works.

Reason

To ensure that the implementation of the approved development is carried out in a manner that does not have adverse heritage impacts.

(19) PUBLIC DOMAIN LEVELS AND GRADIENTS - MAJOR

Prior to certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979), a Public Domain Levels and Gradients submission for the building and site frontages must be submitted to and approved by the City's Public Domain Unit. The submission must be prepared in accordance with the City's *Public Domain Manual* and submitted with a completed Application for *Public Domain Levels and Gradients*. Information on how to complete the submission can be downloaded from the City's website at <https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

Any requirements to comply with Disability Discrimination Act at the entrance to a building or publicly accessible space must be resolved inside the site boundary.

Note: Public Domain Levels and Gradient plans are to be included with the Public Domain Plan – Detailed Documentation for Construction condition submission.

Reason

To ensure public domain levels and gradients comply with Council's requirements.

(20) STORMWATER DRAINAGE DESIGN

Prior to certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979) a detailed stormwater management plan prepared by suitably qualified and experienced professionals must be submitted to and approved by the City's Public Domain Unit. The plan must be submitted with an Application for Approval of Stormwater Drainage Design, together with an application fee in accordance with the City of Sydney's adopted Schedule of Fees and Charges. The submission must include;

A certified stormwater drainage design complying with:

- (i) Council's Sydney Streets Technical Specifications, Part A4 Drainage Design;
- (ii) Council's Sydney Streets Technical Specifications, Standard Drawings;
- (iii) Council's Sydney Streets Technical Specifications, Part B10: Stormwater Drainage Construction;
- (iv) Council's Stormwater Drainage Manual; and
- (v) All relevant Australian Standards.

This information is available for download from the City's website at <https://www.cityofsydney.nsw.gov.au/development/public-domain-works/da-associated-works>.

Note: A Deed of Agreement (Stormwater Deed) for all proposed connections to the City's drainage system, and a Positive Covenant for all OSD systems may be required prior to occupation or use.

Reason

To ensure stormwater drainage design complies with Council's requirements.

(21) STORMWATER ON-SITE DETENTION

The requirements of Sydney Water with regard to the on-site detention (OSD) of stormwater must be ascertained and complied with. Evidence of the approval must be submitted to Council prior to certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979) other than demolition.

Where an OSD is not required by Sydney Water one may still be required by the City.

Reason

To ensure the requirements of Sydney Water are complied with.

(22) DILAPIDATION REPORT - PUBLIC DOMAIN

Prior to an approval for demolition and preparatory works being granted or the certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979), whichever is earlier, a photographic recording of the public domain site frontages is to be prepared as described in the Public Domain Manual and submitted for approval by Council's Public Domain Unit. The City's *Public Domain Manual* is available for download from the City's website at <https://www.cityofsydney.nsw.gov.au/>

The submission is to include written confirmation, issued with the authority of both the applicant and the photographer that the City of Sydney is granted a perpetual non-exclusive license to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.

Reason

To establish and document the condition of the public domain for comparison as building work progresses and is completed.

(23) PUBLIC DOMAIN DAMAGE BOND

- (a) A Public Domain Damage Deposit calculated on the basis of 44 square metres of concrete unit pavers along Glebe Point Road site frontage and 8 square metres of asphalt along Derwent Lane site frontage must be lodged with the City in accordance with the City of Sydney's adopted Schedule of

Fees and Charges. The bond must be provided as security for repairing any damage to the public domain in the vicinity of the site.

- (b) The City's Public Domain Unit must be contacted to determine the bond amount prior to lodgement. The Bond must be lodged with the City prior to an approval for demolition being granted or certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979), whichever is earlier.
- (c) The bond in this condition will be released in full when the occupation or use has commenced and any rectification works to the footway and Public Domain are completed to Council's satisfaction. If rectification works are required the City will release 90% of the total Bond, with the remaining 10% balance to be held for the duration of a 6 months Defect Liability Period.

Reason

To allow for the appropriate management and rectification of damage to the public domain.

(24) PROTECTION OF STONE KERBS

- (a) The existing stone kerbs on the Glebe Point Road and Derwent Lane frontages of the site are to be retained and properly protected during demolition, excavation and construction works.
- (b) To avoid damage to stone kerbs during excavation and construction works for the development, temporary removal and storage of the stone kerbs may be approved by Council. Removed, serviceable stone kerbs (i.e. those that are in good condition as agreed by Council officers) must be re-installed in accordance with the City of Sydney's standard details and specifications after the construction works have been completed. A temporary concrete kerb will need to be constructed to retain the footpath until the stone kerbs can be reinstalled.
- (c) Note the following:
 - (i) all costs associated with the works are to be borne by the developer.
 - (ii) Damaged kerbs are to be replaced to match existing to Council's satisfaction or as otherwise advised by Council officers.
 - (iii) Where new vehicle crossings or temporary crossings are to be constructed to access the property, the affected kerb stones should be salvaged and reused wherever possible.
 - (iv) All new driveway laybacks and kerbs are to be constructed with stone kerbs to match existing stones or as specified by City officers.
 - (v) Council approval is required before kerbs are removed.
 - (vi) Council approval is required prior to the cutting of existing stone kerbs for stormwater kerb outlets.

- (vii) Stone kerbs and gutters may be bonded in accordance with the City of Sydney's adopted Schedule of Fees and Charges. If so, this will be included with the Public Domain Damage Bond.

Reason

To ensure the protection of stone kerbs.

(25) SITE SUPERVISION AND REPORTING

- (a) An arborist with minimum AQF Level 5 qualification in arboriculture must oversee various stages of work within the Tree Protection Zone of any tree listed for retention. The Arborist must certify compliance with each key milestone detailed below:
 - (i) The installation of tree protection measures prior to the commencement of any construction works;
 - (ii) During demolition of any ground surface materials (pavers, concrete, grass etc.) within the Tree Protection Zone (TPZ) of any tree to be retained;
 - (iii) During construction of the specify structure/deck/concrete slab etc);
 - (iv) During any excavation and trenching within the TPZ which has been approved by Council;
 - (v) During any landscape works within the TPZ which has been approved by Council.
- (b) An Arboricultural Compliance Report which includes photographic evidence and provides details on the health and structure of tree/s must be submitted to and approved by Council's Area Planning Coordinator | Area Planning Manager at each hold point listed below:
 - (i) Certification that tree protection measures have been installed in accordance with these consent conditions;
 - (ii) Certification of compliance with each key milestone listed above within 48 hours of completion;
 - (ii) Details of any other works undertaken on any tree to be retained or any works within the TPZ which has been approved by Council.
- (c) Evidence A final compliance report must be submitted to and approved by Council's Area Planning Coordinator | Area Planning Manager prior to occupation or use.

Reason

To ensure the protection and ongoing health of trees on the site.

(26) WASTE AND RECYCLING MANAGEMENT

- (a) The Waste and Recycling Management Plan accompanying this Development Application has been approved by this consent (Council Reference 2023/581076).

Reason

To ensure that waste and recycling is appropriately managed.

(27) SYDNEY WATER CERTIFICATE (TAP-IN)

- (a) The approved plans must be submitted to Sydney Water's "Tap-in" online service to determine whether the development will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. Sydney Water's "Tap-in" online service is available at www.sydneywater.com.au, (see Plumbing, Building & Development and then Sydney Water "Tap-in").
- (b) The Consent Authority or a Principal Certifier must ensure that Sydney Water has appropriately stamped the plans prior to certification being issued (pursuant to Section 6.28 of the Environmental Planning and Assessment Act 1979).

Note: Sydney water recommends developers apply for a Building Plan Approval early as to reduce unnecessary delays to further referrals or development timescales.

Reason

To ensure the development satisfies Sydney Waters requirements.

(28) TREE PLANTING (SYDNEY WATER)

Certain tree species placed in proximity to Sydney Water's underground assets have the potential to inflict damage through invasive root penetration and soil destabilisation. Section 46 of the Sydney Water Act specifies what might occur when there is interference or damage to our assets caused by trees.

For any trees proposed or planted that may cause destruction of, damage to or interference with our work and are in breach of the Sydney Water Act 1994, Sydney Water may issue an order to remove that tree or directly remove it and seek recovery for all loss and associated compensation for the removal.

For guidance on types of trees that can cause damage or interference with our assets see Sydney Water webpage Wastewater blockages. For guidance on how to plant trees near our assets, see Diagram 5 – Planting Trees within Sydney Water's Technical guidelines – Building over and adjacent to pipe assets.

Reason

To ensure the development satisfies Sydney Waters requirements.

BEFORE BUILDING WORK COMMENCES

(29) TREE PROTECTION ZONE

- (a) Before the commencement of works, Tree Protection Zone/s (TPZ) must be established around all trees to be retained not less than the distance indicated in the TPZ schedule below.
- (b) Tree protection must be installed and maintained in accordance with the Australian Standard 4970 Protection of Trees on Development Sites and with the following schedule:

TPZ Schedule

Tree No.	Species Name	Location	Radius (m) From Trunk
1	Jacaranda mimosifolia (Jacaranda)	Neighbouring property - Rear southern boundary corner	5.4
3	Magnolia grandiflora (Southern Bay Magnolia)	Front Yard - form part of front gardens	5.4
9	Populus simonii (Simon's Poplar)	Street tree - front	2.0

Note: The work within the TPZ and installation of tree protection measures is only applicable within the subject development site and the public domain.

- (b) Ground surface protection must be installed if construction access is required through any TPZ where the existing ground surface material is not a hard surface or paving. The ground protection must be:
 - (i) Protected with boarding (ie scaffolding board or plywood sheeting or similar material), placed over a layer of mulch to a depth of at least 75mm and geotextile fabric;
 - (ii) The protective boarding must be left in place for the duration of the construction and development.
- (e) The following works must be excluded from within any TPZs:
 - (i) Excavation except for the localised siting of piers / demolition of the concrete slab;
 - (ii) Soil cut or fill including trenching;
 - (iii) Soil cultivation, disturbance or compaction;

- (iv) Stockpiling, storage or mixing of materials;
 - (v) The parking (except existing on street parking), storing, washing and repairing of tools, equipment and machinery;
 - (vi) The disposal of liquids and refuelling;
 - (vii) The disposal of building materials;
 - (viii) The siting of offices or sheds;
 - (ix) Any action leading to the impact on tree health or structure.
- (f) Any trenching works for services / hydraulics / drainage etc must not be undertaken within any TPZ. Alternative installation methods for services, such as directional boring/drilling, or redirection of services must be employed.
- (g) All work undertaken within or above the TPZ must be:
- (i) Carried out in accordance with a work methodology statement prepared by an Arborist with a minimum AQF Level 5 qualification in arboriculture and written approval is obtained from Council's Tree Management Officer before its implementation; and
 - (ii) Supervised by a Project Arborist with a minimum AQF Level 5 qualification in arboriculture.

Reason

To ensure the protection and ongoing health of trees.

(30) DILAPIDATION REPORT – MINOR

Subject to the receipt of permission of the affected landowner, dilapidation report/s of adjoining buildings are to be prepared by an appropriately qualified practising structural engineer and submitted for the approval of the Registered Certifier prior to the issue of a construction certification.

Reason

To ensure that dilapidation reports are prepared and to identify damage to for adjoining/nearby properties resulting from building work on the development site.

DURING BUILDING WORK

(31) HOURS OF WORK AND NOISE – OUTSIDE CBD

The hours of construction and work on the development must be as follows:

- (a) All work, including building/demolition and excavation work, and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (eg. loading and unloading of goods, transferring of

tools etc) in connection with the proposed development must only be carried out between the hours of 7.30am and 5.30pm on Mondays to Fridays, inclusive, and 7.30am and 3.30pm on Saturdays, with safety inspections being permitted at 7.00am on work days, and no work must be carried out on Sundays or public holidays.

- (b) All work, including demolition, excavation and building work must comply with the City of Sydney Code of Practice for Construction Hours/Noise 1992 and Australian Standard 2436 - 2010 Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- (c) Notwithstanding the above, the use of a crane for special operations, including the delivery of materials, hoisting of plant and equipment and erection and dismantling of on-site tower cranes which warrant the on-street use of mobile cranes outside of above hours can occur, subject to a separate application being submitted to and approved by Council under Section 68 of the Local Government Act 1993 and Sections 138/139 of the Roads Act 1993.

Note: Works may be undertaken outside of hours, where it is required to avoid the loss of life, damage to property, to prevent environmental harm and/or to avoid structural damage to the building. Written approval must be given by the Construction Regulation Team, prior to works proceeding.

The *City of Sydney Code of Practice for Construction Hours/Noise 1992* allows extended working hours subject to the approval of an application in accordance with the Code and under Section 4.55 of the *Environmental Planning and Assessment Act 1979*.

Reason

To protect the amenity of the surrounding area.

(32) COMPLIANCE WITH NATIONAL CONSTRUCTION CODE

All proposed work must comply with the *National Construction Code (previously known as Building Code of Australia)*.

Reason

(Prescribed condition - EP&A Regulation 2021 clause 69(1)).

(33) ASBESTOS REMOVAL WORKS

- (a) All works removing asbestos containing materials must be carried out by a suitably licensed asbestos removalist duly licensed with Safework NSW, holding either a Friable (Class A) or a Non-Friable (Class B) Asbestos Removal Licence which ever applies.

A copy of the relevant licence must be made available to any authorised Council officer on request within 24 hours.

- (b) Five days prior to the commencement of licensed asbestos removal, Safework NSW must be formally notified of the works. All adjoining properties and those opposite the development must be notified in writing of

the dates and times when asbestos removal is to be conducted. The notification must identify the licensed asbestos removal contractor and include a contact person for the site together with telephone number and email address.

- (c) All work must be carried out in accordance with the *Work Health and Safety Regulation 2017* and the NSW Government and SafeWork NSW document entitled *How to manage and control asbestos in the work place: Code of Practice (Safework NSW) December 2011* and the *City of Sydney Managing Asbestos Policy dated 21 October 2013 and associated guidelines*.
- (d) The asbestos removalist must use signs and barricades to clearly indicate the area where the asbestos removal work is being performed. Signs must be placed in positions so that people are aware of where the asbestos removal work area is and should remain in place until removal is completed and clearance to reoccupy has been granted. Responsibilities for the security and safety of the asbestos removal site and removal must be specified in the asbestos removal control plan (where required). This includes inaccessible areas that are likely to contain asbestos.
- (e) Warning signs must be placed so they inform all people nearby that asbestos removal work is taking place in the area. Signs must be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs must be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs must be in accordance with AS 1319 -1994 *Safety Signs for the Occupational Environment* for size, illumination, location and maintenance.
- (f) Asbestos waste must only be transported and disposed of at an EPA licensed waste facility.
- (g) No asbestos products are to be reused on the site (i.e. packing pieces, spacers, formwork or fill etc).
- (h) No asbestos laden skips or bins are to be left in any public place without the written approval of Council.
- (i) A site notice board must be located at the main entrance to the site in a prominent position and must have minimum dimensions of 841mm x 594mm (A1) with any text on the notice to be a minimum of 30 point type size.

The site notice board must include the following:

- (i) contact person for the site;
- (ii) telephone and facsimile numbers and email address; and
- (iii) site activities and time frames.

Reason

To ensure that the handling and removal of asbestos from the site is appropriately managed.

(34) EROSION AND SEDIMENT CONTROL - LESS THAN 250SQM

Where less than 250 square metres are being disturbed, no formal plan is required however, the site is to be provided with sediment control measures and these must be implemented so that sediment, including soil, excavated material, building material or other materials cannot fall, descend, percolate, be pumped, drained, washed or allowed to flow to the street, stormwater system or waterways.

Reason

To ensure that appropriate erosion and sediment control measures are put in place during construction to protect the environment.

(35) DISCHARGE OF CONTAMINATED GROUNDWATER

Contaminated groundwater must not be discharged into the City's stormwater drainage system.

Options for the disposal of groundwater include disposal to sewer with prior approval from Sydney Water or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

Reason

To ensure that the discharge of ground water is appropriately managed.

(36) SURVEY

All footings, walls and floor slabs adjacent to a boundary must be set out by a registered surveyor. On commencement of brickwork or wall construction a survey and report, prepared by a Registered Surveyor, must be submitted to the Principal Certifier indicating the position of external walls in relation to the boundaries of the allotment. Any encroachments by the subject building over adjoining boundaries or roads must be removed prior to continuation of building construction work.

Reason

To ensure the development does not encroach onto neighbouring properties.

(37) COVERING OF LOADS

All vehicles involved in the excavation and/or demolition process and departing the property with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.

Reason

To ensure loads are managed appropriately and do not impact local amenity.

(38) VEHICLE CLEANSING

Prior to the commencement of work, suitable measures are to be implemented to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site. It is an offence to allow, permit or cause materials to pollute or be placed in a position from which they may pollute waters.

Reason

To ensure sediment is not tracked onto the roadway.

(39) DRAINAGE AND SERVICE PIT LIDS

All existing or proposed drainage and service pit lids throughout the public domain must be to City of Sydney specifications and heel/bicycle safe, slip resistant, infill with material to match surrounding surface, finished flush with the adjacent pavement to avoid trip hazards and be clear of obstructions for easy opening and cleaning. Infill pit lids are to be detailed where specified by Council's Public Domain Officer. Private pits are not permitted within the public domain. All details of pit lids must be shown on the public domain plan and must be approved by the City's Public Domain Unit prior to the issue of an approval for public domain works.

Reason

To ensure drainage and service pit lids within the public domain are appropriately designed and installed.

(40) COMPLIANCE WITH ARBORIST'S REPORT

- (a) All recommendations Tree Protection Plans and Methodology Statements contained in the approved Arboricultural Impact Assessment Report prepared by Blues Bros, dated 5 May 2023, and report addendums 1 & 2 dated 23 November 2023 and 29 April 2024, must be implemented during the demolition, construction and use of the development.

Reason

To ensure that works affecting trees are carried out in an appropriate manner and in accordance with the approved arborist's report.

(41) STREET TREE PROTECTION

All street trees located directly outside the site must be retained and protected in accordance with the Australian Standard 4970 Protection of Trees on Development Sites. All street trees must be protected during the construction works as follows:

- (a) Tree trunk and major branch protection must be undertaken prior to the commencement of any works (including demolition). The protection must be installed and certified by an arborist with a minimum AQF Level 5 qualification in arboriculture and must include:
 - (i) An adequate clearance, minimum 250mm, must be provided between the structure and tree branches, and trucks at all times.
 - (ii) Tree trunk/s and/or major branches to a height of two metres must be protected by wrapped thick underlay carpet or similar padding material to limit damage, and
 - (iii) Timber planks (50mm x 100mm or similar) must be placed around tree trunk/s. The timber planks must be spaced at 100mm intervals and must be fixed against the trunk with tie wire, or strapping. The thick

underlay carpet or similar padding material and timber planks must not be fixed to the tree in any instance, or in any fashion.

- (iv) Tree trunk and major branch protection is to remain in place for the duration of construction and development works and must be removed at the completion of the project.
- (b) Temporary signs, or any other items, shall not be fixed or attached to any street tree.
- (c) All hoarding support columns are to be placed a minimum of 300mm from the edge of the existing tree pits/setts, so that no sinking or damage occurs to the existing tree pits. Supporting columns must not be placed on any tree roots that are exposed.
- (d) Young street trees must be protected by installing three (3) wooden stakes around the edge of the tree pits or a minimum of 1 metre from the base of the trunk. Hessian must be wrapped around the stakes. If existing stakes or a metal tree guard are already in place, these suffice as tree protection.
- (e) Materials or goods, including site sheds, must not be stored or placed:
 - (i) around or under the tree canopy; or
 - (ii) within two (2) metres of tree trunks or branches of any street trees.
- (f) Any excavation within any area known to or suspected of having tree roots greater than 30mm diameter must be undertaken by hand.
- (g) Any trenching works for services, hydraulics, drainage etc. must not be undertaken within [specify] metres of the trunk of any street tree. Alternate installation methods for services such as directional boring/drilling or redirection of services must be employed where roots greater than 30mm diameter are encountered during installation of any services.
- (h) Existing sections of kerbs adjacent to any street tree must not be removed without approval from the Council's Tree Management Officer.
- (i) Any damage sustained to street tree/s as a result of the erection of any construction activities (including demolition) must be immediately reported to the Council's Tree Management Officer on 9265 9333. Any damage to street trees as a result of any construction activities may result in prosecution under the Local Government Act 1993 and the Environmental Planning and Assessment Act 1979.

Reason

To ensure the protection and ongoing health of the street trees.

(42) PROTECTION OF NATIVE WILDLIFE

- (a) In the event that wildlife is found during the course of tree removal works, work must stop until a trained wildlife handler attends the site or the animal relocates itself. In regards to tree pruning, works may only proceed if the animals will not come into direct harm.

- (b) In the event that the tree has nesting birds or native animals, works must be delayed until after the nesting period has been completed, unless in the event of an emergency.

Reason

To ensure that wildlife is adequately protected during tree removal/pruning works.

(43) NO OBSTRUCTION OF PUBLIC WAY

Unless otherwise approved by Council, the public way must not be obstructed by any materials, vehicles, waste receptacles, skip-bins or the like. Non-compliance with this requirement may result in the issue of a notice by Council to stop all work on the site.

Reason

To protect the amenity of the public domain.

PRIOR TO OCCUPATION OR USE

(44) SYDNEY WATER CERTIFICATE

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Coordinator. Please refer to the Building Developing and Plumbing section on the web site www.sydneywater.com.au then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Coordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

The Section 73 Certificate must be submitted to Council or the Principal Certifier prior to occupation or use.

Reason

To ensure the requirements of Sydney Water are met.

(45) STORMWATER DRAINAGE CONNECTION

Detailed stormwater drainage connection works approved by the City's Public Domain Unit must be constructed prior to occupation or use.

Reason

To ensure approval of connection into the Council's drainage system is sought.

(46) COMPLIANCE WITH HAZARDOUS MATERIALS SURVEY REPORT

All of the recommendations for management and/or removal of hazardous materials on the site, as outlined in the Hazardous Materials Survey Report (prepared by Hazmat, Ref. 2023/581093, dated 4 March 2022), as approved must be complied with.

Prior to occupation or use, certification must be submitted to the Principal Certifier from a certified Occupational Hygienist (*Australia Institute of Occupational Hygienists*) confirming that all hazardous materials identified have been contained, managed or removed in accordance with the recommendations given in the approved Hazardous Materials Survey Report and that the site is safe for future occupation in accordance with the approved use.

Reason

To ensure that hazardous materials on the site are appropriately managed.

(47) BASIX

All commitments listed in each relevant BASIX Certificate for the development must be fulfilled prior to occupation or use being issued.

Reason

To ensure BASIX commitments are fulfilled in accordance with the BASIX certificate (prescribed condition under clause 75 EP&A Regulation 2021).

(48) SURVEY CERTIFICATE AT COMPLETION

A Survey Certificate prepared by a Registered Surveyor must be submitted to the Principal Certifier at the completion of the building work certifying the location of the building in relation to the boundaries of the allotment.

Reason

To ensure the development does not encroach onto neighbouring properties.

(49) STORMWATER COMPLETION DEED OF AGREEMENT AND POSITIVE COVENANT

Prior to occupation or use:

- (a) The Owner is required to enter into a Deed of Agreement (Stormwater Deed) with the City of Sydney and obtain registration of Title of a Positive Covenant for all proposed connections to the City's underground drainage system. The deed and positive covenant will contain terms reasonably required by the City and will be drafted by the City's Legal Services Unit at the cost of the applicant, in accordance with the City's Fees and Charges.
- (b) A Positive Covenant must be registered on the property title for all drainage systems involving On-Site Detention (OSD) to ensure maintenance of the approved OSD system regardless of the method of connection. The positive covenant will contain terms reasonably required by the City and will be

drafted by the City's solicitor at the cost of the applicant, in accordance with the City's Fees and Charges.

Reason

To protect underground drainage system.

OCCUPATION AND ONGOING USE

(50) ENCROACHMENTS – NEIGHBOURING PROPERTIES

No portion of the proposed structure shall encroach onto the adjoining properties.

Reason

To protect neighbouring properties.

(51) ENCROACHMENTS – PUBLIC WAY

No portion of the proposed structure, including downpipes, gutters, gates and doors during opening and closing operations, shall encroach upon Council's footpath area.

Reason

To protect the public way.

(52) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS

All works to the City's public domain, including rectification of identified defects, are subject to a 6 month defects liability period from the date of Completion. The date of Completion will be nominated by Council on the Public Domain Works – Letter of Completion Operational Acceptance.

Reason

To ensure all works to the City's public domain are protected under a liability period.

(53) WASTE AND RECYCLING MANAGEMENT

Residential waste storage and collection arrangements must be conducted in accordance with the City's Local Approvals Policy for waste bins to be stored on site at all times and only presented on the street for scheduled collection times.

Reason

To keep waste bins off the street