

# Traffic Control Guidance Plan

**Project:** Green Square Market

**Comments:** This Traffic Control Guidance Plan is prepared as a guide only and is not to scale. The positions of the signs and all traffic controllers and all equipment are only suggested guide only and may require changes on site.

**Author:** Seede Marzouk, Lic No TCT 0064782

**Date:** 30/10/2024

**Client:** Cambridge Markets

**Address:** 355 Botany Road, Zetland NSW 2017

**Scope Of Works:** Green Square Christmas Market

**Traffic Management:** Authorised Traffic Controllers to Conduct all traffic movements

**Schedule Of Works:** Dec 2024

**Compliance:** All required permits RMS/Council/pollce to be in hand before works commence. This TCP is drawn in accordance with AS1742.3 and RMS TCAMS Manual.

**Traffic Management:**

- Stop Slow
- Lane Merge
- Contra Flow
- Diversions
- Road Closure
- Pedestrian Management
- Interimment Works

**Road Classification:**

- State
- Regional Council or RMS
- Council

Speed Limit (km/h)	Sign (Overhead or on sign)	Sign Code	Sign Size	Sign Spacing
30	Speed Limit	511	1200	100m
40	Speed Limit	512	1200	100m
50	Speed Limit	513	1200	100m
60	Speed Limit	514	1200	100m
70	Speed Limit	515	1200	100m
80	Speed Limit	516	1200	100m
90	Speed Limit	517	1200	100m
100	Speed Limit	518	1200	100m

- All Traffic Control works signs and devices conducted on site are to comply with Australian Standard AS1742.3 and TCAMS.
- Any amendments to this Traffic Control Plan may only be made by a person holding the appropriate RMS tickets to do so.
- All traffic control devices may only be set out by a person holding the appropriate RMS accreditation.
- All traffic personnel on site must hold the appropriate RMS accreditation required.
- All signs must be erected in a manner that would not create a hazard to pedestrians and must be visible to motorists at all times.
- Regular inspections of the signs must be conducted to ensure they are still in the correct position, and must be visible to motorists at all times.
- Traffic Controllers must be provided with breaks every two hours by a suitably qualified person to comply with Australian Standards and WH&S Act 2011.
- Site supervisor to conduct toolbox talk and ensure that all personnel are familiar with the traffic control SWMS and that all safety issues are correctly addressed. Further a risk assessment must be conducted before commencement of works.
- In the event of an incident/incident reports must be completed immediately.

**Authorised and Licensed Traffic Controllers** and/or suitably qualified site personnel to conduct any stop slow controls if required and where permit is obtained for any task to be conducted across pedestrian or vehicular paths. This TCP is to be used for any such activity where works involve the road and/or the footpath if necessary.

**Pavement Works**  
Road works.  
Concrete Pours  
Cement Work

Any and all works on pavement or road are the subject of individual approval of City Of Sydney Council